

MAINLINE														
LOCATION	LENGTH	AREA (MAINLINE)	AREA (PARKING LANES)	LEV BINDER (MM) 3/4"	LEV BINDER (HM)	MIX CRACK JTS & FLGWYS	AGG PR CT	TEMP RAMP	BIT MAT'LS PR CT	HMA SURF CSE 1 1/2"	AGG SHLD TYPE B			
LOG MILE	FT	SQ. YD.	SQ. YD.	TON	TON	TON	TON	SQ YD	GAL	TON	TON			
0 TO 0.98	5174	13798	8049	579.5	6.9	4.1	30.4	16.0	1976.8	1835.2				
0.98 TO 1.08	528	1408	411	59.1	0.7	0.4	2.8	16.0	183.0	152.8	10.0			
SIDEROAD & ENTRANCES														
TOTALS														
							657.8	7.6	4.6	35.8	152.0	2261.9	2047.6	12.0

SIDEROAD AND ENTRANCE SCHEDULE							
LOCATION	DESCRIPTION	TOTAL AREA	HMA SURF REMOVAL BUTT JOINT	BIT MAT'L PR CT	TEMP RAMP	AGG PR CT	INCIDENTAL HMA SURFACING
LOG MILE		SQ YD	SQ YD	GALLON	SQ YD	TON	TON
0.02	YERK STREET (RT)	80	80	6.40	8.00	0.16	6.7
0.04	GASOLINE ALLEY	80.0	80.00	6.40	8.00	0.16	6.7
0.19	ROSS STREET (LT & RT)	160.0	160.00	12.80	8.00	0.32	13.4
0.29	WALNUT GROVE (LT)	80.0	80.00	6.40	8.00	0.16	6.7
0.33	2ND STR. (LT & RT)	160.0	160.00	12.80	16.00	0.32	13.4
0.40	S MAIN (LT & RT)	160.0	160.00	12.80	16.00	0.32	13.4
0.47	FOURTH ST (LT & RT)	160.0	160.00	12.80	16.00	0.32	13.4
0.57	CR 6 (LT & RT)	160.0	160.00	12.80	16.00	0.32	13.4
0.72	RODNEY (RT & LT)	160.0	160.00	12.80	16.00	0.32	13.4
1.03	VALLEY VIEW (LT)	80.0	80.00	6.40	8.00	0.16	6.7
TOTAL		1280.0	1280.0	102.4	120.0	2.6	107.5

HMA SURFACE REMOVAL					
LOCATION	LENGTH	AREA (MAINLINE)	AREA (PARKING LANE)	HMA SURF REM 1 1/2"	HMA SURF REM 3/4"
LOG MILE	FT	SQ. YD.	SQ YD	SQ YD	SQ YD
0 TO 0.98	5174	13798	8049	13798.4	8049.1
0.98 TO 1.08	528	1408	411	1408.0	410.7
TOTALS				15206.4	8459.7

PAVEMENT MARKING SCHEDULE								
LOCATION	THERMO PVT MK 4"	THERMO PVT MK 6"	RAISED REFL PVT	RAISED REFL PVT	SH TERM PVT	WK ZN PVT MK	TEMP PVT MK 4"	TEMP PVT MK 6"
LOG MILE	WHITE	YELLOW	EACH	EACH	FT	SQ FT	FT	FT
0.00 TO 1.08	11,405	1,426	71	71	1,711	190	11,405	1,426
TOTAL	11,405	1,426	71	71	1,711	190	11,405	1,426

SIDEWALK				
STREET	NUMBER OF RAMPS	DETECTABLE WARNINGS	SIDEWALK REMOVAL	PCC SIDEWALK 4"
		SQ FT	SQ FT	SQ FT
WALNUT GROVE				
NE QUAD	1	8	20	12
NW QUAD	1	8	20	12
2ND STREET				
NE QUAD	1	8	20	12
NW QUAD	1	8	20	12
SE QUAD	1	8	20	12
MAIN STREET				
NE QUAD	2	16	40	24
NW QUAD	2	16	40	24
SE QUAD	2	16	40	24
SW QUAD	2	16	40	24
4TH STREET				
NE QUAD	2	16	40	24
NW QUAD	2	16	40	24
SE QUAD	2	16	40	24
SW QUAD	2	16	40	24
5TH STREET				
NE QUAD	1	8	20	12
NW QUAD	0	NO WORK		
SE QUAD	1	8	20	12
SW QUAD	1	8	20	12
RODNEY STREET				
NE QUAD	1	8	20	12
NW QUAD	1	8	20	12
SE QUAD	2	16	40	24
SW QUAD	2	16	40	24
TOTAL		240	600	360

MANHOLE AND WATER VALVE ADJUSTMENTS		
LOCATION	MANHOLES TO BE ADJUSTED	WATER VALVES TO BE ADJUSTED
LOG MILE	EACH	EACH
0.00 TO 1.08 Throughout project)	1	12
TOTAL	1	12