

SIDEROADS, ENTRANCES & MAILBOX TURNOUT

LOCATION		LENGTH (AVERAGE)	WIDTH	AREA	SAW CUTS	HMA SURF. REMOVAL VAR. DEPTH	POLY. BIT. PRIME COAT	AGG PRIME COAT	HMA SURF. CSE, MIX "D" N50	HMA BASE COURSE 6"	HMA CONC. SURF. CSE, MIX "C" PAID AS INCIDENTAL HMA SURFACING
SIDEROADS		FOOT	FOOT	SQ. YD.	FOOT	SQ. YD.	TON	TON	TON	SQ. YD.	TON
RT. 80+52	AYRSHIRE RD. (E300)	47.4	3	15.80			0.003		1.55		
RT. 107+36	MAIN GATE RD. (E350)	35.6	14.4	56.88	20.8	56.88	0.02				4.78
LT. 107+36	MAIN GATE RD. (E350)	41.0	17.5	79.72	30	79.72	0.03				6.70
RT. 161+17	CAMP ELLIS (E450)	41.0	3	13.65			0.003		1.34		
LT. 161+17	CAMP ELLIS (E450)	30.3	28	94.11	19.2	94.11	0.04				7.91
LT. 171+19	DOBBINS (N1150)	57.4	24.8	158.03	33	158.03	0.06				13.27
RT. 194+00	CO. HWY 12 (E500)	56.0	33	205.33	32.5	205.33	0.08				17.25
RT. 247+62	PLANT (E 800)	42.4	30.8	145.10	20.6	145.10	0.06				12.19
RT. 261+49	BERNODETTE ST.	28.3	3	9.43			0.002		0.92		
LT. 261+49	BERNODETTE ST.	33.4	22.2	82.39	21.8	82.39	0.03				6.92
RT. 265+67	MILLS ST.	39.5	3	13.17			0.003		1.29		
LT. 265+67	MILLS ST.	35.0	3	11.65			0.002		1.14		
RT. 267+81	MARKET ST.	44.0	3	14.65			0.003		1.44		
LT. 267+81	MARKET ST.	36.2	3	12.07			0.002		1.18		
RT. 270+00	FULTON ST.	33.8	18.6	69.85	27.7	69.85	0.03				5.87
LT. 270+00	FULTON ST.	30.3	3	10.10			0.002		0.99		
RT. 272+11	ORCHARD ST.	25.0	3	8.33			0.002		0.82		
LT. 272+11	ORCHARD ST.	28.0	3	9.33			0.002		0.91		
LT. 274+23	HOME ST.	36.9	3	12.28			0.002		1.20		
RT. 276+55	ST. JAMES ST.	29.9	3	9.97			0.002		0.98		
LT. 276+55	ST. JAMES ST.	28.7	3	9.55			0.002		0.94		
LT. 278+79	ST. MARY'S ST.	30.7	3	10.22			0.002		1.00		
LT. 280+28	ILLINOIS ST.	46.9	3	15.62			0.003		1.53		
RT. 282+43	COLFAX ST.	31.0	20.7	71.30	19.8	71.30	0.03				5.99
LT. 285+49	N. EAST ST.	41.3	3	13.75		13.75	0.003		1.35		
RT. 286+86	KINSEY ST.	33.3	8	29.60	30	29.60	0.01				2.49
RT. 289+86	EAST ST.	30.6	3	10.18		10.18	0.002		1.00		
RT. 293+63	VERA ST.	32.0	3	10.67		10.67	0.002		1.05		
RT. 302+10	CO. HWY 2 (E 700)	60.8	54	364.50	28.1	364.50	0.15				30.82
RT. 358+35	TATER CREEK (E 800)	34.3	29.6	112.64	18.3	112.64	0.05				9.46
LT. 358+35	TATER CREEK (E 800)	35.1	3	11.70		11.70	0.002		1.15		
LT. 412+00	LADDS (E 900)	48.0	3	15.98		15.98	0.003		1.57		
RT. 446+55	OTTER CREEK (E 950)	45.8	34.9	177.60	22	177.60	0.07				14.92
RT. 474+00	SUMMUN (E 1000)	36.1	3	12.03		12.03	0.002		1.18		
LT. 474+00	SUMMUN (E 1000)	25.4	28.5	80.43	14.8	80.43	0.03				6.76
		1310.7									
ENTRANCES & MAILBOX TURNOUTS											
3R SECTION											
LT. 479+55.16	C.E.	98.6	8	143.27	44.6					143.27	16.05
LT. 489+32.49	F.E.	86.4	8	64.00						64.00	7.17
RT. 501+08.75	F.E.			152.33	15.8					152.33	17.06
RT. 501+53.29	P.E. & M.T.									0.00	0.00
LT. 501+09.06	F.E.	84	8	63.86						63.86	7.15
RT. 38+83.92	P.E.	71	8	53.76						53.76	6.02
LT. 39+21.6	P.E.	84	8	63.90						63.90	7.16
RT. 53+65.15	P.E.	84	8	64.00						64.00	7.17
3P SECTION-EXISTING BIT. ENTRANCES											
RT. 237+60	F.E.	31.5	3	10.50	25	10.50			1.03		
LT. 248+86	P.E. & M.T.	38.8	3	12.93	30	12.93			1.27		
LT. 249+42	P.E.	39.9	3	13.30	30	13.30			1.30		
LT. 250+91	P.E.	39.1	3	13.03	30	13.03			1.28		
RT. 496+78	M.T.	60.7	3	20.23	50	20.23			1.98		
RT. 499+62	M.T.	52.3	3	17.43	45	17.43			1.71		
SHEET TOTAL					609	1889	0.7	0.0	33.1	605	213

SEE HMA TABLE FOR TOTAL QUANTITY

FILE NAME = ppoplanshts.dgn	USER NAME = ghdinoam	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	315	109RS-4,110RS-2	FULTON	13
		CHECKED -	REVISED -		CONTRACT NO. 68330									
		DATE -	REVISED -		ILLINOIS FED. AID PROJECT									