

SCHEDULE OF QUANTITIES

TOPSOIL FURNISH AND PLACE, 4"	
RT. STA. 140+53.00 TO 146+78.00	1890 SQ YD
TOTAL =	1890 SQYD

GRADING AND SHAPING DITCHES	
RT. STA. 141+35.00 TO 146+78.00	543 FOOT
TOTAL =	543 FOOT

CLASS C PATCHES, 13 INCH			
LOCATION	Type II	Type III	Type IV
PATCHING UNITS 1 WB (Sterling Ave. - Glen Hollow)	88.00 SQYD	72.00 SQYD	
PATCHING UNITS 2 WB (Glen Hollow - Sherwood Pl.)	32.00 SQYD		
PATCHING UNITS 3 WB (Sherwood Pl. - Mountello)	954.67 SQYD	80.00 SQYD	
PATCHING UNITS 4 WB (Mountello - Big Hollow)	1,120.00 SQYD	245.33 SQYD	
PATCHING UNITS 5 WB (Big Hollow - Frostwood)	168.00 SQYD		
PATCHING UNITS 1 EB (Sterling Ave. - Glen Hollow)	88.00 SQYD	21.33 SQYD	
PATCHING UNITS 2 EB (Glen Hollow - Sherwood Pl.)	226.67 SQYD		
PATCHING UNITS 3 EB (Sherwood Pl. - Mountello)	128.00 SQYD		
PATCHING UNITS 4 EB (Mountello - Big Hollow)	456.00 SQYD		26.67 SQYD
PATCHING UNITS 5 EB (Big Hollow - Frostwood)	136.00 SQYD		
TOTAL =	3,397.00 SQYD	451.00 SQYD	27.00 SQYD

LOCATION	PAY ITEMS				
	SEEDING CLASS 2A	MULCH, METHOD 2	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT
RT. STA. 140+53.00 TO 146+78.00	0.4 ACRE	0.4 ACRE	36 POUNDS	36 POUNDS	36 POUNDS
TOTAL =	0.4 ACRE	0.4 ACRE	36 POUNDS	36 POUNDS	36 POUNDS

DEFORMED BARS - EXPANTION JOINT	
LOCATION	QTY.
STA. 70+00	55.00 EACH
STA. 72+25	55.00 FOOT
TOTAL =	110.00 FOOT

CLASS B PATCHES, TYPE II, 10 INCH	
LT. STA. 60+78 TO LT. STA. 64+86 (Turn Lane)	136 SQYD
TOTAL =	136 SQYD

CLASS B PATCH - EXPANTION JOINT	
LOCATION	QTY.
STA. 70+00	62.00 FOOT
STA. 72+25	62.00 FOOT
TOTAL =	124.00 FOOT

SAW CUTS	
LT. STA. 60+78 TO LT. STA. 64+86 (Turn Lane)	816 FOOT
TOTAL =	816 FOOT

DOWEL BARS 1 1/2"	
LT. STA. 60+78 TO LT. STA. 64+86 (Turn Lane)	340 EACH
TOTAL =	340 EACH