

SCHEDULE OF QUANTITIES

TEMPORARY PAVEMENT MARKING											
STA.	TO	STA.	LENGTH (FT)	4" WHITE SOLID	4" YELLOW SOLID	6" WHITE SKIP	8" WHITE SOLID	12" WHITE SOLID	12" YELLOW SOLID	24" WHITE SOLID	LETTERS & SYMBOL
				(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(SQ FT)
				(LT/RT)	(LT/RT)	(LT/RT)	(LT/RT)	(LT/RT)	(LT/RT)	(LT/RT)	(LT/RT)
Eastbound - Mainline and Turnlanes											
37+94	TO	52+50	1,456	834	322	364	444		24	59	31
52+50	TO	67+50	1,500	1,358	2,031	375	536		261	48	94
67+50	TO	80+50	1,300	1,294	2,405	325	288		443		47
80+50	TO	95+00	1,450	1,186	1,949	363	317		240	35	62
95+00	TO	109+50	1,450	1,424	2,400	363	226		440		31
109+50	TO	122+50	1,300	923	1,671	325	1,076	87	27	46	125
122+50	TO	136+00	1,350	1,105	2,639	338	164	53			
136+00	TO	150+50	1,450	822	2,037	363	886	54	490	36	94
150+50	TO	161+86	1,136			284	964	118		40	125
Westbound - Mainline and Turnlanes											
37+94	TO	52+50	1,456	1,209	957	364			32	59	62
52+50	TO	67+50	1,500	1,312	2,031	375	640			36	62
67+50	TO	80+50	1,300	1,303	2,405	325	37				16
80+50	TO	95+00	1,450	1,219	1,963	363	488			35	78
95+00	TO	109+50	1,450	1,211	2,400	363	252				47
109+50	TO	122+50	1,300	1,061	1,672	325	1,146	87	116	47	140
122+50	TO	136+00	1,350	1,350	1,850	338	176		523		31
136+00	TO	150+50	1,450	1,221	2,034	363	431	81		45	47
150+50	TO	161+86	1,136	887		284	1,020		45	23	109
Sideroads											
Frostwood				350	500		443	143		46	
N. Bigelow				529			468	135		23	31
N. Willow Knolls Rd.							633	148		19	31
S. Barring Trace							174			20	
N. Barring Trace				0	0	0	0	0	0	0	0
S. Mountello Drive				231	92		404	143	15		
N. Mountello Drive				329	178		425	152	30		
W. Bacon Drive				284	324		421	147		28	
N. Allen Rd				85			271	64			62
W. Charter Oak Rd				45			387	105			
Cannes Drive					173		253	74	29	11	
W. Sherwood Place					235		274	118	17	12	
Glen Hollow Drive							145			27	
N. Rockwood Rd.							56	31			
W. Northland Ave.					98		183		37		
SUB-TOTAL				21,572	32,363	6,196	13,629	1,739	2,769	695	1,326
TOTAL				53,935	6,196	13,629	4,507	695	1,326		

SHORT - TERM PAVEMENT MARKING	
JOBSITE (2 APPLICATIONS)	36,936 FOOT

WORK ZONE PAVEMENT MARKING REMOVAL	
JOBSITE	6,156 SQFT