

SCHEDULE OF QUANTITIES

ROUTE		SECTION	COUNTY	SHEET	
F.A.	VAR	*	PEORIA	TOTAL	NO.
MKD.	US 150			100	18

***(108X,130,102)RS-3;129RS-4,101RS-2**

MATERIAL TRANSFER DEVICE	
LOCATION	TON
JOBSITE	3,741
TOTAL	3,741

MOWING	
LOCATION	UNIT
JOBSITE (1 APPLICATION)	159
TOTAL	159

EPOXY AND TEMPORARY PAINT PAVEMENT MARKINGS						
	LINE - 4"	LINE - 4"	LINE - 4"	LINE - 24"	LINE - 8"	LINE - 12"
LOCATION	YELLOW	YELLOW	WHITE	WHITE	WHITE	WHT/YLW
	SKIP	SOLID	SOLID	SOLID	SOLID	SOLID
	FEET	FEET	FEET	FEET	FEET	FEET
* Centerline/Edgeline						
STA 754+80.00 TO STA. 899+42.50	3615	800	28925			
STA. 899+42.50 TO STA. 907+42.50		1600	1600			
STA. 10+23.00 TO STA. 18+50.00		3955	1475	25	135	100
SEE PAVEMENT MARKING DETAILS						
TOTAL	3,615	6,355	32,000	25	135	100

The quantity shown represents one application of the epoxy pavement markings required
 The same quantity is required if temporary paint pavement markings are used
 *Locations shown are approximate. Field verify exact locations before milling.

CONSTRUCTING TEST STRIP	
LOCATION	EACH
JOBSITE	1
TOTAL	1