

# SUMMARY OF QUANTITIES

CONSTR. CODE  
PEORIA COUNTY  
100% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	
				J000	RURAL
55101200	STORM SEWER REMOVAL 24"	FOOT	8	8	
55101400	STORM SEWER REMOVAL 30"	FOOT	56	56	
60107700	PIPE UNDERDRAINS 6"	FOOT	1730	1730	
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	
60219200	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 10 FRAME AND GRATE	EACH	1	1	
60240305	INLETS, TYPE B, TYPE 10 FRAME AND GRATE	EACH	4	4	
60500040	REMOVING MANHOLES	EACH	3	3	
60500060	REMOVING INLETS	EACH	7	7	
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	7.7	7.7	
60602900	CONCRETE GUTTER, TYPE B (MODIFIED)	FOOT	1358	1358	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24'	FOOT	82	82	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	375	375	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MS	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	

\* Denotes Specialty Item.

**FOR INFORMATION ONLY**