

RESURFACING TABLE

Location	Length	Width	Area	HMA Surface Removal	Temporary Ramp	HMA Surface Removal	Polymerized Bituminous Materials	Aggregate Materials	HMA Surf Cse
				Butt Joint	Sq Yd	1 1/2"	(Prime Coat)	(Prime Coat)	Mix D N50
	Feet	Feet	Sq Yd	Sq Yd	Sq Yd	Sq Yd	Ton	Ton	Ton
IL 78									
653+86.00 TO 653+91.00	5	26	14.4	14.44	14.4		0.01	0	1.2
653+91.00 TO 654+50.00	59	26	170.4			170.4	0.07	0.3	14.3
PCC Pavement 10" Location			750						
662+00.00 TO 663+95.00	195	26	563.3			563.3	0.23	1.1	47.3
663+95.00 TO 664+00.00	5	26	14.4	14.44	14.4		0.01	0	1.2
<b>Total</b>	<b>1014</b>		<b>762.5</b>	<b>29</b>	<b>29</b>	<b>734</b>	<b>0.3</b>	<b>1.4</b>	<b>64</b>

SURFACE TYPE	BITUMINOUS PRIME COAT (GAL/SQ YD)	AGGREGATE PRIME COAT (LB/SQ YD)
ON COLD MILLED SURFACE	0.1	4
EXISTING PAVEMENT	0.05	4
FOG COAT ON NEW BINDER	0.03	2

0.004 TONS PER GALLON FOR BITUMINOUS PRIME COAT

SURFACE TYPE	
BITUMINOUS SURFACE COURSE	112 LB / SQ YD / IN
ALL OTHER BITUMINOUS	112 LB / SQ YD / IN
AGGREGATE SHOULDERS	2.05 TONS / CU YD

Guardrail Locations	Length	Guardrail Removal
Lt. Sta. 657+39.00 TO 658+41.00	102	93
Rt. Sta. 657+39.00 TO 658+41.00	102	94
Lt. Sta. 658+82.00 TO 659+84.00	102	94
Rt. Sta. 658+82.00 TO 659+84.00	102	94
<b>Totals</b>		<b>375</b>

Guardrail Locations	Length*	Ty 1 Spl Tangent End Section	Ty 6 End Section	Guardrail Markers Type A	Terminal Marker Direct-Applied
Lt. Sta. 657+39.50 TO 658+41.00	101.5	1	1	4	1
Rt. Sta. 657+39.50 TO 658+41.00	101.5	1	1	4	1
Lt. Sta. 658+82.00 TO 659+83.50	101.5	1	1	4	1
Rt. Sta. 658+82.00 TO 659+83.50	101.5	1	1	4	1
<b>Totals</b>		<b>4</b>	<b>4</b>	<b>16</b>	<b>4</b>

\*The Guardrail Station lengths are total lengths of Type 1 (Spl) plus Type 6.

Location	Length	Removal & Disposal of Unsuitable Material	Porous Granular Embankment	Geotechnical Fabric for Ground Stabilization	Sub-base Granular Material, Type A	Rock Fill
		Cu Yd	Cu Yd	Sq Yd	Ton	Ton
IL 78						
654+50.00 TO 662+00.00	750	3405.7	579	3406	2323.7	2349.1
<b>Total</b>	<b>750</b>	<b>3405.7</b>	<b>579</b>	<b>3406</b>	<b>2323.7</b>	<b>2349.1</b>

Location	4" (W)	4" (Y)
	Foot	Foot
653+86.00 TO 664+00.00	2028	2028
<b>TOTAL</b>	<b>4056</b>	

Location	Length	Dash	WORK ZONE PAVEMENT MARKING REMOVAL
		Foot	
653+86.00 TO 664+00.00	1014	110	36.3
Type III Tape	2762		911.5
<b>Total</b>		<b>110</b>	<b>947.8</b>