

TRENCH BACKFILL	
LOCATION	CU YD
Sta. 654+50 to 662+00	206.1
TOTAL	206.1

INLET AND PIPE PROTECTION	
LOCATION	EACH
Rt. Sta. 658+05	1
TOTAL	1

FILTER FABRIC	
LOCATION	SQ YD
Sta. 654+50 to 662+00	374.9
TOTAL	374.9

PCC PAVEMENT 10"	
LOCATION	SQ YD
Sta. 654+50 to 662+00	2291.7
TOTAL	2291.7

PAVEMENT FABRIC	
LOCATION	SQ YD
Sta. 654+50 to 662+00	2291.7
TOTAL	2291.7

PAVEMENT REMOVAL	
LOCATION	SQ YD
Sta. 654+50 to 662+00	2194.1
TOTAL	2194.1

GUTTER REMOVAL	
LOCATION	FOOT
Lt. Sta. 654+50 to 658+41	392
Lt. Sta. 658+82 to 661+58	277
TOTAL	669

COMBINATION CONCRETE CURB & GUTTER REMOVAL	
LOCATION	FOOT
Rt. Sta. 654+26 to 658+41	415
Rt. Sta. 658+82 to 660+00	118
TOTAL	533

BITUMINOUS CONCRETE SHOULDER REMOVAL	
LOCATION	SQ YD
Lt. Sta. 654+50 to 658+00	233.3
Lt. Sta. 658+00 to 658+41	13.7
Lt. Sta. 658+82 to 659+23	13.7
Lt. Sta. 659+23 to 662+00	184.7
TOTAL	445.4

PCC SHOULDER 10"	
LOCATION	SQ YD
Lt. Sta. 654+50 to 658+05	216.9
Lt. Sta. 658+05 to 658+36	14.6
Lt. Sta. 658+82 to 659+13	17.0
Lt. Sta. 659+13 to 661+58	149.7
TOTAL	398.2

CONSTRUCTION LAYOUT	
LOCATION	L SUM
Jobsite	1
TOTAL	1

PIPE UNDERDRAINS 6"	
LOCATION	FOOT
Sta. 654+50 to 662+00	1730
TOTAL	1730

REMOVING MANHOLES	
LOCATION	EACH
Lt. Sta. 658+62	1
CL Sta. 658+62	1
Lt. Sta. 659+25	1
TOTAL	3

REMOVING INLETS	
LOCATION	EACH
Lt. Sta. 658+00	1
Rt. Sta. 658+05	1
Lt. Sta. 658+62	1
Rt. Sta. 658+62	1
Lt. Sta. 659+22	1
Rt. Sta. 659+22	1
Rt. Sta. 659+59	1
TOTAL	7

CLASS SI CONCRETE (OUTLET)	
LOCATION	CU YD
Rt. Sta. 654+26	0.73
Lt. Sta. 654+50	0.73
Lt. Sta. 661+40	0.73
Rt. Sta. 661+58	0.73
Entrances	4.78
TOTAL	7.7

CONCRETE GUTTER, TYPE B (MODIFIED)	
LOCATION	FOOT
Rt. Sta. 654+50 to 658+41	391
Rt. Sta. 658+82 to 661+58	276
Lt. Sta. 654+26 to 658+41	415
Lt. Sta. 658+82 TO 661+58	276
TOTAL	1358

COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24	
LOCATION	FOOT
Rt. Sta. 658+41 to 658+82	41
lt. Sta. 658+41 to 658+82	41
TOTAL	82

ENGINEER'S FIELD OFFICE	
LOCATION	CAL MO
Jobsite	3
TOTAL	3

MOBILIZATION	
LOCATION	L SUM
Jobsite	1
TOTAL	1

TRAFFIC CONTROL & PROTECTION, STD 701306	
LOCATION	L SUM
Jobsite	1
TOTAL	1

TRAFFIC CONTROL & PROTECTION, STD 701321	
LOCATION	EACH
Jobsite	1
TOTAL	1

TRAFFIC CONTROL & PROTECTION, BLR 21	
LOCATION	L SUM
Jobsite	1
TOTAL	1

TEMPORARY BRIDGE TRAFFIC SIGNALS	
LOCATION	EACH
Jobsite	1
TOTAL	1

PAVEMENT MARKING TAPE TYPE III	
LOCATION	FOOT
Sta. 652+34 to 664+16	2514
Stop Bars	248
TOTAL	2762

TEMPORARY CONCRETE BARRIER	
LOCATION	FOOT
Sta. 654+50 to 662+00	950
TOTAL	950

RELOCATE TEMPORARY CONCRETE BARRIER	
LOCATION	FOOT
Sta. 654+50 to 662+00	950
TOTAL	950

PAVEMENT MARKING REMOVAL	
LOCATION	SQ FT
Sta. 651+90 to 653+90	100
Sta. 662+57 to 664+57	100
TOTAL	200

CHANGEABLE MESSAGE SIGNS	
LOCATION	CAL DA
Jobsite	14
TOTAL	14

IMPACT ATTENUATOR TEMP NRD TL 3	
LOCATION	EACH
Jobsite	2
TOTAL	2

IMPACT ATTENUATOR RELOCATE	
LOCATION	EACH
Jobsite	2
TOTAL	2

RAILROAD PROTECTIVE LIABILITY INSURANCE	
LOCATION	L SUM
Jobsite	1
TOTAL	1