

ROUTE		SECTION	COUNTY	SHEET	
F.A.P.	VAR.	*	PEORIA	TOTAL	NO.
MKD.	IL 90			100	80

* (108X, 130, 102)RS-3; 129RS-4, 101RS-2

STA	TO	STA	LENGTH	WIDTH	AREA	HMA SURFACE REMOVAL BUTT JOINT	HMA SURFACE REMOVAL 3/4"	HMA SURFACE REMOVAL 1 1/4"	HMA SURFACE REMOVAL 1 1/2"	HMA SURFACE REMOVAL 2"	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	POLYMERIZED LEVELING BINDER, 3/4"	HMA SURFACE COURSE, 1 1/2"	HMA SHOULDERS 1 1/2"	MATERIAL TRANSFER DEVICE	TEMPORARY RAMP	AGGREGATE SHOULDERS, TYPE B					
			FT	FT	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	TON	TON	TON	TON	SQ YD	TON					
115+63	TO	115 + 93	30	36	120.0	120.0					0.050	0.2	5.0	10.1	0.0	10.1	14.4						
115 + 93	TO	117 + 50	157	26	453.6			87.2		453.6	0.293	1.6	19.0	38.1	7.3	45.4							
117 + 50	TO	123 + 50	600	26	1733.3			746.0		1733.3	1.342	7.4	72.8	145.6	62.7	208.3							
123 + 50	TO	141 + 97.1	1880	26	5431.1					5431.1	2.940	16.3	228.1	456.2		456.2							
141 + 97.1	TO	142 + 84.5	87.4	27.5	267.1					267.1	0.145	0.8	11.2	22.4		22.4							
142 + 84.5	TO	145 + 27.9	243.4	28.4	768.1					768.1	0.416	2.3	32.3	64.5		64.5							
145 + 27.9	TO	146 + 14.9	87	27.8	268.7					268.7	0.145	0.8	11.3	22.6		22.6							
146 + 14.9	TO	147 + 94.6	179.7	27.95	558.1					558.1	0.302	1.7	23.4	46.9		46.9							
147 + 94.6	TO	149 + 02.31 (BK)	107.71	28.2	337.5					337.5	0.183	1.0	14.2	28.3		28.3							
592 + 04.48 (AH)	TO	591 + 23	81.48	29.1	263.5					263.5	0.143	0.8	11.1	22.1		22.1							
591 + 23	TO	590 + 93	30	VAR.	100.0	100.0					0.042	0.2	4.2	8.4		8.4	16.7						
W. MAIN ST. MAINLINE E.O.P.						TO	1002 + 85	VAR	VAR	389.0	389.0		0.211	1.2	16.3	32.7		16.1					
COTTAGE GROVE (NORTH)						TO	93 + 45	30	VAR	130.0	130.0		0.070	0.4	5.5	10.9		15.0					
COTTAGE GROVE (SOUTH)						TO	93 + 00	30	VAR	130.0	130.0		0.070	0.4	5.5	10.9		15.6					
TREMONT (NORTH)						TO	83 + 44	30	VAR	130.0	130.0		0.070	0.4	5.5	10.9		15.0					
TREMONT (SOUTH)						TO	83 + 00	30	VAR	130.0	130.0		0.070	0.4	5.5	10.9		15.0					
SANTE FE/MAIN ST (NORTH)						TO	593 + 31	117	VAR	3333.0	83.0	3250.0	1.804	10.0	140.0	280.0		13.3					
SANTE FE (SOUTH)						TO	71 + 07	107	VAR	370.0	93.0	277.0	0.200	1.1	15.5	31.1		16.7					
SUB-TOTALS											1305		833		13608	8.5	47	626	1253	70	935	138	
TOTALS											2243 *	1597	833	126697	13608	78 *	434	5948	11974	204	11791	208	2346

* Subtotal for roadway resurfacing areas, for additional quantities see sheet 18

APPLICATION RATE (POLY PRIME)
 0.1 Gal./Sq. Yd. on Cold Milled Surface
 .05 Gal./Sq. Yd. on Shoulder Overlay
 .03 Gal./Sq. Yd. Fog Coat on New Binder

APPLICATION RATE (AGG PRIME)
 4 Lb/Sq. Yd. on Cold Milled Surface
 2 Lb/Sq. Yd. on Binder

TABULATION OF RESURFACING QUANTITIES (SHEET 3 OF 6)