

SUMMARY OF QUANTITIES

CONTRACT NO. 70025				
F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	**	104	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* 74(10-70)RS-3 & (10-71,73)RS-2				
** PIATT & CHAMPAIGN				

LOCATION OF WORK:

PIATT COUNTY RURAL ROADWAY/ STRUCTURE IMPROVEMENTS FAI-72 STA. 1376+84 TO STA. 1518+02.71 1000 100% STATE QUANTITY	CHAMPAIGN COUNTY RURAL ROADWAY/ STRUCTURE IMPROVEMENTS FAI-72 STA. 1518+02.71 TO STA. 1764+26 1000 100% STATE QUANTITY	CHAMPAIGN COUNTY URBAN ROADWAY/ STRUCTURE IMPROVEMENTS FAI-72 STA. 1764+26 TO STA. 2041+32 1000 100% STATE QUANTITY	CHAMPAIGN COUNTY RURAL STRUCTURE IMPROVEMENTS FAI-72 S.N. 010-0203 S.N. 010-0204 SFTY-2A 100% STATE QUANTITY	CHAMPAIGN COUNTY URBAN ROADWAY/ STRUCTURE IMPROVEMENTS FAI-72 S.N. 010-0205 S.N. 010-0206 SFTY-2A 100% STATE QUANTITY	CHAMPAIGN COUNTY URBAN ROADWAY/ STRUCTURE IMPROVEMENTS FAI-72 S.N. 010-0034 S.N. 010-0035 SFTY-2A 100% STATE QUANTITY
-----------------------------------------------------------------------------------------------------------------------------------------------	---------------------------------------------------------------------------------------------------------------------------------------------------	------------------------------------------------------------------------------------------------------------------------------------------------	-----------------------------------------------------------------------------------------------------------------------------------------	--------------------------------------------------------------------------------------------------------------------------------------------------	--------------------------------------------------------------------------------------------------------------------------------------------------

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY	PIATT COUNTY QUANTITY	CHAMPAIGN COUNTY QUANTITY	CHAMPAIGN COUNTY QUANTITY	CHAMPAIGN COUNTY QUANTITY	CHAMPAIGN COUNTY QUANTITY	CHAMPAIGN COUNTY QUANTITY
50300100	FLOOR DRAINS	EACH	40.0				20.0	20.0	
50300225	CONCRETE STRUCTURES	CU YD	6.7	6.7					
50300255	CONCRETE SUPERSTRUCTURE	CU YD	53.8			53.8			
* 50300530	FLOOR DRAIN EXTENSION	EACH	12.0		12.0				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,926.0	806.0	40.0	1,080.0			
54002020	EXPANSION BOLTS 3/4 INCH	EACH	64.0			64.0			
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	4,326.7				718.3	756.4	2,852.0
60260100	INLETS TO BE ADJUSTED	EACH	15.0			15.0			
60260200	INLETS TO BE ADJUSTED (SPECIAL)	EACH	9.0			9.0			
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	2.0			2.0			
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	6,775.0	1,415.0	2,845.0	2,515.0			
* 63000003	STEEL PLATE BEAM GUARD RAIL, TYPE A, 9 FOOT POSTS	FOOT	3,112.5			3,112.5			
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	15.0		1.0	14.0			
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	22.0		4.0	18.0			
* 63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	11.0		4.0	7.0			
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) FLARED	EACH	37.0	2.0	8.0	27.0			
* 63100217	TRAFFIC BARRIER TERMINAL, TYPE 6B (SPECIAL)	EACH	5.0	1.0	2.0	2.0			
63200310	GUARDRAIL REMOVAL	FOOT	11,033.0	901.0	1,802.0	8,530.0			
* 63400105	GUARD POSTS	EACH	143.0	30.0	53.0	60.0			
63400205	GUARD POST REMOVAL	EACH	165.0	35.0	61.0	69.0			

(CONTD NEXT SHEET)

* SPECIALTY ITEM
** SFTY-2A (S.N. 010-0160)

SHEET 3 OF 6

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 F.A.I. ROUTE 72
 SECTION 74(10-70)RS-3&(10-71,73)RS-2
 PIATT & CHAMPAIGN CO.
 SCALE: N/A
 DATE: 04-01-09
 DRAWN BY: JMS
 CHECKED BY:

PLOT DATE * 4/17/2009
 FILE NAME * c:\va\so\h\p\m\001\bl.ac\rt\8112995\0978025-wt-500.dgn
 PLOT SCALE * 1/8"=1'-0"
 USER NAME * jbb@ct