

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	**	104	28

*74(10-70)RS-3 & (10-71,73)RS-2
 ** CHAMPAIGN & PIATT

78000200 THERMOPLASTIC PAVEMENT MARKING LINE-4" (WHITE)

		STATION	TO	STATION	FOOT
I-72 MAINLINE					
I-72 EB	RT	1376+84.00		RT 1406+25.92	2941.9
I-72 WB	LT	1376+84.00		LT 1401+58.89	2474.9
I-72 EB	RT	1411+56.00		RT 1432+15.00	2059.0
I-72 WB	LT	1411+09.00		LT 1431+37.00	2028.0
I-72 EB	RT	1441+84.65		RT 1518+02.71	7618.1
I-72 WB	LT	1431+37.37		LT 1518+02.71	8665.3
I-72 EB	RT	1518+02.71		RT 1663+08.96	14506.3
I-72 WB	LT	1518+02.71		LT 1654+57.96	13655.3
I-72 EB	RT	1663+09.00		RT 1684+36.00	2127.0
I-72 WB	LT	1664+08.00		LT 1685+36.00	2128.0
I-72 EB	RT	1693+86.40		RT 1764+26.00	7039.6
I-72 WB	LT	1690+65.68		LT 1764+26.00	7360.3
I-72 EB	RT	1764+26.00		RT 1942+97.42	17871.4
I-72 WB	LT	1764+26.00		LT 1939+18.51	17492.5
I-72 EB	RT	1949+61.00		RT 1957+36.00	775.0
I-72 WB	LT	1949+82.00		LT 1955+75.00	593.0
I-72 EB	RT	1965+52.00		RT 1971+92.00	640.0
I-72 WB	LT	1964+12.00		LT 1971+71.00	759.0
I-72 EB	RT	1982+21.27		RT 1993+30.60	1109.3
I-72 WB	LT	1978+42.36		LT 1993+30.60	1488.2
I-72 EB	RT	1993+30.58		RT 2024+85.00	3154.4
I-72 WB	LT	1993+30.58		LT 2024+98.00	3167.4

SUB-TOTAL = 119654.0

I-72 EB UNIVERSITY AVENUE

COUNTRY FAIR INTERSECTION

I-72 EB	LTL	2025+05.00		LTL 2028+25.00	320.0
I-72 EB	RTL	2025+85.00		RTL 2028+25.00	240.0

MATTIS AVENUE INTERSECTION

I-72 EB	RTL	2039+35.00		RTL 2041+75.00	240.0
---------	-----	------------	--	----------------	-------

SUB-TOTAL = 800.0

78000200 THERMOPLASTIC PAVEMENT MARKING LINE-4" (WHITE) (CONT'D)

		STATION	TO	STATION	FOOT
I-72 WB CHURCH STREET					
COUNTRY FAIR INTERSECTION					
I-72 WB	LTL	2027+05.00		LTL 2029+50.00	245.0
I-72 WB	RTL	2027+05.00		RTL 2030+00.00	295.0
SUB-TOTAL =					540.0
I-72 & IL 10 RAMPS					
RAMP A	RT	100+90.00		RT 118+20.00	1730.0
RAMP B	RT	200+00.00		RT 219+65.00	1965.0
RAMP C	RT	300+00.00		RT 319+65.00	1965.0
RAMP D	RT	401+00.00		RT 418+14.00	1714.0
SUB-TOTAL =					7374.0
I-72 & IL 47 RAMPS					
RAMP E	RT	500+85.00		RT 521+40.00	2055.0
RAMP F	RT	600+00.00		RT 617+55.00	1755.0
RAMP G	RT	700+00.00		RT 717+20.00	1720.0
RAMP H	RT	800+50.00		RT 821+40.00	2090.0
SUB-TOTAL =					7620.0

I-57 & I72 INTERCHANGE

LOOP A	RT	11+15.00		RT 15+54.00	439.0
LOOP B	RT	27+38.00		RT 32+65.00	527.0
LOOP C	RT	71+53.00		RT 75+52.00	399.0
LOOP D	RT	87+30.00		RT 92+71.00	541.0
RAMP E	RT	141+00.00		RT 152+31.00	1131.0
RAMP F	RT	160+00.00		RT 167+10.00	710.0
RAMP G	RT	220+80.00		RT 232+31.00	1151.0
RAMP H	RT	240+00.00		RT 247+85.00	785.0

SUB-TOTAL = 5683.0

TOTAL = 141671.0

USE = 141675.0

PLOT DATE = 4/16/2009
 FILE NAME = c:\pnt\work\PIATT\PIATT\SHERER\JM\0112945\70025 Schedule.dgn
 PLOT SCALE = 4.23629 / IN.
 USER NAME = sherer_jm

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES

F.A.I. ROUTE 72
 SECTION 74(10-70)RS-3 & (10-71,73)RS-2
 CHAMPAIGN & PIATT COUNTY

SCALE: NONE DRAWN BY: MLB
 DATE: 04/01/2009 CHECKED BY: