

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	**	104	34

*74(10-70)RS-3 & (10-71,73)RS-2
** CHAMPAIGN & PIATT

GUARDRAIL SCHEDULES

SING TRUSS @ 1973+60.00

63200310 GUARDRAIL REMOVAL

STATION	TO	STATION	LENGTH(FT)
1973+60.00		1974+85.00	WB RT 125.00
1973+60.00		1975+73.00	WB LT 213.00

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION	EACH
1971+85.00		1972+35.00	WB RT 1.0
1973+10.00		1973+60.00	WB LT 1.0

63000001 STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS

STATION	TO	STATION	LENGTH(FT)
1972+35.00		1973+60.00	WB RT 125.00

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION	TO	STATION	EACH
1973+60.00		1973+74.27	WB RT 1.0
1973+60.00		1973+74.27	WB LT 1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION	EACH
WB RT	1.0
WB LT	1.0

010-0170

63200310 GUARDRAIL REMOVAL

STATION	TO	STATION	LENGTH(FT)
1985+45.00		1987+95.00	EB RT 250.00
1987+07.00		1989+45.00	WB RT 238.00

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION	EACH
1984+13.85		1984+63.85	EB RT 1.0
1990+32.30		1990+82.30	WB RT 1.0

63000001 STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS

STATION	TO	STATION	LENGTH(FT)
1984+63.85		1986+63.85	EB RT 200.00
1987+94.80		1990+32.30	WB RT 237.50

63100069 TRAFFIC BARRIER TERMINAL TYPE 6B

STATION	TO	STATION	EACH
1986+63.85		1987+22.00	EB RT 1.0
1987+37.00		1987+95.15	EB RT 1.0
1987+36.65		1987+94.80	WB RT 1.0

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION	TO	STATION	EACH
1987+95.15		1988+09.42	EB RT 1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION	EACH
1984+13.85	EB RT 1.0
1990+82.30	WB RT 1.0

010-0036 (EB) & 010-0037 (WB)

63200310 GUARDRAIL REMOVAL

STATION	TO	STATION	LENGTH(FT)
2005+72.00		2011+10.00	EB RT 538.00
2012+66.00		2017+04.00	EB RT 438.00
2005+79.00		2011+10.00	EB LT 531.00
2012+66.00		2017+04.00	EB LT 438.00
2007+03.00		2012+05.00	WB RT 502.00
2014+62.00		2018+45.00	WB RT 383.00
2007+06.00		2012+08.00	WB LT 502.00
2014+55.00		2018+07.00	WB LT 352.00

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION	EACH
2005+64.35		2008+14.35	EB RT 1.0
2005+76.85		2008+26.85	EB LT 1.0
2017+95.15		2018+45.15	WB RT 1.0
2017+63.15		2018+13.15	WB LT 1.0

63000003 STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS

STATION	TO	STATION	LENGTH(FT)
2006+14.35		2010+64.35	EB RT 450.00
2013+11.65		2016+99.15	EB RT 387.50
2006+26.85		2010+64.35	EB LT 437.50
2013+11.65		2016+99.15	EB LT 387.50
2007+09.35		2011+59.35	WB RT 450.00
2015+07.65		2017+95.15	WB RT 287.50
2007+12.35		2011+62.35	WB LT 450.00
2015+00.65		2017+63.15	WB LT 282.50

63100085 TRAFFIC BARRIER TERMINAL TYPE 6

STATION	TO	STATION	EACH
2010+64.35		2011+10.00	EB RT 1.0
2012+66.00		2013+11.65	EB RT 1.0
2010+64.35		2011+10.00	EB LT 1.0
2012+66.00		2013+11.65	EB LT 1.0
2011+59.35		2012+05.00	WB RT 1.0
2014+62.00		2015+07.65	WB RT 1.0
2011+62.35		2012+08.00	WB LT 1.0
2014+55.00		2015+00.65	WB LT 1.0

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION	TO	STATION	EACH
2016+99.15		2017+13.42	EB RT 1.0
2016+99.15		2017+13.42	EB LT 1.0
2006+95.08		2007+09.35	WB RT 1.0
2006+98.08		2007+12.35	WB LT 1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION	EACH
2005+64.35	EB RT 1.0
2005+76.85	EB LT 1.0
2018+45.15	WB RT 1.0
2018+13.15	WB LT 1.0

63400105 GUARD POSTS

LOCATION EACH

S.N. 074-0007	10.0
S.N. 010-0160	10.0
S.N. 010-0156	10.0
S.N. 010-0146	10.0
S.N. 010-0166	10.0
S.N. 010-0168	10.0
S.N. 010-0170	10.0

* TOTAL = 70.0

* QTY DOES NOT REFLECT ENTIRE JOB

PLOT DATE = 4/13/2009
FILE NAME = c:\p\work\PIATT\PIATT\SHERER\JM\0112945\70025 Schedules.dgn
PLOT SCALE = 4.23629 / IN.
USER NAME = sherer_jm

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES

F.A.I. ROUTE 72
SECTION 74(10-70)RS-3 & (10-71,73)RS-2
CHAMPAIGN & PIATT COUNTY

SCALE: NONE DRAWN BY: MLB
DATE: 04/01/2009 CHECKED BY: