CLASS A PATCHING, 14" (CONT'D)

## PATCH AREA

			LENGTH	WIDTH	44200620 TYPE II 14.0"	44200624 TYPE III 14.0"	44200628 TYPE IV 14.0"	44213200 SAW CUTS	Z0075300 TIE BARS	44213000 PATCHING REINFORCEMENT
STATION	DIRECTION	LANE	(ft)	<u>(ft)</u>	(sq. yd)	<u>(sq. yd)</u>	<u>(sq. yd)</u>	(ft)	(each)	<u>(sq. yd)</u>
1379+95.00	EB	PL	6	12	8.0	0.0	0.0	60.0	0	8.0
1379+95.00	EB	DL	6	12	8.0	0.0	0.0	60.0	0	8.0
1387+00.00	EB	PL	10	12	13.3	0.0	0.0	68.0	0	13.3
1387+00.00	EB	DL	10	12	13.3	0.0	0.0	68.0	0	13.3
1387+37.00	EB	DL	6	12	8.0	0.0	0.0	60.0	0	8.0
1398+36.00	EB	PL	8	12	10.7	0.0	0.0	64.0	0	10.7
1398+36.00	EB	DL	12	12	0.0	16.0	0.0	72.0	0	16.0
1401+41.00	EB	DL	10	12	13.3	0.0	0.0	68.0	0	13.3
1413+06.00	EB	PL	12	12	0.0	16.0	0.0	72.0	0	16.0
1413+06.00	EB	DL	12	12	0.0	16.0	0.0	72.0	0	16.0
1420+23.00	EB	DL	24	6	0.0	16.0	0.0	72.0	12	16.0
1422+91.00	EB	DL	8	12	10.7	0.0	0.0	64.0	0	10.7
1427+07.00	EB	PL	10	12	13.3	0.0	0.0	68.0	0	13.3
1427+07.00	EB	DL	10	12	13.3	0.0	0.0	68.0	0	13.3
1428+96.00	EB	PL	20	12	0.0	0.0	26.7	88.0	10	26.7
1428+96.00	EB	DL	20	12	0.0	0.0	26.7	88.0	10	26.7
1431+66.00	EB	PL	20	12	0.0	0.0	26.7	88.0	10	26.7
1431+66.00	EB	DL	20	12	0.0	0.0	26.7	88.0	10	26.7
1445+25.00	EB	PL	12	12	0.0	16.0	0.0	72.0	0	16.0
1445+25.00	EB	DL	12	12	0.0	16.0	0.0	72.0	0	16.0
1454+03.00	EB	PL	20	12	0.0	0.0	26.7	88.0	10	26.7
1454+03.00	EB	DL	20	12	0.0	0.0	26.7	88.0	10	26.7
1459+81.00	EB	DL	6	12	8.0	0.0	0.0	60.0	0	8.0
1462+34.00	EB	PL	12	12	0.0	16.0	0.0	72.0	0	16.0
1462+34.00	EB	DL	12	12	0.0	16.0	0.0	72.0	0	16.0
1465+68.00	EB	PL	12	12	0.0	16.0	0.0	72.0	0	16.0
1465+68.00	EB	DL	12	12	0.0	16.0	0.0	72.0	0	16.0
1466+68.00	EB	DL	6	12	8.0	0.0	0.0	60.0	0	8.0
1471+60.00	EB	PL	6	12	8.0	0.0	0.0	60.0	0	8.0
1471+60.00	ЕВ	DL	6	12	8.0	0.0	0.0	60.0	0	8.0
				SUB-TOTAL =	144.0	160.0	160.0	2136.0	72.0	464.0

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES

F.A.I. ROUTE 72 SECTION 74(10-70)RS-3 & (10-71,73)RS-2 CHAMPAIGN & PIATT COUNTY

SCALE: NONE DATE: 04/01/2009 DRAWN BY: MLB CHECKED BY