GENERAL PLAN

CONTRACT NO. 70025 COUNTY TOTAL SHEE NO. SECTION 104 69

> * 74(10-70)RS-3 & (10-71,73)RS-2 ** PIATT & CHAMPAIGN

> > SHEET 1 OF 2

S.N. 010-0203 & 010-0204

THE EXISTING DUAL MAINLINE STRUCTURES WERE BUILT IN 1968 AS FA ROUTE 11, SECTION 10-71B AT STATION 1840+85 IN CHAMPAIGN COUNTY. THE 14 INCH R.C. SLABS ARE SUPPORTED BY TWO STRAIGHT STEM PIERS ON SPREAD FOOTINGS AND STUB ABUTMENTS ON CONCRETE PILES. THE EXISTING STRUCTURES MEASURE 80'-10' FROM BACK TO BACK OF ABUTMENTS AND 42'-6" OUT TO OUT OF DECK. THE HORIZONTAL CLEARANCE IS 39'-0" FROM FACE TO FACE OF PARAPET.


IN 1975, THE STRUCTURES WERE IMPROVED WITH A 1¾" HMA WEARING SURFACE AND WATERPROOFING MEMBRANE SYSTEM WITH FAI ROUTE 72, SECTION: DISTRICT 5 BRIDGE DECK WATERPROOFING 1975-2.

SEE LIST OF PROPOSED IMPROVEMENTS ON THIS SHEET.

LEGEND

H.M.A. SURFACE REMOVAL, DECK & PROPOSED 2" HMA WEARING SURFACE & WATERPROOFING MEMBRANE SYSTEM


TRAFFIC SHALL BE MAINTAINED USING STAGE CONSTRUCTION.



5'-6" 9'-6" ¢ ROADWAY & STAGE CONSTRUCTION LINE 3/16" / FT 3/16" / FT 1/4" / FT 1/4" / FT SEE DETAIL BELOW EXISTING 1 1/2" HMA WEARING SURFACE EXISTING AND PROPOSED WATER-PROPOSED POLYMERIZED HMA SURFACE COURSE, MIX D. N-90, 168 LBS/SQ YD

TYPICAL DECK CROSS SECTION S.N. 010-0203 LOOKING UP-STATION S.N. 010-0204 LOOKING DOWN-STATION

WATERPROOFING TREATMENT AT STAGE CONSTRUCTION



NOTE:

ALSO EXTEND WATERPROOFING MEMBRANE LONGITUDINALLY 6" BEYOND EACH END OF DECK.

QUANTITY OF PROPOSED HMA BEYOND END OF DECK INCLUDED WITH ROADWAY.

BUNTE OF A

081-004625

GENERAL NOTES

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN SCOPE OF WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.

TOTAL BILL OF MATERIALS - TWO STRUCTURES

SECTION AT DRAIN


EXTEND WATERPROOFING MEMBRANE 3" UP FACE OF PARAPET, FULL

PROPOSED WATERPROOFING MEMBRANE

LENGTH OF DECK

PROPOSED HMA OVERLAY

UNIT	TOTAL
SQ YD	700.6
SQ YD	718.3
GAL.	70.0
TON	58.9
SQ YD	6.0
SQ YD	35.0
EACH	20.0
	SQ YD SQ YD GAL TON SQ YD SQ YD SQ YD



ILLINOIS DEPARTMENT OF TRANSPORTATION

GENERAL PLAN S.N. 010-0203 & 010-0204

F.A.I. ROUTE 72 SECTION 74(10-70)RS-3&(10-71,73)RS-2 SCALE: NONE PIATT/CHAMP. CO. DRAWN BY: GMS

3. REPLACE EXISTING DRAINS.

REMOVAL AND REPLACEMENT OF THE EXISTING HMA WEARING SURFACE AND WATERPROOFING MEMBRANE SYSTEM.

2. FULL AND PARTIAL-DEPTH PATCHING OF DECK SLAB.

PROPOSED WORK

DATE VAME SCALE PLOT FILE PLOT USER