

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
709	(104)RS-1	MCLEAN	21	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

SURVEY MARKER VAULT - X0301232

LOCATION	STATION	EACH
3700E	1184+50.00	1
3700E	1184+64.00	1
3800E	1237+20.00	1
3800E	1237+75.00	1
3900E	1290+55.00	1
3900E	1289+89.00	1
4000E	1343+61.00	1
4200E	1450+30.00	1
TOTAL		8

PAVEMENT MARKINGS

	STATION	STATION	78001110 PAINT LINE 4" (WHITE) (FOOT)	78001110 PAINT LINE 4" (YELLOW) (FOOT)	78000100 THERMOPLASTIC LETTERS & SYMBOLS (SQ. FT.)	78000650 THERMOPLASTIC LINE 24" (FOOT)
FAP 709 (US 136)	1162+80.00	1416+53.00	50,746.00	13,736.00		
FAP 709 (US 136)	1417+23.00	1442+63.00	5,080.00	924.00		
FAP 709 (US 136)	1444+62.00	1450+95.00	1,266.00	867.00		
RAILROAD CROSSING	1443+60.00	---			123.00	72.00
TOTALS			57,092.00	15,527.00	123.00	72.00

SIDE ROADS AND ENTRANCES

STATION	TYPE	DIST. EOP TO JOINT (FOOT)	40800040 INCIDENTAL BIT. SURF. (TON)	44000196 HMA REM. SPEC. (SQ YD)	40800010 BIT. MATLS. (PRIME COAT) (GAL)	40800030 AGGREGATE (PRIME COAT) (TON)	44000100 PAVEMENT REMOVAL (SQ YD)	35101400 AGG. BASE. CSE., TYPE B (TON)
1166+63.00	LT PE	6.00	1.52	18.00	1.80	0.04		
1166+63.00	RT MB	6.50	2.52	30.00	3.00	0.06		
1184+50.00	RT SR	32.00	9.08	108.00	10.80	0.22		
1184+64.00	LT SR	25.60	8.40	100.00	10.00	0.20		
1237+20.00	RT SR	27.70	11.76	140.00	14.00	0.28		
1264+32.00	LT SR	62.00	32.68	389.00	38.90	0.78		
1270+78.00	RT PE	10.70	2.27	27.00	2.70	0.06		
1289+89.00	RT SR	28.00	20.16	240.00	24.00	0.48		
1343+61.00	RT SR	46.50	18.23	217.00	21.70	0.44		
1343+66.00	LT SR	18.00	5.97	71.00	7.10	0.15		
1396+85.00	RT SR	28.00	9.41	112.00	11.20	0.23		
1397+31.00	LT SR	27.50	10.17	121.00	12.10	0.25		
1411+55.00	LT PE	5.50	4.04	48.00	4.80	0.10		
1450+30.00	RT SR	26.00	7.90	94.00	9.40	0.19		
1450+30.00	LT SR	27.00	10.50	0.00	12.50	0.25	125.00	48.00
			154.61	1715.00	184.00	3.73	125.00	48.00
USE			155.00	1715.00	184.00	4.00	125.00	48.00

RAISED REFLECTIVE PAVEMENT MARKER 78100100

STATION	TO	STATION	2 WAY AMBER (EACH)
1162+80.00		1265+50.00	130
1265+50.00		1270+78.00	16
1270+78.00		1416+53.00	184
1417+23.00		1442+63.00	33
1444+62.00		1450+95.00	9
TOTAL			372

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL 78300200

STATION	TO	STATION	EACH
1162+80.00		1416+53.00	319
1417+23.00		1442+63.00	33
1444+62.00		1450+95.00	9
TOTAL			361