

SUMMARY OF QUANTITIES

CODE NO.	DESCRIPTION	UNIT	LOCATION OF WORK:	MCLEAN CO.	MCLEAN CO.	MCLEAN CO.
			FUNDING BREAKOUT:	FAP 693	FAP 693	FAP 693
			CONSTRUCTION TYPE CODE:	IL 9	IL 9	IL 9
			TOTAL	100% STATE	100% STATE	100% STATE
			QUANTITY	QUANTITY	QUANTITY	QUANTITY
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON		351.0	351.0	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD		151,019.0	151,019.0	
44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD		3,335.0	3,335.0	
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD		743.0	743.0	
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD		125.0	125.0	
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD		393.0	393.0	
44201851	CLASS D PATCHES, TYPE II, 17 INCH	SQ YD		47.0	47.0	
48101200	AGGREGATE SHOULDERS, TYPE B	TON		2,639.0	2,639.0	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD		1,007.0	1,007.0	
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH		1.0		1.0
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH		1.0		1.0
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH		1.0		1.0
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH		1.0		1.0
50100700	REMOVAL OF EXISTING STRUCTURES NO. 5	EACH		1.0		1.0
50100800	REMOVAL OF EXISTING STRUCTURES NO. 6	EACH		1.0		1.0
50105220	PIPE CULVERT REMOVAL	FOOT		40.0		40.0
50200100	STRUCTURE EXCAVATION	CU YD		1,305.0		1,305.0
51500100	NAME PLATES	EACH		6.0		6.0
54001001	BOX CULVERT END SECTION, CULVERT NO.1	EACH		1.0		1.0
54001002	BOX CULVERT END SECTION, CULVERT NO.2	EACH		2.0		2.0
54001003	BOX CULVERT END SECTION, CULVERT NO.3	EACH		2.0		2.0
54001004	BOX CULVERT END SECTION, CULVERT NO.4	EACH		1.0		1.0
54001005	BOX CULVERT END SECTION, CULVERT NO.5	EACH		2.0		2.0
54001006	BOX CULVERT END SECTION, CULVERT NO.6	EACH		2.0		2.0
54020804	PRECAST CONCRETE BOX CULVERT 8' X 4' (M273)	FOOT		73.0		73.0
54020805	PRECAST CONCRETE BOX CULVERT 8' X 5' (M273)	FOOT		146.0		146.0
54021003	PRECAST CONCRETE BOX CULVERT 10' X 3' (M273)	FOOT		73.0		73.0

* SPECIALTY ITEMS

FILE NAME =	USER NAME = carrollrt	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cr:\pw\work\FWIDOT\CARROLLRT\0104712\d570509\sh-t-cover.dgn		DRAWN -	REVISED -			693	(21,22)R,RS-1	MCLEAN	105	5	
PLOT SCALE = 40.0000 / / IN.		CHECKED -	REVISED -			CONTRACT NO. 70509					
PLOT DATE = 4/3/2009		DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO

ILLINOIS FED. AID PROJECT