

SCHEDULE OF QUANTITIES

78300100

PAVEMENT MARKING REMOVAL

LOCATION	SQ. FT.
MAINLINE U.S. 36 (INTERSECTION U.S. 36 & IL. 1)	
LT. & RT. STA. 1682+40 TO 1687+78.6	
WHITE EOP LINES	359.1
1682+40 TO 1687+78.6	
MEDIAN DOUBLE YELLOW LINES	718.1
1682+40 TO 1687+78.6	
EXISTING DIAGANOLS	166.0
IL. 1 (SOUTH LEG)	
LT. & RT. 1475+85.8 TO 1477+26.0	
WHITE EOP LINES	93.5
1475+85.8 TO 1477+26.0	
MEDIAN DOUBLE YELLOW LINES	186.9
1475+85.8 TO 1477+26.0	
EXISTING DIAGANOLS	16.0
IL. 1 (NORTH LEG)	
327+17.8 TO 327+50	
WHITE EOP LINES	21.5
327+17.8 TO 327+50	
MEDIAN DOUBLE YELLOW LINES	42.9
TOTAL	1,604.0

NOTE:
 THE PAVEMENT MARKING REMOVAL QUANTITY IS INTENDED TO REMOVE THE EXISTING PAVEMENT MARKINGS THAT ARE BEYOND THE RESURFACING LIMITS OF THE JOB. QUANTITIES FOR NEW THERMO-PLASTIC PAVEMENT MARKINGS HAVE BEEN INCLUDED FOR THE ABOVE AREAS.

Z0055300

RUMBLE STRIPS

LOCATION	EACH
E.B. U.S. 36 & IL. 1	
WEST OF INTERSECTION	
SEE CADD STANDARD FOR LOCATIONS	
TOTAL	3.0

X4032500

BITUMINOUS MATERIALS (COVER & SEAL COATS) SPECIAL

LOCATION	OFFSET	WIDTH	GALLONS
LT. & RT. 932+29.05 TO 944+84.70	9'	2'	167.42
LT. & RT. 944+84.70 TO 990+71.00	9'	2'	611.51
990+71.00 TO 991+73.00		STRUCTURE OMISSION	
LT. & RT. 991+73.00 TO 1046+26.50	9'	2'	727.13
1046+26.50 TO 1047+27.50		STRUCTURE OMISSION	
LT. & RT. 1047+27.50 TO 1120+32.00	9'	2'	973.93
1120+32.00 TO 1122+12.00		STRUCTURE OMISSION	
LT. & RT. 1122+12.00 TO 1135+25.00	9'	2'	175.07
LT. & RT. 1135+25.00 TO 1144+54.00	9'	2'	123.87
LT. & RT. 1144+54.00 TO 1182+01.75	9'	2'	499.70
1182+01.75 TO 1182+98.25		STRUCTURE OMISSION	
LT. & RT. 1182+98.25 TO 1281+31.00	9'	2'	1,311.03
1281+31.00 TO 1281+43.40		RAILROAD OMISSION	
LT. & RT. 1281+43.40 TO 1338+67.00	9'	2'	763.15
1338+67.00 TO 1339+83.85		STRUCTURE OMISSION	
LT. & RT. 1339+83.85 TO 1522+26.00	9'	2'	2,432.86
1522+26.00 TO 1523+04.00		STRUCTURE OMISSION	
LT. & RT. 1523+04.00 TO 1579+91.00	9'	2'	758.27
1579+91.00 TO 1581+49.00		STRUCTURE OMISSION	
LT. & RT. 1581+49.00 TO 1646+45.00	9	2	866.13
LT. & RT. 1646+45.00 TO 1650+67.50	11'	2'	56.33
1650+67.50 TO 1651+92.50		R.R. UNDERPASS OMISSION	
LT. & RT. 1651+92.50 TO 1656+55.00	11'	2'	61.67
LT. & RT. 1656+55.00 TO 1668+52.00	9'	2'	159.60
LT. & RT. 1668+52.00 TO 1682+40.00	9'	2'	185.07
			9,872.74

ALL OFFSETS SHOULD BE VERIFIED IN FIELD