

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1613	21N	SANGAMON	46	5
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

	ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE
				I000 100% STATE
44000100	PAVEMENT REMOVAL	SQ YD	537	537
44004250	PAVED SHOULDER REMOVAL	SQ YD	189	189
44200094	PAVEMENT PATCHING, TYPE II, 8 INCH	SQ YD	70	70
48101200	AGGREGATE SHOULDERS, TYPE B	TON	77	77
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	201	201
48203100	<i>HOT-MIX ASPHALT</i> SHOULDERS	TON	85	85
50105220	PIPE CULVERT REMOVAL	FOOT	34	34
54200430	PIPE CULVERTS, TYPE 1 RCCP 15"	FOOT	24	24
54200643	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 18"	FOOT	92	92
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2	2
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	10	10
64200105	SHOULDER RUMBLE STRIP	FOOT	1649	1649
67100100 *	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1

* SEE SPECIAL PROVISIONS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
SHEET 3 OF 4
FAS 1613 (OLD US 36) AND
FARMINGDALE ROAD (CH 15)
SECTION 21N
SANGAMON COUNTY
SCALE: VERT. NONE DRAWN BY DJK
 HORIZ. CHECKED BY DBS
DATE: AUGUST, 2004