

SUMMARY OF QUANTITIES

LOCATION OF WORK: IL 10 LINCOLN, IL				100% STATE	
SUMMARY OF QUANTITIES				RURAL	URBAN
PAY CODE	PAY ITEM	UNIT	TOTAL QUANTITY	1000	1000
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	42.1	5.7	36.4
40600300	AGGREGATE (PRIME COAT)	TON	221.5	30.1	191.4
40600895	CONSTRUCTING TEST STRIP	EACH	1		1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	3,150	190	2,960
40600990	TEMPORARY RAMP	SQ YD	808	69	739
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	7,881	996	6,885
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	221		221
42001200	PAVEMENT FABRIC	SQ YD	60		60
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	107,603	14,859	92,744
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	200		200
44200998	CLASS B PATCHES, TYPE III, 12 INCH	SQ YD	20		20
44201000	CLASS B PATCHES, TYPE IV, 12 INCH	SQ YD	40		40
44213200	SAWCUTS	FOOT	192		192
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1,201	268	933
56109210	WATER VALVES TO BE ADJUSTED	EACH	9		9
60255500	MANHOLES TO BE ADJUSTED	EACH	10		10
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	200		200
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	6	1	5
67100100	MOBILIZATION	L SUM	1		1
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1		1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1		1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1		1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1
70 301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4,304	500	3804
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10,330	1,200	9,130

SUMMARY OF QUANTITIES

LOCATION OF WORK: IL 10 LINCOLN, IL				100% STATE	
SUMMARY OF QUANTITIES				RURAL	URBAN
PAY CODE	PAY ITEM	UNIT	TOTAL QUANTITY	1000	1000
70300210	TEMPORARY PAVEMENT MARKING-LETTERS AND SYMBOLS	SQ FT	1,789.9	156	1,633.9
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	49,165	7,330	41,835
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	8,625	728	7,897
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1,909	354	1,555
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	583	101	482
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1,036	138	898
*78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SQ FT	1,789.9	156	1,633.9
*78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	6,320	760	5,560
*78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	8,311	650	7,661
*78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	1,036	138	898
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	674	57	617
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	701	72	629
*88600100	DETECTOR LOOP, TYPE I	FOOT	3,282		3,282
*X7800620	URETHANE PAVEMENT MARKING - LINE 5"	FOOT	42,845	6,570	36,275
*X7800630	URETHANE PAVEMENT MARKING - LINE 6"	FOOT	314	78	236
*X7800640	URETHANE PAVEMENT MARKING - LINE 8"	FOOT	1,909	354	1,555
*X7800650	URETHANE PAVEMENT MARKING - LINE 12"	FOOT	583	101	482
Z0017100	DOWEL BARS	EACH	160		160

* Specialty Items

Rev

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVING SCHEDULE	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwid01\LAUGHLINR1\dms72477\672045-shit-schedule.dgn	DRAWN -	REVISED -	320			103RS-2, 104RS-4	LOGAN	67	3	
PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -	CONTRACT NO.							
PLOT DATE = Apr-10-2009 02:44:29PM	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							