

SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		1000 80% FED 20% STATE	
35650500	BASE COURSE WIDENING 10"	SQ YD	154	154	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	14	14	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	12910	12910	
40600300	AGGREGATE (PRIME COAT)	TON	258	258	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600990	TEMPORARY RAMP	SQ YD	47	47	
40600995	TEMPORARY RAMP, SPECIAL	SQ YD	161	161	
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	6870	6870	
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	5051	5051	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	10	10	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	6426	6426	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	54520	54520	
44004250	PAVED SHOULDER REMOVAL	SQ YD	4362	4362	
44004260	PAVED SHOULDER REMOVAL (SPECIAL)	SQ YD	13630	13630	
44201811	CLASS D PATCHES, TYPE I, 14 INCH	SQ YD	188	188	
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	980	980	
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	210	210	
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	350	350	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	777	777	
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	4362	4362	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1213	1213	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	2	2	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4	4	
67100100	MOBILIZATION	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6845	6845	
70300610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	62	62	
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	52649	52649	
70300635	TEMPORARY PAINT PAVEMENT MARKING LINE 6"	FOOT	219	219	

SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		1000 80% FED 20% STATE	
70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT	335	335	
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	23	23	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	800	800	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	62	62	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4466	4466	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	219	219	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	335	335	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	48183	48183	
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	23	23	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	323	323	