

SUMMARY OF QUANTITIES

FAI 64  
RURAL  
100% STATE  
JEFFERSON COUNTY

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	EASTBOUND LANES	WESTBOUND LANES
				1000 QUANTITY	1000 QUANTITY
X0322729	MATERIAL TRANSFER DEVICE	TON	36,463.0	17,934.0	18,529.0
Z0075310	TIE BARS 3/4"	EACH	<b>2105</b>	<b>1157</b>	<b>948</b>
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	50,511.0	25,002.0	25,509.0
40600300	AGGREGATE (PRIME COAT)	TON	842.0	416.8	425.2
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	24.0	12.0	12.0
40600895	CONSTRUCTING TEST STRIP	EACH	2.0	1.0	1.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	4,891.0	3,890.0	1,001.0
40600985	PORTLAND CONCRETE CEMENT SURFACE REMOVAL - BUTT JOINT	SQ YD	3,392.0	1,513.0	1,879.0
40600990	TEMPORARY RAMP	SQ YD	218.0	99.0	119.0
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, N105 (IL-19.0)	TON	21,983.0	10,813.0	11,170.0
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIXTURE D, N105	TON	14,480.0	7,121.0	7,359.0
44200525	CLASS A PATCHES, TYPE I, 8 INCH	SQ YD	<b>155</b>	<b>50</b>	<b>105</b>
44200529	CLASS A PATCHES, TYPE II, 8 INCH	SQ YD	<b>2470</b>	<b>1271</b>	<b>1199</b>
44200533	CLASS A PATCHES, TYPE III, 8 INCH	SQ YD	<b>1962</b>	<b>717</b>	<b>1245</b>
44200535	CLASS A PATCHES, TYPE IV, 8 INCH	SQ YD	<b>4098</b>	<b>2610</b>	<b>1408</b>
44212900	PAVEMENT PATCHING (PARTIAL DEPTH)	SQ YD	1,262.0	631.0	631.0
44213000	PATCHING REINFORCEMENT	SQ YD	<b>8685</b>	<b>4650</b>	<b>4035</b>
44213200	SAW CUTS	FOOT	<b>35,815</b>	<b>18,179</b>	<b>17,636</b>
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3,197.0	1,549.0	1,648.0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	23,626.0	11,803.0	11,823.0
50102400	CONCRETE REMOVAL	CU YD	0.4	0.2	0.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	2.0	1.0	1.0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	284.0	142.0	142.0
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1700	850	850
* 63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	8	4	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE I(SPECIAL) TANGENT	EACH	8	4	4
63200310	GUARDRAIL REMOVAL	FOOT	1125	550	575
63500105	DELINEATORS	EACH	234.0	110.0	124.0
64200105	SHOULDER RUMBLE STRIP	FOOT	117,364.0	59,488.0	57,876.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5.0	2.5	2.5
67100100	MOBILIZATION	L SUM	1.0	0.5	0.5

\*Specialty Items

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FILE NAME =	USER NAME = mccordkr	DESIGNED -	REVISED -	SCALE: _____ SHEET NO. _____ OF _____ SHEETS STA. _____ TO STA. _____	F.A.I. RTE. 64	SECTION 141-9-41-2-185-1	COUNTY JEFFERSON	TOTAL SHEETS 47	SHEET NO. 5
or \pwork\PIWIDOT\MCCORDKR\dms58145\d9	8099-sht-misc.dgn	DRAWN -	REVISED -		CONTRACT NO. 78099				
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
	PLOT DATE = 2/25/2009	DATE -	REVISED -						

Rev.