

PROPOSED MAINLINE RESURFACING AND SHOULDER SCHEDULE

LOCATION STATION TO STATION	LENGTH (INFORMATION ONLY)	TEMP RAMPS	PCC SURF REMOVAL - BUTT JOINT	HMA SURF REMOVAL - BUTT JT	POLY HMA SUR CSE, MIX D, N105	POLY HMA BINDER CSE, N105, IL-19.0	SHOULDERS				PRIME COAT		NOTES	
							BITUMINOUS		AGGREGATE		BITUMINOUS MATERIALS	AGGREGATE		
							10' OUTSIDE	6' INSIDE	LT. 2' WEDGE	RT. 2' WEDGE				
		SQ YD	SQ YD	SQ YD	TON	TON	TON	TON	TON	TON	GAL	TON		
EASTBOUND														
3003+41.0 TO 3010+66.0	725	14											Mainline	
3003+41.0 TO 3148+78.1	14537				3222	3273	4973	3444	2087	345	345	11630	193.8	Mainline
EQ. STA. 3148+78.06 (BK.) = STA. 3150+00.00 (AH.)														
3150+00.0 TO 3202+83.0	5283					1190	1807					4226	70.4	Mainline
3150+00.0 TO 3184+82.0	3482							825	759	125				
3191+40.0 TO 3202+83.0	1143	9						271			83			
3202+83.0 TO 3204+48.0		14	267								27			SN 041-0081
S. N. 041-0081 - 3202+83 to 3204+48														
3204+48.0 TO 3215+76.0		14	267											SN 041-0081
3221+00.0 TO 3221+19.0		9						267			27			SN 041-0083
S. N. 041-0083 - 3221+19 to 3222+66														
3222+66.0 TO 3313+40.8	1671	20				376	572		240	40		1337	22.3	Mainline
3222+66.0 TO 3313+40.8	9075	19	300											SN 041-0083
3313+40.8 TO 3314+91.0	150					668	2043	2154	1306	215	215	7260	121.0	Mainline
						34	51	35	22	4	4	120	2.0	Mainline
EB SUBTOTALS		99	1,167	3,890	6,916	10,508	6,996	4,414	729	701	24,573	409.5		
WESTBOUND														
3003+41.0 TO 3004+16.0	75	14						18		2				Mainline
3016+37.0 TO 3034+17.0		18				333		421		42				
3040+73.0 TO 3148+78.1								2560		256				
3003+41.0 TO 3148+78.1	14537					3273	4973		2087		345	11630	193.8	Mainline
EQ. STA. 3148+78.06 (BK.) = STA. 3150+00.00 (AH.)														
3150+00.0 TO 3202+70.0	5270					1187	1803	736	757	74	125	4216	70.3	RR Overpass
3150+00.0 TO 3181+08.0								271		27				
3188+39.0 TO 3199+85.0		9												
3199+70.0 TO 3202+70.0		9												
3202+70.0 TO 3204+27.0		23	380											SN 041-0082
S. N. 041-0082 - 3202+70 to 3204+27														
3204+27.0 TO 3220+87.0	1660	18	273			374	568	393	239	39	39	1328	22.1	RR Overpass SN 041-0082
3220+87.0 TO 3222+37.0		14	267											Mainline & Inside shld
S. N. 041-0084 - 3220+87 to 3222+37														
3222+37.0 TO 3313+40.8	9104	14	267			2050	3115	2157	1308	216	216	7283	121.4	Ramp A Taper
3222+37.0 TO 3313+40.8	150					668	34	36	22	4	4	120	2.0	Along Ramp A
WB SUBTOTALS		119	1,187	1,001	6,917	10,510	6,592	4,413	660	729	24,577	409.6		
TOTALS		218	2,354	4,891	13,833	21,018	13,588	8,827	1,389	1,430	49,150	819.2		
							22,415		2,819					