

MAINLINE PAVEMENT MARKING SCHEDULE

EASTBOUND LANE PAVEMENT MARKING

LOCATION STATION TO STATION	PERFORMED		THERMOPLASTIC		PERFORMED		SHORT TERM PAVEMENT MARKING (WHITE)		RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKERS		WORK ZONE PAVEMENT MARKING REMOVAL	NOTES
	LINE 6"		LINE 4"		LINE 8" (ON RAMPS)		MAINLINE SKIP-DASH	SHLDR. SKIP-DASH		CRYSTAL	AMBER		
	WHITE (SKIP-DASH)		SOLID YELLOW (LT EP)	SOLID WHITE (RT EP)	SOLID YELLOW	SOLID WHITE							
	FOOT		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT		EACH	EACH		
Eastbound Lanes Centerline													
3003+41.0 TO 3148+78.1	3634	14537	14537				1163	2326	183	183		12054	Rt., Lt. EP and Centerline SB Lanes
EQ. STA. 3148+78.1 (BK.) = STA. 3150+00.0 (AH.)													
3150+00.0 TO 3184+82.0			3482					279				1252	Rt. EP
3191+40.0 TO 3202+83.0			1143					69					Rt. EP
3150+00.0 TO 3202+83.0	1321	5283					423	423	67	67			Lt. EP and Centerline SB Lanes
S. N. 041-0081													
3204+48.0 TO 3215+76.0			1128					90				406	Rt., Lt. EP and Centerline SB Lanes
3227+33.0 TO 3314+91.0			8758										Rt. EP
3204+48.0 TO 3221+19.0	418	1671					134	134	22	22			Lt. EP and Centerline SB Lanes
S. N. 041-0083													
3222+66.0 TO 3314+91.0	2306	9225					738	1476	116	116		4577	Lt. EP and Centerline SB Lanes
Ramps													
3184+82.0 TO 3191+40.0			660						52	52			Ramp C
3187+88.0 TO 3190+90.0								305					Ramp C
3187+88.0 TO 3191+40.0								355					Ramp C
3190+90.0 TO 3191+40.0					50				2		2		Ramp C
3215+76.0 TO 3221+19.0			543										Ramp D
3222+66.0 TO 3227+33.0			467										Ramp D
3215+76.0 TO 3219+88.0								412					Ramp D
3216+26.0 TO 3217+96.0								170					Ramp D
3217+96.0 TO 3219+88.0								192					Ramp D
3215+76.0 TO 3216+26.0					50								Ramp D (skip-dash)
EASTBOUND TOTALS	7,680	30,717	30,719	100	1,434	2,458	4,797	442	440	2	18,289		
		61,436		1,534		7,255			442				