

SUMMARY OF QUANTITIES

FUNDING
100% STATE
CONSTRUCTION TYPE CODE
SFTY-2A
ALEXANDER
SN 002-0023 & 002-0024

CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	174
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	123
40600990	TEMPORARY RAMP	SQ YD	15
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE MIX "D", N105	TON	21
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	90
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	648
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	26322
48203100	HOT-MIX ASPHALT SHOULDERS	TON	55
50102400	CONCRETE REMOVAL	CU YD	44.3
50157300	PROTECTIVE SHIELD	SQ YD	892
50300255	CONCRETE SUPERSTRUCTURE	CU YD	48.8
50300260	BRIDGE DECK GROOVING	SQ YD	25060
50300300	PROTECTIVE COAT	SQ YD	26400
50300530	FLOOR DRAIN EXTENSION	EACH	758
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	5020
50800515	BAR SPLICERS	EACH	76
52000110	PREFORMED JOINT STRIP SEAL	FOOT	278
64200105	SHOULDER RUMBLE STRIP	FOOT	1155
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	11
67100100	MOBILIZATION	L SUM	1
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	4
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	11
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	700
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	14860
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5190
70400100	TEMPORARY CONCRETE BARRIER	FOOT	3337.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	12925
* 78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	15180
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	80
78300100	PAVEMENT MARKING REMOVAL	SQ FT	495

FUNDING
100% STATE
CONSTRUCTION TYPE CODE
SFTY-2A
ALEXANDER
SN 002-0023 & 002-0024

CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	80
X0321460	PLUG EXISTING DECK DRAINS	EACH	152
X0323644	PAVEMENT MARKING GROOVING	FOOT	15180
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	166
X7010820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	L SUM	1
XZ191200	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/2"	SQ YD	26322
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	26322
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	26
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	6
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	8

*SPECIALTY ITEMS