



NUMBER	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)
1	2	2	0.4
2	4	4	1.8
3	3	3	1.0
4	2	2	0.4
5	5	3	1.7
6	5	3	1.7
7	5	5	2.8
8	1	2	0.2
9	5	5	2.8
10	1	1	0.1
11	4	4	1.8
12	5	6	3.3
13	4	4	1.8
14	4	4	1.8
15	3	3	1.0
16	5	5	2.8
17	1	1	0.1

Notes:  
 The Resident Engineer will determine final patch locations and quantities in the field before bridge deck patching operations begin.  
 Deck Slab Repair (Partial Depth) quantity estimated at 265 Sq Yd (info only).  
 Area of deck repairs shown are estimated. The Engineer shall show actual locations of deck repairs on As-Built plans.

**BILL OF MATERIAL**

Item	Unit	Total
Deck Slab Repair (Full Depth, ty1)	Sq Yd	26

**DECK SLAB REPAIRS  
 ALEXANDER COUNTY  
 S.N. 002-0023 & 002-0024**