

ROUTE: IL 83 (Peterson Road to IL 60 and IL 60 to Lake Cook Road)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	HMA SURF REM 2-1/4" & RESURF	HMA SURF REM (SP) & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
FROM	TO														
Buffalo Grove Road	Arlington Heights Road	NB	1	4	4	16	2			2					
		NB	2	4	4	16	2			2					
		NB	1	4	4	16	2			2					
		NB	2	4	4	16	2			2					
		NB	1	4	4	16	2			2					
		NB	2	4	4	16	2			2					
Arlington Heights Road	IL 53	NB	1	4	4	16	2			2					
		NB	2	4	12	48	5				5				
IL 53	IL 22	NB	1	4	4	16	2			2					
IL 22	Gilmer Road	NB	2	4	4	16	2			2					
		NB	1	4	4	16	2			2					
		NB	2	4	4	16	2			2					
		NB	1	4	4	16	2			2					
Gilmer Road	US 45	NB	CL	2	100	150	17				17				
		NB	1	4	4	16	2			2					
US 45	IL 60	NB	2	6	10	60	7				7				
		NB	1	2	300	450	50		50						
IL 60	Winchester Road	NB		2	100	150	17		17						
		NB		4	4	16	2			2					
		NB		4	4	16	2			2					
		NB		4	4	16	2			2					
		NB		2	100	150	17		17						
Winchester Road	Peterson Road	NB		4	6	24	3			3					
		NB		4	4	16	2			2					
		NB		4	4	16	2			2					

TOTALS:

88
SY

917
SY

116
SY

117
SY

400
FT

40
EACH

FILE NAME =
c:\projects\dl36008\design_aa.dgn

USER NAME = wlgreendp
DESIGNED -
DRAWN -
PLOT SCALE = 100.0000' / IN.
CHECKED -
DATE -
PLOT DATE = 4/10/2008

DESIGNED -
DRAWN -
CHECKED -
DATE -
REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
IL 83

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-020 PP	LAKE	59	38
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

CONTRACT NO. 60E49