


BL062

REVISIONS		
NUMBER	BY	DATE



INDEX TO SHEETS	
SHT. NO.	TITLE
01	COVER SHEET
02	INDEX TO SHEETS/SUMMARY OF QUANTITIES
03	AIRPORT SITE PLAN
04	CONSTRUCTION ACTIVITY PLAN PHASE 1 A-E
05	CONSTRUCTION ACTIVITY PLAN PHASE 1 F-M
06	CONSTRUCTION ACTIVITY PLAN PHASE 2 A-F
07	CONSTRUCTION ACTIVITY PLAN PHASE 2 F-M
08	EXISTING CONDITIONS AND REMOVALS SHEET 1
09	EXISTING CONDITIONS AND REMOVALS SHEET 2
10	EXISTING CONDITIONS AND REMOVALS SHEET 3
11	EXISTING GATE LOCATIONS AND GATE TABLE
12	PROPOSED FENCE IMPROVEMENTS 1
13	PROPOSED FENCE IMPROVEMENTS 2
14	PROPOSED EROSION IMPROVEMENTS AND DETAILS
15	FENCING DETAILS 1
16	FENCING DETAILS 2

SUMMARY OF QUANTITIES			
ITEM NO.	ITEM DESCRIPTION	UNIT	QUANTITY
BASE BID			
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1
AR151420	CLEARING TREES 0-2.5' BUTT. DIA.	EACH	14
AR151429	STUMP REMOVAL 0.0-2.5 FT. DIA.	EACH	14
AR151430	CLEARING TREES 2.5'-5' BUTT. DIA.	EACH	4
AR151431	STUMP REMOVAL 2.5'-5.0 FT. DIAM.	EACH	4
AR800224	REGRADE SWALE	S.Y.	400
AR162324	CLASS E GATE 24'-VINYL	EACH	2
AR162408	CLASS E FENCE, VINYL-8'	L.F.	9200
AR162510	CLASS E FENCE 10'	L.F.	9150
AR162624	CLASS E GATE - 24'	EACH	2
AR162900	REMOVE CLASS E FENCE	L.F.	18700
AR162905	REMOVE GATE	EACH	4
AR901510	SEEDING	ACRE	1
AR908520	EXCELSIOR BLANKET	S.Y.	400
ADDITIVE ALTERNATE #1			
AS162510	CLASS E FENCE 10'	L.F.	1900
AS162624	CLASS E GATE - 24'	EACH	1
AS162900	REMOVE CLASS E FENCE	L.F.	1900
AS162905	REMOVE GATE	EACH	1

BLOOMINGTON-NORMAL AIRPORT AUTHORITY
 CENTRAL ILLINOIS REGIONAL AIRPORT
 BLOOMINGTON, ILLINOIS

UPGRADE PERIMETER FENCE PHASE 2
 INDEX TO SHEETS/SUMMARY OF QUANTITIES

© copyright CMT, Inc.
CMT
 CRAWFORD, MURPHY & TILLY, INC.
 CONSULTING ENGINEERS
 License No. 184-000613



DESIGN BY:	CBG
DRAWN BY:	CMT
CHECKED BY:	CBG
APPROVED BY:	FLW
DATE:	MAY 9, 2008
JOB No:	0708506