## SUMMARY OF QUANTITIES

| ITEM NO. | DESCRIPTION | UNIT | TOTAL QUANTITIES | AS BUILT QUANTITIES |
|---|---|---|---|---|
| AR108158 | 1/C #8 5 KV UG CABLE IN UD | L.F. | 17,607 | |
| AR109210 | VAULT MODIFICATIONS | L.S. | 1 | |
| AR110552 | EXTEND 2-WAY DUCT | L.F. | 19 | |
| AR125505 | MIRL, STAKE MOUNTED | EACH | 40 | |
| AR125510 | MIRL, BASE MOUNTED | EACH | 12 | |
| AR125540 | MI THRESHOLD LIGHT STAKE MTD | EACH | 16 | |
| AR125901 | REMOVE STAKE MOUNTED LIGHT | EACH | 54 | |
| AR125902 | REMOVE BASE MOUNTED LIGHT | EACH | 13 | |
| AR125961 | RELOCATE STAKE MOUNTED LIGHT | EACH | 29 | |
| AR125962 | RELOCATE BASE MOUNTED LIGHT | EACH | 2 | |
| AR125967 | RELOCATE REILS | PAIR | 1 | |
| AR150510 | ENGINEER'S FIELD OFFICE | L.S. | 1 | |
| AR150540 | HAUL ROUTE | L.S. | 1 | |
| AR152410 | UNCLASSIFIED EXCAVATION | C.Y. | 2,931 | |
| AR156510 | SILT FENCE | L.F. | 1,137 | |
| AR156513 | SEPARATION FABRIC | S.Y. | 15,729 | |
| AR156520 | INLET PROTECTION | EACH | 3 | |
| AR156521 | HEADWALL PROTECTION | EACH | 3 | |
| AR156530 | TEMPORARY SEEDING | ACRE | 7.5 | |
| AR156531 | EROSION CONTROL BLANKET | S.Y. | 9,032 | |
| AR209510 | CRUSHED AGGREGATE BASE COURSE | TON | 3,650 | |
| AR401610 | BITUMINOUS SURFACE COURSE | TON | 56 | |
| AR401650 | BITUMINOUS PAVEMENT MILLING | S.Y. | 268 | |
| AR401900 | REMOVE BITUMINOUS PAVEMENT | S.Y. | 129 | |
| AR501506 | 6" PCC PAVEMENT | S.Y. | 14,831 | |
| AR501530 | PCC TEST BATCH | EACH | 1 | |
| AR501900 | REMOVE PCC PAVEMENT | S.Y. | 715 | |
| AR602510 | BITUMINOUS PRIME COAT | GAL. | 33 | |
| AR603510 | BITUMINOUS TACK COAT | GAL. | 69 | |
| AR620520 | PAVEMENT MARKING-WATERBORNE | S.F. | 30,900 | |
| AR620525 | PAVEMENT MARKING-BLACK BORDER | S.F. | 6,605 | |
| AR620900 | PAVEMENT MARKING REMOVAL | S.F. | 6,808 | |
| AR705410 | POROUS BACKFILL | C.Y. | 571 | |
| AR705524 | 4" PERFORATED UNDERDRAIN W/SOCK | L.F. | 9,546 | |
| AR705631 | UNDERDRAIN INSPECTION HOLE, TY A | EACH | 3 | |
| AR705632 | UNDERDRAIN INSPECTION HOLE, TY B | EACH | 9 | |
| AR705633 | UNDERDRAIN INSPECTION HOLE, TY C | EACH | 4 | |
| AR705900 | REMOVE UNDERDRAIN | L.F. | 55 | |
| AR705903 | REMOVE UNDERDRAIN INSP. HOLE | EACH | 17 | |
| AR901510 | SEEDING | ACRE | 7.5 | |
| AR908510 | MULCHING | ACRE | 5.7 | |

## INDEX TO SHEETS


| SHEET NO. | DESCRIPTION |
|---|---|
| 1 | COVER SHEET |
| 2 | SUMMARY OF QUANTITIES AND INDEX TO SHEETS |
| 3 | PROPOSED SAFETY PLAN |
| 4 | PROPOSED SEQUENCING PLAN |
| 5 | PROPOSED STORMWATER POLLUTION PREVENTION PLAN STA. 146+00 TO STA. 122+00 |
| 6 | PROPOSED STORMWATER POLLUTION PREVENTION PLAN STA. 122+00 TO STA. 109+00 |
| 7 | PROPOSED CONSTRUCTION PLAN STA. 160+00 TO STA. 147+00 |
| 8 | PROPOSED CONSTRUCTION PLAN STA. 147+00 TO STA. 123+00 |
| 9 | PROPOSED CONSTRUCTION PLAN STA. 123+00 TO STA. 109+00 |
| 10 | PROPOSED STAKING PLAN STA. 160+00 TO STA. 147+00 |
| 11 | PROPOSED STAKING PLAN STA. 147+00 TO STA. 123+00 |
| 12 | PROPOSED STAKING PLAN STA. 123+00 TO STA. 109+00 |
| 13 | PROPOSED JOINTING PLAN STA. 160+00 TO STA. 147+00 |
| 14 | PROPOSED JOINTING PLAN STA. 147+00 TO STA. 123+00 |
| 15 | PROPOSED JOINTING PLAN STA. 123+00 TO STA. 109+00 |
| 16 | PROPOSED INTERSECTION JOINTING DETAILS |
| 17 | PROPOSED JOINTING DETAILS |
| 18 | PROPOSED DRAINAGE PLAN STA. 160+00 TO STA. 147+00 |
| 19 | PROPOSED DRAINAGE PLAN STA. 147+00 TO STA. 123+00 |
| 20 | PROPOSED DRAINAGE PLAN STA. 123+00 TO STA. 109+00 |
| 21 | EXISTING ELECTRICAL PLAN STA. 160+00 TO STA. 147+00 |
| 22 | EXISTING ELECTRICAL PLAN STA. 147+00 TO STA. 123+00 |
| 23 | EXISTING ELECTRICAL PLAN STA. 123+00 TO STA. 109+00 |
| 24 | PROPOSED ELECTRICAL PLAN STA. 160+00 TO STA. 147+00 |
| 25 | PROPOSED ELECTRICAL PLAN STA. 147+00 TO STA. 123+00 |
| 26 | PROPOSED ELECTRICAL PLAN STA. 123+00 TO STA. 109+00 |
| 27 | PROPOSED ELECTRICAL PLAN FOR HOMERUNS |
| 28 | ELECTRICAL LEGEND AND ABBREVIATIONS |
| 29 | NEW ELECTRICAL ONE LINE FOR VAULT |
| 30 | AIRFIELD LIGHTING WIRING SCHEMATIC |
| 31 | HIGH VOLTAGE WIRING SCHEMATIC |
| 32 | VAULT FLOOR PLAN & ELEVATIONS |
| 33 | LEGEND PLATE SCHEDULE & GROUNDING DETAILS |
| 34 | PROPOSED REIL DETAILS |
| 35 | EXISTING REIL WIRING DIAGRAM |
| 36 | PROPOSED ELECTRICAL DETAILS SHEET 1 |
| 37 | PROPOSED ELECTRICAL DETAILS SHEET 2 |
| 38 | ELECTRICAL NOTES SHEET 1 |
| 39 | ELECTRICAL NOTES SHEET 2 |
| 40 | PROPOSED MARKING PLAN STA. 160+00 TO STA. 147+00 |
| 41 | PROPOSED MARKING PLAN STA. 147+00 TO STA. 123+00 |
| 42 | PROPOSED MARKING PLAN STA. 123+00 TO STA. 109+00 |
| 43 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 109+00 TO STA. 110+00 |
| 44 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 110+50 TO STA. 111+50 |
| 45 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 112+00 TO STA. 113+00 |
| 46 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 113+50 TO STA. 114+50 |
| 47 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 115+00 TO STA. 116+00 |
| 48 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 116+50 TO STA. 117+50 |
| 49 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 118+00 TO STA. 118+87.50 |
| 50 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 119+00 TO STA. 119+50 |
| 51 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 120+00 TO STA. 121+00 |
| 52 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 121+50 TO STA. 122+50 |
| 53 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 123+00 TO STA. 124+00 |
| 54 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 124+50 TO STA. 125+50 |
| 55 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 126+00 TO STA. 127+00 |
| 56 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 127+50 TO STA. 128+50 |
| 57 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 129+00 TO STA. 130+00 |
| 58 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 130+50 TO STA. 131+50 |
| 59 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 132+00 TO STA. 133+00 |
| 60 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 133+50 TO STA. 134+50 |
| 61 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 135+00 TO STA. 136+00 |
| 62 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 136+50 TO STA. 137+50 |
| 63 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 138+00 TO STA. 139+00 |
| 64 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 139+50 TO STA. 140+50 |
| 65 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 141+00 TO STA. 142+00 |
| 66 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 142+50 TO STA. 143+50 |
| 67 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 144+00 TO STA. 145+00 |
| 68 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 145+50 TO STA. 146+50 |
| 69 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 147+00 TO STA. 148+00 |
| 70 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 148+50 TO STA. 149+50 |
| 71 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 150+00 TO STA. 151+00 |


## INDEX TO SHEETS


| SHEET NO. | DESCRIPTION |
|---|---|
| 72 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 151+50 TO STA. 152+50 |
| 73 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 153+00 TO STA. 154+00 |
| 74 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 154+50 TO STA. 155+50 |
| 75 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 156+00 TO STA. 157+00 |
| 76 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 157+50 TO STA. 158+50 |
| 77 | PROPOSED CROSS-SECTIONS FOR RUNWAY 11/29 WIDENING STA. 159+00 TO STA. 160+00 |
| 78 | EARTHWORK VOLUME TABLES |


| DATE | REVISION | BY |
|---|---|---|
| 04/11/08 | REVISED AS PER IDA REVIEW | GAH |

EFFINGHAM COUNTY
MEMORIAL AIRPORT
EFFINGHAM, ILLINOIS

IL. PROJ.: 1H2-3761 A.I.P. PROJ.: 3-17-0040-B11

HG Project No. 07A01430.0800
Filename R-002FLP.DWG
Scale NOT TO SCALE
Date 02/12/08

| | | |
|---|---|---|
| LAYOUT | KDM | 11/28/07 |
| DRAWN | BAK | 11/28/07 |
| REVIEWED | CAH | 02/12/08 |

HANSON
Hanson Professional Services Inc.
1525 South Sixth Street
Springfield, Illinois 62703-2886
Offices Nationwide

WIDEN RUNWAY 11/29
AND REPLACE MIRL'S

SUMMARY OF QUANTITIES
AND
INDEX TO SHEETS

2



Apr 11, 2008 1:21 PM HAGL000382
...\AIRPORTS\EFFINGHAM\07A01430\CAD\SHEETS\R-002FLP.DWG - Layout1