

QUANTITIES				
ITEM No.	DESCRIPTION	UNIT	QUANTITY	AS BUILT QUANTITY
AR162960	RELOCATE CLASS E FENCE	L.F.	168	
AR162963	RELOCATE GATE 5'	EACH	(SHEET 4)	
AR162964	RELOCATE GATE	EACH	(SHEET 4)	
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	13	

COORDINATE DATA				
ID.	STATION	OFFSET	NORTHING	EASTING
1	0+38	87' LT.	729394.11	950300.47
2	1+97	87' LT.	729553.26	950299.50
3	1+97	72' LT.	729553.41	950314.50
4	2+18	72' LT.	729574.28	950314.45

- LEGEND**
- EXISTING PAVEMENT
  - EXISTING BUILDING
  - EXISTING PROPERTY LINE
  - EXISTING CLASS E FENCE
  - EXISTING INLET
  - EXISTING AIRPORT ROTATING BEACON
  - PROPOSED P.C.C. PAVEMENT
  - PROPOSED CLASS E FENCE

**FENCING NOTES**

THE PROPOSED RELOCATED CLASS "E" FENCE (4' HIGH) WILL BE INSTALLED AT THE LOCATIONS SHOWN ON THIS SHEET AND IN ACCORDANCE WITH THE DETAILS SHOWN IN THE SPECIAL PROVISIONS.

THIS ITEM OF WORK WILL BE PAID FOR UNDER ITEM:  
AR162960 "RELOCATE CLASS E FENCE" - PER L.F.

THE EXISTING CLASS "E" MANUAL WALKWAY GATE WILL BE REINSTALLED AT THE LOCATION SHOWN ON THIS SHEET AND IN ACCORDANCE WITH THE DETAILS SHOWN IN THE SPECIAL PROVISIONS.

THIS ITEM OF WORK WILL BE PAID FOR UNDER ITEM:  
AR162963 "RELOCATE GATE 5'" - PER EACH.

THE EXISTING CLASS "E" 22' ELECTRIC SLIDE GATE WILL BE REINSTALLED AT THE LOCATION SHOWN ON THIS SHEET AND IN ACCORDANCE WITH THE DETAILS SHOWN IN THE SPECIAL PROVISIONS.

THIS ITEM OF WORK ALSO INCLUDES THE RELOCATION OF THE CARD READER AND THE REPLACEMENT OF THE GATE OPERATOR. (SEE SPECIFICATIONS FOR DETAILS.)


THIS ITEM OF WORK WILL BE PAID FOR UNDER ITEM:  
AR162964 "RELOCATE GATE" - PER EACH.

THE CONTRACTOR WILL ALSO PLACE CA-6 CRUSHED AGGREGATE UNDER & ALONG THE RELOCATED FENCE AT A DEPTH OF 6" AND APPROXIMATELY 24" IN WIDTH.

THIS ITEM OF WORK WILL BE PAID FOR UNDER ITEM:  
AR209510 "CRUSHED AGGREGATE BASE COURSE" - PER TON.

THE LOCATION, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ON THE PLANS IS NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.

CALL J.U.L.I.E. FOR UTILITY INFORMATION AT 1-800-892-0123.



BY: \_\_\_\_\_ DATE: \_\_\_\_\_

REVISION: \_\_\_\_\_

FLORA AIRPORT  
FLORA, ILLINOIS

IL. PROJ.: FDA-3758 A.I.P. PROJ.: 3-17-0044-B14

07A0122D-0800  
R-171FEN.DWG  
Scale: 1" = 10'  
Date: 01/04/08

LAYOUT	CCC	01/04/08
DRAWN	CCC	01/04/08
REVIEWED	CAH	01/25/08

**HANSON**  
Hanson Professional Services Inc.  
1925 South Sixth Street  
Springfield, Illinois 62703-2886  
Offices Nationwide

EXPAND  
HANGAR PAVEMENT  
PROPOSED FENCE PLAN

10

10 of 15 sheets