


- NOTES**
1. ALL VAULT WORK AND/OR POWER OUTAGES SHALL BE COORDINATED WITH THE AIRPORT MANAGER.
 2. ALL ELECTRICAL EQUIPMENT SHALL BE INSTALLED IN CONFORMANCE WITH NFPA 70-NATIONAL ELECTRICAL CODE (NEC) MOST CURRENT ISSUE IN FORCE, THE RESPECTIVE EQUIPMENT MANUFACTURER'S DIRECTIONS AND ALL OTHER APPLICABLE LOCAL CODES, LAWS, ORDINANCES AND REQUIREMENTS IN FORCE. ANY INSTALLATIONS WHICH VOID THE U.L. LISTING, ETL LISTING, (OR OTHER THIRD PARTY LISTING) AND/OR THE MANUFACTURER'S WARRANTY OF A DEVICE SHALL NOT BE PERMITTED.
 3. ALL EQUIPMENT SHOWN NOT LABELED AS EXISTING IS NEW.
 4. HIGH VOLTAGE & LOW VOLTAGE CIRCUITS SHALL NOT BE INSTALLED IN THE SAME WIREWAY, CONDUIT, DUCT, OR HANDHOLE.
 5. LTFMC DENOTES LIQUID TIGHT FLEXIBLE METAL CONDUIT UL LISTED, SUNLIGHT RESISTANT, & SUITABLE FOR GROUNDING. LIQUID TIGHT FLEXIBLE METAL CONDUIT AND ASSOCIATED FITTINGS SHALL BE U.L. LISTED TO MEET THE REQUIREMENTS OF NEC 350.6. LIQUID TIGHT FLEXIBLE METAL CONDUIT THAT IS USED FOR FLEXIBILITY (INCLUDING CONNECTIONS TO CCR'S & TRANSFORMERS) SHALL REQUIRE AN EXTERNAL BONDING JUMPER OR INTERNAL EQUIPMENT GROUNDING CONDUCTOR PER NEC 350.60. EXTERNAL BONDING JUMPERS USED WITH CCR INSTALLATIONS SHALL BE #6 AWG COPPER (MINIMUM). DO NOT INSTALL LTFMC THAT IS NOT UL LISTED.
 6. ALL WORK SHOWN ON THIS SHEET SHALL BE PAID FOR UNDER ITEM AR162964 - RELOCATE GATE.

BY	
REVISION	
DATE	

FLORA AIRPORT
FLORA, ILLINOIS

IL PROJ.: FOA-3756 A.I.P. PROJ.: J-17-0044-B14

HEL Project No.	07A0122D_0800
Drawings	E-601.DWG
Scale	N/A
Date	01/29/08
LAYOUT	KNL 01/28/08
DRAWN	MY 01/29/08
REVIEWED	CAH 01/29/08



EXPAND
HANGAR PAVEMENT

ELECTRICAL ONE LINE
DIAGRAM FOR
GATE OPERATOR

ELECTRICAL ONE LINE DIAGRAM FOR GATE OPERATOR

MAP 12, 2008 8:10 AM HAGL000382
I:\AIRPORTS\FLORA\07A0122\CAD\SHEETS\F-601.DWG - Layout1