

FOR TEMPORARY PAVEMENT CONSTRUCTION USE HIGHWAY STANDARDS NO. 701601 & 701701

FOR STORM SEWER AND WATER MAIN CONSTRUCTION USE HIGHWAY STANDARDS NO. 701101 & 701106

ROAD CONSTRUCTION AHEAD SIGNAGE [W20-1(0)] SHALL BE IN ACCORDANCE WITH IDOT DISTRICT 1 DETAIL TC-10 NOTES

1. EXISTING LANE CONFIGURATIONS ARE TO REMAIN IN OPERATION DURING THIS STAGE OF CONSTRUCTION.

2. SEE TEMPORARY PAVEMENT DETAIL ON MAINTENANCE OF TRAFFIC DETAILS SHEET.

DESIGNED PJO	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	MAINTENANCE OF TRAFFIC - PRE-STAGE 1 New York Street	F.A.P. RTE. SECTION	COUNTY TOTAL SHEET
DRAWN KES	REVISED -			338 (112 & 113) WRS-7	DUPAGE 1156 114
CHECKED JCM	REVISED -				CONTRACT NO. 60R30
DATE 12/14/2012	REVISED -		SCALE: AS SHOWN SHEET NO. 25 OF 195 SHEETS STA. 87+00 TO STA. 97+00	ILLINOIS FED.	AID PROJECT

