


NOTES

1. FOR PROPOSED PAVEMENT, CURB & GUTTER, AND PROFILE INFORMATION SEE PLAN / PROFILE NORTH AURORA ROAD.
2. FOR PROPOSED PAVEMENT MARKING & SIGNAGE INFORMATION SEE PAVEMENT MARKING AND SIGNING NORTH AURORA ROAD.
3. THE 6 INCH SIDE CURB ADJACENT TO SIDEWALK RAMPS SHALL BE INCLUDED IN THE MEASURED AREA FOR PAYMENT FOR "PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH". THE 6 INCH SIDE CURB SHALL BE IN ACCORDANCE WITH IDOT HIGHWAY STANDARDS 424001 & 424006.

4. LIMITS OF SIDE CURB SHOWN ON THE PLANS ARE ESTIMATED. ACTUAL LIMITS SHALL BE DETERMINED BY THE ENGINEER IN THE FIELD. ANY ADDITIONAL LENGTH OF SIDE CURB SHALL BE INCLUDED IN THE MEASURED AREA FOR PAYMENT FOR PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH.
5. THE EXISTING SIDEWALK INDICATED ON THE PLANS SHALL NOT BE REMOVED. ANY DAMAGE TO THE SIDEWALK BY THE CONTRACTOR, AS DETERMINED BY THE ENGINEER, SHALL BE REMOVED AND REPLACED BY THE CONTRACTOR AT THE CONTRACTOR'S OWN EXPENSE. NO ADDITIONAL COMPENSATION WILL BE ALLOWED FOR THIS WORK.

LEGEND

- DETECTABLE WARNINGS
- PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH
- PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH
- PORTLAND CEMENT CONCRETE SIDEWALK 10 INCH, SPECIAL



| | | | | | | | | | | |
|--|------------------------|---------------------------------|---|---|---------------------------|-------------------|--------|--------------|-----------|--|
| | DESIGNED <i>PJO</i> | REVISED - ADDENDUM A 02/20/2013 | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SIDEWALK / SHARED-USE PATH DETAILS NORTH AURORA ROAD | F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. | |
| | DRAWN <i>KES</i> | REVISED - | | | 338 | (112 & 113) WRS-7 | DUPAGE | 1156 | 356 | |
| | CHECKED <i>JCM</i> | REVISED - | | | CONTRACT NO. 60R30 | | | | | |
| | DATE <i>12/14/2012</i> | REVISED - | | | ILLINOIS FED. AID PROJECT | | | | | |

SCALE: AS SHOWN | SHEET NO. 31 OF 32 SHEETS | STA. 406+50 TO STA. 412+00