

STR. NUM.	STATION	OFFSET	RIM ELEVATION	N INVERT	NE INVERT	E INVERT	SE INVERT	S INVERT	SW INVERT	W INVERT	NW INVERT	EXISTING MANHOLES EACH	EXISTING CATCH BASINS EACH	EXISTING INLETS EACH	EXISTING FL END SEC EACH	COMMENTS
100	3900+12.40	59.87 RT	697.63						694.08					X		
101	3899+99.47	53.23 RT	698.69		693.89					693.89				X		REPLACE WITH CLOSED LID
102	3900+07.71	52.58 LT	698.64			693.49					692.84			0		
103	3900+13.90	57.78 LT	699.07	692.07			692.42					0				
104	3903+68.76	53.13 RT	693.87							691.72				X		
105	3903+67.23	1.40 LT	694.99			691.44				691.44				X		
106	3903+67.55	52.66 LT	694.02		691.02	691.02							0			
107	3903+82.11	57.75 LT	694.45	690.35			690.80	690.55				0				
108																STRUCTURE OFFSITE
109	3905+48.17	57.79 LT	689.41					689.41	689.61			0				
110	3905+71.54	53.21 RT	692.66							690.73				X		
111	3905+71.70	5.89 LT	693.43			690.28					690.28			X		
112	3906+01.48	66.69 LT	693.30	688.60			689.15	688.60				0				
113	3907+70.89	94.19 LT	692.03						689.58					X		
114	3906+44.17	102.80 LT	692.16	688.61			688.56							X		
115	3906+39.28	102.13 RT	693.17	688.27			688.02			688.02		0				
116	3906+46.29	180.64 LT	693.29						689.04					X		
117	3907+33.53	306.73 LT	693.13			690.33		689.33		690.33			X			
118	3906+32.71	293.43 LT	693.05	687.53					687.65					X		
119	3906+13.57	298.19 LT										0				SURVEY MISSED
120	95+80.54	62.87 RT	693.25					689.20					X			
121	94+53.86	43.83 LT	694.20						690.85					X		
122	94+11.08	4.50 LT	695.77		689.87		689.57							X		
123	94+57.32	61.15 RT	694.06				689.36			689.36			X			
131	93+26.54	54.93 RT	694.41					690.91						X		
132	93+25.42	65.50 RT	926.23	689.03		686.23		687.48		686.23		0				
135	91+84.91	5.55 RT	696.64		***	685.44		688.39		685.44		0				
145	3930+68.96	87.22 LT	708.17							705.17				X		
150	3941+72.30	65.42 RT	711.41							707.82				X		
151	3941+73.58	61.41 RT	711.57			707.47		707.27				X				
152	3941+23.49	64.66 RT	711.24							707.69				X		
153	3941+23.90	57.04 RT	711.48	707.28		707.03		707.23					X			
154	3940+92.67	69.69 RT	710.49						707.64					X		
155	3940+86.18	65.10 RT	711.07		707.27				707.47				X			
156	3940+70.11	55.42 RT	711.32	707.22	707.47					707.57			X			
157	3940+72.85	7.30 LT	712.14			706.59				706.59				X		
158	3940+71.60	39.24 LT	711.72			706.07			706.07				X			
159	3940+64.60	52.76 LT	709.44	***			704.59						X			
160	3940+23.36	64.67 RT	710.59							707.99				X		
161	3940+24.55	53.63 RT	711.26			707.66		707.46					X			
162	3939+66.30	64.75 RT	710.92							707.62				X		
163	3939+66.45	85.59 RT	711.08	707.68		707.78				707.88		X				
164	3939+66.00	11.30 RT	711.43			706.38				706.38				X		
165	3939+66.11	43.83 LT	711.23		705.83					705.73			X			
166	3939+13.23	64.53 RT	710.52							708.17				X		
167	3939+14.41	52.48 RT	710.88			707.08		707.38				X				
168	3938+59.39	63.02 RT	710.61							707.51				X		
169	3938+59.53	52.51 RT	810.80	807.30		707.80					707.70	X				
170	3938+68.45	11.27 RT	711.12				706.92				706.92			X		
171	3938+86.38	48.26 LT	710.82				707.52							X		
172	3938+81.45	44.06 LT	711.12				705.07		704.82	707.37	X					
173	3938+01.67	51.08 LT	710.52						706.42					X		
174																STRUCTURE OFFSITE
175	3937+59.07	56.77 RT	710.33							707.73				X		
176	3937+58.99	53.23 RT	710.55			707.35			707.65				X			
177	3937+46.20	11.40 RT	710.72				706.02			706.02				X		
178	3937+29.45	51.10 LT	710.22				707.97							X		
179	3937+26.84	47.09 LT	710.50			704.75			704.50	706.85			X			
180	3937+22.44	55.80 LT	710.48	702.73	***			702.73					X			
181	3936+73.11	10.91 RT	710.78							706.63				X		
182																STRUCTURE OFFSITE
183	3936+64.21	7.27 LT	710.89		706.79		706.79			706.89	X					
184	3936+87.96	51.16 LT	710.03				703.98		703.93				X			

X - STRUCTURE TO BE REMOVED
0 - STRUCTURE TO REMAIN
*** - UNKNOWN INVERT

DESIGNED <i>PJO</i>	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	EXISTING DRAINAGE STRUCTURE SCHEDULE OF QUANTITIES		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
DRAWN <i>KES</i>	REVISED -				338	(112 & 113) WRS-7	DUPAGE	1156	411
CHECKED <i>JCM</i>	REVISED -				SC-01		CONTRACT NO. 60R30		
DATE <i>12/14/2012</i>	REVISED -				ILLINOIS FED. AID PROJECT				
			SCALE: AS	SHEET NO. 1 OF 9 SHEETS	STA.	TO STA.			