

STR. NUM.	STATION	OFFSET	RIM ELEVATION	N INVERT	NE INVERT	E INVERT	SE INVERT	S INVERT	SW INVERT	W INVERT	NW INVERT	EXISTING MANHOLES EACH	EXISTING CATCH BASINS EACH	EXISTING INLETS EACH	EXISTING FL END SEC EACH	COMMENTS
30	392+11.45	60.05 RT	706.53							704.38				X		
31																STRUCTURE OFFSITE
32	391+29.76	67.92 RT	706.53			701.93		701.53		701.73			0			
33	389+96.05	66.78 RT	706.24				700.79		700.79			0				
43	388+25.28	27.53 RT	709.93						***				X			
44	387+96.67	37.03 RT	707.18					707.18							X	
45	387+30.46	50.79 RT	706.88					706.88							X	
46	387+02.28	64.41 RT	708.71		***						***			X		
55	401+83.17	8.39 RT	704.09					701.49						X		
56	401+83.70	35.89 RT	703.62				700.32						X			
57	401+91.12	39.72 RT	704.12			700.42					700.42	X				
58	403+12.95	46.64 LT	703.62					700.37						X		
59	403+11.61	9.71 RT	703.75	699.90				699.90					X			
60	403+12.60	37.10 RT	703.19	699.64		699.64						X				
61	403+21.30	40.94 RT	703.87			699.07				699.07	699.67	X				
62	404+69.70	47.85 LT	702.39					699.49					X			
63	404+69.21	40.06 LT	702.56	699.36				699.06					X			
64	404+67.39	33.81 RT	702.42	698.47			698.42						X			
65	405+88.99	35.73 LT	702.03					699.23						X		
66	405+88.37	31.13 RT	***	***		***							X			
67	406+07.42	33.61 RT	702.30			696.30				696.40			X			
68	407+63.17	32.25 LT	700.92					697.92						X		
69	407+64.17	29.54 RT	700.73	697.38			696.73						X			
70	407+73.29	32.73 RT	701.55		696.50	695.95				695.95		X				
71																STRUCTURE NUMBER NOT USED
79	413+22.06	29.09 RT	699.47	695.37									0			
80	413+13.98	70.29 LT	692.35					690.85						0		
81	413+23.21	28.50 LT	699.44	***		***		***			695.54	0				
82	412+10.41	29.32 RT	698.81	695.71									X			
83	412+10.66	28.39 LT	698.91			***		***		***		0				
84	410+64.44	29.34 RT	699.59	696.24				***					X			
85	410+63.49	28.43 LT	699.59			***		***		***		0				
86	409+19.56	29.33 RT	700.35	695.70									X			
87	409+21.03	40.52 LT	700.07					697.82						X		
88	409+20.56	28.23 LT	700.38	697.78		***		***		***		0				
89	408+15.88	30.12 LT	700.83	693.23		***				***		0				
										TOTAL	76	181	136	17		

X - STRUCTURE TO BE REMOVED
0 - STRUCTURE TO REMAIN
*** - UNKNOWN INVERT

DESIGNED <i>PJO</i>	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	EXISTING DRAINAGE STRUCTURE SCHEDULE OF QUANTITIES		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
DRAWN <i>KES</i>	REVISED -				338	(112 & 113) WRS-7	DUPAGE	1156	419	
CHECKED <i>JCM</i>	REVISED -				SC-09		CONTRACT NO. 60R30			
DATE <i>12/14/2012</i>	REVISED -				SCALE: NONE	SHEET NO. 9 OF 9 SHEETS	STA.	TO STA.		
ILLINOIS FED. AID PROJECT										