

ITEM	UNIT	TOTAL	IL 59 @ NEWYORK ST/ AURORA AVE.	AURORA AVE. @ NAPER PLAZA/ WESTRIDGE CT.	IL 59 @ MEIJER WESTRIDGE COURT ENTR.	IL 59 @ LIBERTY ST/ JEFFERSON AVE.	LIBERTY ST. @ COMMERCIAL DRIVEWAY (MEIJER)	IL 59 @ MERIDIAN PKWY/ GLACIER PARK DR.	IL 59 @ NORTH AURORA RD.	IL 59 @ NORTH AURORA RD. FAIRWAY DR. *	PUMP STATION #47	NORTH AURORA INTERCONNECT *	IL 59 INTERCONNECT CONTRACT 60R30
SIGN PANEL - TYPE 1	SQ FT	405	90		30	90		90	90	15			
SIGN PANEL - TYPE 2	SQ FT	24								24			
SERVICE INSTALLATION - GROUND MOUNTED	EACH	5	1		1	1		1	1				
UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA	FOOT	11,850	1406		785	1002		886	2013	551			5227
UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA	FOOT	445	59		23				284	79			
UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA	FOOT	285			64	67		121		33			
UNDERGROUND CONDUIT, GALVANIZED STEEL, 3 1/2" DIA	FOOT	133	67						66				
UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA	FOOT	5,179	1550		639	640		660	1410	280			
HANDHOLE	EACH	43	8		5	5		5	12	2			6
HEAVY-DUTY HANDHOLE	EACH	21	4		4	4		4	4	1			
DOUBLE HANDHOLE	EACH	17	5		2	2		2	5	1			
ELECTRIC CABLE IN CONDUIT, 800V (XLP TYPE USE) 3-1C NO. 8, 1C NO. 8 GROUND	FOOT	237								237			
LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	1								1			
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2									1		1
TRANSCIVER - FIBER OPTIC	EACH	7	1		1	1		1	1	1	1		
FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F 5M12F	FOOT	853										852.5	
ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	11,614										852.5	10761
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	14,361	3865		1661	1735		1785	3572	1743			
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	24,352	6977		2539	2902		2973	6448	2513			
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	23,998	6140		2981	3753		3837	5774	1514			
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	15,874	4033		1925	2021		2096	3797	2002			
ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	32,599	8637		2235	3793		6148	6698	3090			
ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 4 2 C	FOOT	504								504			
ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 3 2 C	FOOT	257	58		44	65		49	41				
ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	7,774	1392		851	894		932	2425	1280			
TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	12	4		2				4	2			
TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	1							1				
STEEL MAST ARM ASSEMBLY AND POLE, 60 FT.	EACH	1								1			
STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 48 FT.	EACH	1								1			
STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 48 FT.	EACH	2	2										
STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 50 FT.	EACH	1			1								
STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 56 FT.	EACH	2	2										
STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 60 FT.	EACH	1			1								
STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 48 FT. AND 22 FT.	EACH	1							1				
STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 52 FT. AND 18 FT.	EACH	1			1								
STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 54 FT. AND 36 FT.	EACH	1				1							
CONCRETE FOUNDATION, TYPE A	FOOT	116	20		20	20		20	24	12			
CONCRETE FOUNDATION, TYPE C	FOOT	24	4		4	4		4	4	4			
CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	211	26		47	32		32	60	14			
CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	172	42		21	46		42		21			
DRILL EXISTING HANDHOLE	EACH	5								3			
SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	72	12		10	14		14	16	6			
SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1			1								
SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	11	4		1				4	2			

\* 100% COST TO THE CITY OF NAPERVILLE

\*\* 50% COST TO THE CITY OF NAPERVILLE  
50% COST TO THE CITY OF AURORA

FILE NAME *	USER NAME * #USER#	DESIGNED - DW	REVISED Addendum A 02/20/2013
K:\Projects\090809\Design\Sheet Files\671\wps00.dgn		DRAWN - JDH	REVISED -
		CHECKED - KMM	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

TRAFFIC SIGNALS  
SUMMARY OF QUANTITIES

SCALE: SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	(112 & 113) WRS-7	DUPAGE	1156	593
TS-1			CONTRACT NO. 60R30	
[ILLINOIS] FED. AID PROJECT				