PLAN
SURVEYED
PLOTTED
CROSS CHECKED
BM. NOTED
NOTE BOOK
NO.
BY
DATE

PROFILE
SURVEYED
PLOTTED
CROSS CHECKED
BM. NOTED
STRUCTURE NOTATYNS CKHD
NOTE BOOK
NO.
BY
DATE

EXISTING R.O.W.
PROPOSED R.O.W.
~ PROPOSED IL RTE 59
DREXELL AVE.
MEIJER DRIVE
STA. 3926+33.87 ILLINOIS ROUTE 59 =
STA. 100+00.00 MEIJER DRIVE
STA. 3926+16.85 ILLINOIS ROUTE 59 =
STA. 100+00.00 SHOPPING CENTER DR.
PROPOSED R.O.W.
RB-04
RB-05
3915+00
3920+00
3925+00
ILLINOIS ROUTE 59
MATCH LINE STA. 3914+00
MATCH LINE STA. 3928+00
RW-04
RW-05
RW-06
RB-06
PROPOSED R.O.W.
PROPOSED R.O.W.
EXISTING R.O.W.
PROPOSED RETAINING WALL (TYP.)
PROPOSED RETAINING WALL (TYP.)
SHOPPING CENTER DR.
MEIJER DRIVE
STA. 3926+33.87
~ SHOPPING CENTER DR.
STA. 3926+16.85
N
50 0 50 100
HORIZONTAL SCALE: 1"=50'-0"
5 0 5 10
VERTICAL SCALE: 1"=5'-0"

RB-04
3916+87
42.0' Left
701.1

	N	Qu	W%
TOPSOIL AS	-		15
	10	4.0S	20
CLAY LOAM FILL (A-6)	9	1.5B	18
	12	1.0P	21
	19	6.4B	18
	14	4.7B	18
CLAY (A-6)	16	4.7S	18
	16	3.8B	16
	15	4.4B	17

EOB

RW-04
3920+65
62.0' Right
703.5

	N	Qu	W%
TOPSOIL AS	-		26
	17	2.25B	29
SILTY CLAY (A-6)	11	1.5P	29
SILTY CLAY LOAM (A-4)	10	0.25P	24
	15	2.5B	15
CLAY LOAM (A-6)	14	0.5B	16
	16	2.2B	17
CLAY (A-6)	12	2.2B	19
CLAYEY SAND & GRAVEL (A-2)	39	2.0P	16

EOB

RB-05
3923+00
37.0' Left
705.9

	N	Qu	W%
TOPSOIL AS	-		28
	12	5.9B	18
CLAY LOAM FILL (A-6)	13	4.3B	13
	13	4.8B	12
	20	2.5S	10

EOB

RB-06
3925+38
61.5' Right
706.3

	N	Qu	W%
TOPSOIL AS	-		24
CLAY LOAM FILL (A-6)	8	4.5+P	13
SILTY CLAY (A-6)	11	2.8B	26
LOAM (A-4)	9	1.25P	15
	10	4.2B	13
	12	4.0B	13
CLAY (A-6)	15	5.5B	17
	18	3.5B	18
	10	2.3S	14

EOB

710 705 700 695 690 685 680

698.77 699.27 699.77 700.27 700.77 701.27 701.77 702.27 702.77 703.27 703.77 704.25 704.63 704.90 705.08 705.26 705.43 705.61 705.78 705.96 706.13 706.31 706.48 706.66 706.83 707.01 707.18 707.36 707.53

3914+00 3915+00 3916+00 3917+00 3918+00 3919+00 3920+00 3921+00 3922+00 3923+00 3924+00 3925+00 3926+00 3927+00 3928+00

Geo Services, Inc.
Geotechnical, Environmental & Civil Engineering
805 Amherst Court, Suite 204
Naperville, Illinois 60565
(630) 355-2838

USER NAME =		DESIGNED - RWC		REVISED -	
		DRAWN - RWC		REVISED -	
PLOT SCALE =		CHECKED - AJP		REVISED -	
PLOT DATE =		DATE - 3/24/2011		REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SOIL BORING
PLAN / PROFILE ILLINOIS ROUTE 59

SCALE: | SHEET NO. OF SHEETS | STA. 3914+00 | TO STA. 3928+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338/IL 59	~~(12 & 13) WRS-5~~	DUPAGE	1156	879
		CONTRACT NO. 60R30		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		