THE CONTRACTOR SHALL CALL THE ELECTRICAL
FIELD OFFICE AT (708) 524-2145 FOR AN ELECTRICAL
MAINTEMANCE TRANSFER 7 DAYS PRIOR TO THE START
GENERAL NOTES OF ANY WORK.

- 1. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E."
  AT 800-892-0123 OR 811 FOR FIELD LOCATIONS, BURIED ELECTRIC LINES,
  TELEPHONE AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED).
- 2. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES. THE CITY OF NAPERVILLE AND NAPERVILLE TOWNSHIP.
- THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
- 4. THE CONTRACTOR SHOULD BE AWARE THAT CONTRACTS 60R30 AND 60131 ARE DIRECTLY ADJACENT TO THIS CONTRACT AND SOME WORK MAY RUN CONCURRENTLY WITH THIS CONTRACT. THE CONTRACTORS SHALL COORDINATE ALL CONSTRUCTION ACTIVITIES WITH THE ADJACENT CONTRACTS.
- 5. WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL CAREFULLY PRESERVE ALL PROPERTY MARKERS AND MONUMENTS UNTIL THE OWNER, AN AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED EACH LOCATION.
- 6. THE LOCATIONS OF EXISTING UTILITIES SHOWN ON THE PLANS ARE BASED ON FIELD INVESTIGATIONS AND BEST INFORMATION AVAILABLE, BUT THEY ARE NOT GUARANTEED. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO ASCERTAIN THEIR EXACT LOCATIONS FROM THE UTILITY COMPANIES AND BY FIELD INSPECTION.
- 7. THE CONTRACTOR SHALL TAKE CARE IN REMOVING OR EXCAVATING NEAR ALL EXISTING ITEMS WHICH WILL REMAIN. ANY DAMAGE DONE TO EXISTING ITEMS BY THE CONTRACTOR SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
- 8. THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS, AS REQUIRED, PRIOR TO COMMENCING WITH CONSTRUCTION. ANY COST ASSOCIATED WITH OBTAINING THESE PERMITS SHALL BE CONSIDERED INCLUDED IN THE CONTRACT UNIT PRICE FOR THE ITEMS BEING INSTALLED.
- 9. POLLUTION CONTROL: THE CONTRACTOR SHALL BE REQUIRED TO COMPLY WITH STATE REGULATIONS REGARDING AIR, WATER AND NOISE POLLUTION. THIS WORK WILL NOT BE PAID FOR SEPARATELY AND SHALL BE CONSIDERED INCLUDED IN THE COST OF THE CONTRACT.
- 10. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING DRAINAGE THROUGHOUT THE CONSTRUCTION OF THIS PROJECT. THIS WORK WILL NOT BE PAID FOR SEPARATELY AND SHALL BE CONSIDERED INCLUDED IN THE COST OF THE CONTRACT.
- 11. FOR WORK OUTSIDE THE LIMITS-OF BRIDGE APPROACH PAVEMENT, ALL REFERENCES
  IN THE HIGHWAY STANDARDS AND STANDARD SPECIFICATIONS FOR REINFORCEMENT;

  DOWEL DARS AND TIE BARS IN PAVEMENT, SHOULDERS, GURB, GUTTER, GOMBINATION
  CURB AND OUTTER AND MEDIAN, AND CHAIR SUPPORTS FOR CRC PAVEMENT, SHALL
  BE FOXY COATED, UNLESS NOTED ON THE PLAN.
- 12. FOR STORM SEWER CONSTRUCTED UNDER THE ROADWAY, BACKFILLING METHODS TWO AND THREE SPECIFIED UNDER THE PROVISIONS OF ARTICLE 550.07 OF THE STANDARD SPECIFICATIONS WILL NOT BE ALLOWED.
- 13. THE CONTRACTOR WILL BE REQUIRED TO RELOCATE OR REMOVE AND REPLACE ALL ROAD SIGNS WHICH INTERFERE WITH CONSTRUCTION OPERATIONS AND TO TEMPORARILY RESET ALL SUCH SIGNS DURING ALL STAGES OF CONSTRUCTION. THIS WORK SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR TRAFFIC CONTROL AND PROTECTION, (SPECIAL).

  ALL WORK INVOLVING SIGNS SHALL BE GOVERNED BY THE FOLLOWING:
  - A. SIGNS SHALL NOT BE REMOVED UNTIL NECESSITATED BY THE PROGRESS OF THE WORK.
  - B. EVERY SIGN REMOVED MUST BE RE-ERECTED AT A TEMPORARY LOCATION IN A WORKMANLIKE MANNER AND VISIBLE TO THE TRAFFIC FOR WHICH IT IS INTENDED.

    ALL SIGNS MUST BE MAINTAINED STRAIGHT AND CLEAN FOR THE DURATION OF THE TEMPORARY SETTING.
  - C. ALL UNUSED SIGNS SHALL BE RETURNED TO APPROPRIATE GOVERNING BODY AS DIRECTED BY THE ENGINEER.

- 14. THE CONTRACTOR SHALL CONTACT THE ARTERIAL TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING ANY WORK.
- 15. NO WORK SHALL COMMENCE UNTIL TRAFFIC CONTROL REQUIREMENTS ARE MET.
- 16. THE RESIDENT ENGINEER SHALL CONTACT DON CHIARUGI AT IDOT (847) 741-9857 A MINIMUM OF 2 WEEKS PRIOR TO PLACEMENT OF PERMANENT PAVEMENT MARKINGS.
- 17. DURING CONSTRUCTION OPERATIONS, WHENEVER LOOSE MATERIAL IS DEPOSITED IN THE FLOW LINE OF GUTTERS, DRAINAGE STRUCTURES, DITCHES, ETC., SUCH THAT THE NATURAL FLOW LINE OF WATER IS OBSTRUCTED, THE LOOSE MATERIAL SHALL BE REMOVED AT THE CLOSE OF EACH WORKING DAY. AT THE CONCLUSION OF THE CONSTRUCTION OPERATIONS, ALL DRAINAGE STRUCTURES AND FLOW LINES SHALL BE FREE FROM DIRT AND DEBRIS. THE CONTRACTORS FAILURE TO PROVIDE THE ABOVE WILL PRECLUDE ANY POSSIBLE ADDED COMPENSATION REQUESTED DUE TO DELAYS OR UNSUITABLE MATERIAL CREATED AS A RESULT THERE OF.
- 18. THE COST OF SAW CUTTING, (FULL DEPTH) SHALL BE INCLUDED IN THE UNIT PRICES FOR THE VARIOUS REMOVAL PAY ITEMS.
- 9. ITEMS OCCUPYING NEWLY ACQUIRED PARCELS SHALL BE CLEARED BY OTHERS. THESE ITEMS ARE NOT SHOWN ON THE PLANS. THE CONTRACTOR IS TO CONFIRM WITH THE ENGINEER THAT THIS WORK HAS BEEN COMPLETED PRIOR TO STARTING ANY OPERATION ON THE NEWLY ACQUIRED PARCEL.
- 20. FIRE HYDRANTS TO BE REMOVED SHALL BE SALVAGED AND RETURNED TO THE CITY OF NAPERVILLE. THE CONTRACTOR IS TO CONTACT THE DEPARTMENT OF PUBLIC UTILITIES AT (630)305-5937 AND COORDINATE THEIR RETURN. THIS WORK WILL NOT BE PAIDFOR SEPARATELY, BUT SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR FIRE HYDRANTS TO BE REMOVED.
- 21. THE CONTRACTOR SHALL REMOVE SAPLINGS WHERE INDICATED ON THE PLANS.
  THIS WORK SHALL NOT BE PAID FOR SEPARATELY, BUT IS CONSIDERED CLEARING.
  SEE SSRBC ARTICLE 201.01, 201.02 & 201.10 FOR ADDITIONAL INFORMATION.
- 22. THE CONTRACTOR'S ATTENTION IS CALLED TO THE FACT THAT THE PRESERVATION OF EXISTING TREES IS OF UTMOST IMPORTANCE TO THE CITY OF NAPERVILLE. ALL TREE PROTECTION, TREE REMOVAL, PRUNING AND ROOT PRUNING SHALL BE COMPLETED BEFORE CONSTRUCTION OPERATIONS COMMENCE IN ANY AREA. AT NO TIME SHALL THE CONTRACTOR PRUNE OR REMOVE ANY TREES UNLESS SPECIFICALLY DIRECTED BY THE ENGINEER.
- 23. THE CONTRACTOR SHALL TAKE EXTRA CARE IN GRADING AND EXCAVATING NEAR TREES WHICH ARE NOT MARKED FOR REMOVAL SO AS NOT TO CAUSE INJURY TO THE ROOT SYSTEM OR TRUNKS. MAJOR ROOTS OF A TREE THAT ARE TO REMAIN IN PLACE EXTENDING INTO THE EXCAVATION AREAS AT AN ELEVATION THAT WOULD INTERFERE WITH ANY PORTION OF THE PLANNED CONSTRUCTION SHALL BE SEVERED AT A POINT IMMEDIATELY OUTSIDE OF THE EXCAVATION AREA IN A MANNER THAT WILL CAUSE THE LEAST AMOUNT OF SYSTEMIC TO THE REMAINING TREE STRUCTURE. ANY DAMAGE DONE TO EXISTING ITEMS BY THE CONTRACTOR SHALL BE REPAIRED BY THE CONTRACTOR AT THE CONTRACTOR'S OWN EXPENSE.
- 24. THE CONTRACTOR SHALL ERECT A TEMPORARY FENCE AROUND ALL TREES WITHIN THE CONSTRUCTION AREA TO ETABLISH A "TREE PROTECTION ZONE" AND AROUND EXISTING WETLANDS TO ESTABLISH A "WETLAND PROTECTION ZONE" BEFORE ANY WORK BEGINS OR ANY MATERIAL IS DELIVERED TO THE JOBSITE. NO WORK IS TO BE PERFORMED (OTHER THAN ROOT PRUNING), MATERIALS STORED OR VEHICLES DRIVEN OR PARKED WITHIN THE "TREE PROTECTION ZONE" AND "WETLAND PROTECTION ZONE". REMOVE PROTECTIVE TEMPORARY FENCE ONLY AFTER ALL CONSTRUCTION WORK HAS BEEN COMPLETED.
- 25. THE CONTRACTOR SHALL ATTACH AN ALUMINUM SIGN WITH THE FOLLOWING TEXT: PROTECTED WETLAND NO INTRUSION. THESIGN(S) SHALL BE ATTACHED TO THE STAKES BY A METHOD APPROVED BY THE ENGINEER. THE SIGN(S) WILL BE PROVIDED BY THE DEPARTMENT AND SHALL BE PICKED UP BY THE CONTRACTOR FROM THE DISTRICT ONE ROADSIDE DEVELOPMENT ARCHITECT IN SCHAUMBURG, ILLINOIS. SCHEDULING THE PICKUP OF THE SIGNS CAN BE ARRANGED BY CONTACTING THE DISTRICT ONE ROADSIDE DEVELOPMENT UNIT AT (847) 705-4171. WHEN WORK HAS BEEN COMPLETED, THE SIGN SHALL BE RETURNED TO THE DISTRICT ONE ROADSIDE DEVELOPMENT UNIT. THE COST OF PICKING UP. ATTACHING THE SIGNS TO THE TEMPORARY FENCE STAKES AND RETURNING THE SIGNS WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR TEMPORARY FENCE.
- 26. AN ENGINEER'S FIELD OFFICE IS NOT INCLUDED IN THIS CONTRACT. THE ENGINEER SHALL UTILIZE THE ENGINEER'S FIELD OFFICE INCLUDED IN CONTRACTS 60P41 AND 60I31 FOR THIS CONTRACT.

## COMMITMENTS

NONE.

HOT-MIX ASPHALT MIXTURE REQUIREMENTS					
MIXTURE TYPE	AIR VOI				
HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 12" - BROOKDALE RD, DEARBORN C					
HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 (IL-9,5 mm); 2"	4% <b>c</b> 50 G				
HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50; 10"	4% <b>Q</b> 50 G				
HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 14" - DIEHL ROAD					
POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90 (IL-9.5 mm); 2"	4% ₽ 90 G				
POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90; 2-1/4"	4% @ 90 G				
HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90; 9-3/4"	4% <b>e</b> 90 G				
PAVEMENT RESURFACING - BROOKDALE ROAD					
HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 (IL-9.5 mm); 2"	4% <b>c</b> 50 G				
LEVELING BINDER (MACHINE METHOD) NSO, (IL 9.5 mm); 3/4"	4% <b>c</b> 50 G				
PAVEMENT RESURFACING - DIEHL ROAD					
POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90 (IL-9.5 mm); 2"	4% <b>c</b> 90 G				
LEVELING BINDER (MACHINE METHOD) N70, (IL 9.5 mm); 3/4"	4% <b>c</b> 70 G				
TEMPORARY PAVEMENT					
HOT-MIX ASPHALT SURFACE COURSE, MIX "D", NSO (IL-9.5 mm); 2"	4% <b>c</b> 50 G				
HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50; 10"	4% @ 50 G				
TEMPORARY ACCESS (WINTERIZE)					
HOT-MIX ASPHALT SURFACE COURSE, MIX "O", N50 (IL-9.5 mm); 2"	4% <b>o</b> 50 G				
HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 8"					
HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 (IL-9.5 mm); 2"	4% <b>c</b> 50 G				
HOT-MIX ASPHALT BASE COURSE (HMA BINDER IL-19 mm); 6"	4% <b>e</b> 50 G				
HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 10"					
HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 (IL-9.5 mm); 2"	4% <b>c</b> 50 G				
HOT-MIX ASPHALT BASE COURSE (HMA BINDER IL-19 mm); 8"	4% <b>c</b> 50 G				
CLASS D PATCHES, TYPE IV, 12"					
CLASS D PATCHES (HMA BINDER IL-19 mm) 12"	4% <b>c</b> 70 G				
CLASS D PATCHES, TYPE III, 15" (SPECIAL)					
HOT-MIX ASPHALT SURFACE COURSE, MIX D, N70 (IL-9.5 mm); 2"	4% <b>©</b> 70 G				
CLASS D PATCHES (HMA BINDER IL-19 mm) 13"	4% <b>c</b> 70 G				
HOT-MIX ASPHALT STABILIZATION, 5"					
HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50, 5"	4% <b>c</b> 50 G				

THE UNIT WEIGHT USED TO CALCULATE ALL HMA SURFACE MIXTURE QUANTITIES IS 112 LBS/SQ YD/IN.

THE AC TYPE FOR POLYMERIZED MIXES SHALL BE "SBS / SBR PG 76-22" AND FOR NON-POLYMERIZED HMA THE "AC TYPE" SHALL BE "PG 64-22" UNLESS MODIFIED BY DISTRICT ONE SPECIAL PROVISIONS,

FOR USE OF RECYCLED MATERIALS SEE DISTRICT ONE SPECIAL PROVISIONS.

TO STA.

PCC TEMPORARY PAVEMENT SHALL CONSIST OF 12" OF CLASS PV CONCRETE MEETING THE REQUIREMENTS OF ARTICLE 1020 OF THE STANDARD SPECIFICATIONS.

TEMPORARY PAVEMENT (VARIABLE DEPTH)

HOT-MIX ASPHALT SURFACE COURSE, 4°1. @ 50Gyr

MIX "O", N 50 (IL-

 <u> </u>				
	DESIGNED	PJÖ	REVISED	
	DRAWN	KES	REVISED	
	CHECKED	JCM	REVISED	-
	DATE	12/14/2012	REVISED	-

## STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: ANDINEOWN SHEET NO. 1 OF 1 SHEETS STA.