

**INDEX OF SHEETS**




1. COVER
2. INDEX OF SHEETS, GENERAL NOTES, AND HIGHWAY STANDARDS
3. SUMMARY OF QUANTITIES
4. TYPICAL SECTIONS

**HIGHWAY STANDARDS**

- 701001-02
- 701006-04
- 701201-04
- 701301-04
- 701306-03
- 701311-03
- 701901-02
- 780001-03

**GENERAL NOTES**

1. ANY REFERENCE TO THE STANDARDS THROUGHOUT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS INCLUDED IN THE PLANS.
2. NO EXCAVATION IS ANTICIPATED ON THIS PROJECT. SHOULD ANY EXCAVATION BE REQUIRED, J.U.L.I.E. SHALL BE NOTIFIED A MINIMUM OF 48 HOURS IN ADVANCE (800) 892-0123.
3. THE CONTRACTOR SHALL GIVE I.D.O.T. OPERATIONS TWO WEEKS NOTICE PRIOR TO STARTING WORK IN ORDER FOR I.D.O.T. TO COMPLETE PATCHING AND R.R.P.M. COVERING.
4. THE AGGREGATE FOR THE MICROSURFACING SHALL MEET THE FRICTION AGGREGATE REQUIREMENTS FOR MIXTURE "C" IN ARTICLE 1009.03(a).
5. THE AGGREGATE GRADATION FOR THE A-1 BITUMINOUS SURFACE TREATMENT SHALL BE CA-16 OR CA-20.
6. AGGREGATE FOR THE A-1 BITUMINOUS SURFACE TREATMENT SHALL BE CRUSHED LIMESTONE.
7. SHORT-TERM PAVEMENT MARKING SHALL BE PAINT - TAPE WILL NOT BE ALLOWED.

<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS DISTRICT 6</b>			
EXAMINED	3/27	20	13
	 ENGINEER OF OPERATIONS		
EXAMINED	MARCH 15	20	13
	 ENGINEER OF PROJECT IMPLEMENTATION		
EXAMINED	March 18	20	13
	 ENGINEER OF PROGRAM DEVELOPMENT		

FILE NAME *	USER NAME * #USERS	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, HIGHWAY STANDARDS AND GENERAL NOTES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILES		DRAWN -	REVISED -			1615	1231-3	SANGAMON	4	2
		CHECKED -	REVISED -							
Default		DATE -	REVISED -		SCALE: _____ SHEET 1 OF 1 SHEETS STA. _____ TO STA. _____					CONTRACT NO. T2012KXK
										ILLINOIS FED. AID PROJECT