## GENERAL NOTES

THE REFLECTIVE LENS OF ALL RAISED REFLECTIVE PAVEMENT MARKERS IN CONFLICT WITH THE STAGE TRAFFIC CONTROL SHALL BE REMOVED AND PAID FOR AT THE CONTRACT UNIT PRICE EACH FOR RAISED REFLECTIVE PAVEMENT MARKERS, REFLECTOR REMOVAL.

MATERIAL EXCAVATED FROM MEDIAN SHALL BE STOCKPILED AND REPLACED AT COMPLETION OF STAGE CONSTRUCTION WORK. COST OF EXCAVATION, STOCKPILING, AND REPLACEMENT OF EXCAVATED MATERIAL SHALL BE INCLUDED IN THE UNIT PRICE FOR PORTLAND CEMENT CONCRETE BASE COURSE 9".

FIELD MARKINGS OF UNDERGROUND UTILITIES IN CRITICAL AREAS MAY BE OBTAINED BY PROVIDING A MINIMUM OF 96 HOURS ADVANCE NOTICE THROUGH THE J. U. L. I. E. SYSTEM BY CALLING 800-892-0123.

THE TOTAL QUANTITY OF PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4" CONSISTS OF 625 FEET OF WHITE AND 500 FEET OF YELLOW.

THE TOTAL QUANTITY OF RAISED REFLECTIVE PAVEMENT MARKERS IS 8 ONE-WAY CRYSTAL.

## INDEX OF SHEETS

16-32 STRUCTURAL SHEETS

SHEET NO TITLE

1 COVER SHEET
2 GENERAL NOTES. INDEX OF SHEETS, LIST OF STANDARDS
3-4 SUMMARY OF QUANTITIES
5 SCHEDULES
6 STAGING TYPICAL
7-8 STAGE 1 CONSTRUCTION DETAILS
9-10 STAGE 2 CONSTRUCTION DETAILS
11 BICYCLE RAILING
12-15 TYPICAL APPLICATIONS OF PAVEMENT MARKING

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED FOLLOWING THE LAST NUMBERED SHEET OF THE PLANS.

000001-06	STANDARD SYMBOLS, ABBREVIATIONS. AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
420001-07	PAVEMENT JOINTS
606001-05	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
606301-04	PC CONCRETE ISLANDS AND MEDIANS
701101-03	OFF-ROAD OPERATIONS, MULTILANE, 15' TO 24" FROM PAVEMENT EDGE
701426-05	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPERATION, FOR SPEEDS >= 45 MPH
701606-08	URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
701901-02	TRAFFIC CONTROL DEVICES
780001-03	TYPICAL PAVEMENT MARKINGS
781001-03	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS
	·

TO STA.

SECTION

CONTRACT NO. 74615

	FILE NAME <	USER HARE I staffensk	DESIGNED -	REVISED -		GENERAL NOTES &				EC 8.		
-	st\pw,wo-k\pwidot\eteffenmk\d0187065\07	4615-shi-gennote.dgn	DRAWN -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION							
1	-	PLOT SCALE * 100,0000 1/ in.	CHECKED -	REVISED -		INDEX OF SHEETS						
l	Defoult	PLOT DATE > 3/28/2013	DATE -	REVISED -		SCALE:	SHEET	0F	SHEETS	STA.		
								,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		-,		