

SIDEWALK REMOVAL SCHEDULE		
LOCATION	SIDE	SIDEWALK REMOVAL (SQ FT)
IL RTE 159		
166+40.13 TO 166+80.52	RT	352.5
167+65.00 TO 168+69.36	LT	779.4
167+65.00 TO 176+74.47	RT	6127.8
168+83.54 TO 170+25.46	LT	1131.3
170+57.70 TO 170+98.20	LT	345.2
175+79.46 TO 176+90.62	LT	770.3
177+20.72 TO 182+62.75	RT	3098.3
177+36.33 TO 177+61.06	LT	281.5
177+79.09 TO 180+57.14	LT	1952.4
180+69.21 TO 180+80.55	LT	35.7
181+08.61 TO 183+30.95	LT	1711.9
182+98.94 TO 184+44.02	RT	805.7
184+08.42 TO 184+43.63	LT	176.5
184+62.66 TO 185+04.25	RT	187.5
184+67.62 TO 186+03.42	LT	913.7
185+39.52 TO 185+77.18	RT	170.6
186+11.84 TO 186+64.44	RT	300.2
186+31.77 TO 187+69.77	LT	940.6
187+00.14 TO 190+84.24	RT	2436.8
187+96.67 TO 188+92.25	LT	461.3
189+19.99 TO 190+08.18	LT	437.9
190+38.05 TO 190+56.91	LT	91.5
190+71.85 TO 192+23.24	LT	1120.2
191+40.02 TO 193+18.26	RT	961.2
192+57.72 TO 194+11.52	LT	1366.1
193+37.87 TO 196+71.88	RT	2000.3
194+26.79 TO 195+02.57	LT	435.4
194+84.87 TO 194+87.76	LT	6.9
195+41.75 TO 195+82.04	LT	450.9
196+14.24 TO 197+29.47	LT	529.7
196+83.03 TO 198+05.92	RT	927.9
197+36.26 TO 199+38.02	LT	1271.0
198+38.28 TO 198+50.94	RT	114.3
198+56.32 TO 199+88.82	RT	745.4
199+71.37 TO 201+60.26	LT	1001.8
200+04.25 TO 200+57.16	RT	324.5
200+88.41 TO 201+50.47	RT	411.0
201+75.48 TO 202+93.81	LT	653.3
201+81.94 TO 203+65.52	RT	964.1
203+02.69 TO 203+64.05	LT	321.6
203+53.54 TO 203+60.28	LT	15.7
203+92.60 TO 204+79.54	RT	415.6
204+00.73 TO 205+52.02	LT	960.7
204+93.05 TO 207+12.66	RT	1176.1
205+47.20 TO 205+52.31	LT	16.9
205+67.60 TO 207+21.13	LT	910.5
207+61.54 TO 218+84.04	LT	5657.4
207+62.27 TO 210+13.07	RT	1410.9
209+06.54 TO 209+18.35	LT	214.7
210+34.35 TO 212+67.82	RT	1341.4
213+14.09 TO 214+77.56	RT	750.7
214+06.39 TO 214+16.34	RT	30.6
215+18.01 TO 217+38.90	RT	1192.8
217+80.73 TO 218+66.61	RT	416.4
218+79.78 TO 219+84.97	RT	500.6
219+27.85 TO 223+69.95	LT	2023.3
219+99.83 TO 221+34.88	RT	773.9
222+20.43 TO 222+40.68	RT	72.4
222+69.39 TO 223+50.15	RT	320.1
223+80.80 TO 223+94.40	RT	49.9
223+98.14 TO 224+76.19	LT	382.1
224+14.70 TO 224+42.94	RT	110.2
224+79.56 TO 225+90.46	RT	434.7
225+07.41 TO 226+85.89	LT	722.0
226+32.62 TO 228+21.13	RT	860.7
227+16.10 TO 227+68.87	LT	212.4
227+95.93 TO 231+95.42	LT	1576.8
228+49.23 TO 229+73.75	RT	551.4
230+06.15 TO 231+84.79	RT	895.7
232+19.47 TO 236+38.71	RT	1972.9
232+93.43 TO 234+11.13	LT	467.0
234+36.15 TO 236+20.09	LT	726.2
236+38.19 TO 236+46.06	LT	32.1
236+70.35 TO 236+84.72	RT	166.3
SUBTOTAL (1)		64475.2

SIDEWALK REMOVAL SCHEDULE (CONT'D)		
LOCATION	SIDE	SIDEWALK REMOVAL (SQ FT)
WICKLIFFE AVE		
57+76.98 TO 59+44.69	RT	1355.9
58+00.00 TO 58+94.30	LT	413.6
60+10.73 TO 61+38.84	RT	533.1
60+72.99 TO 60+93.38	LT	117.6
61+11.27 TO 61+23.67	LT	77.4
61+46.77 TO 61+54.33	LT	34.0
61+71.74 TO 62+00.00	LT	107.5
61+83.16 TO 62+00.00	RT	60.3
SPRING ST		
80+51.15 TO 82+25.00	LT	728.0
80+80.04 TO 82+25.00	RT	609.8
81+13.47 TO 81+17.31	RT	11.7
AUTUMN AVE		
90+24.08 TO 91+06.88	LT	385.7
90+69.77 TO 91+64.39	RT	424.5
TILLOTSON AVE		
3+28.13 TO 4+32.50	RT	462.3
ALLEY @ 201+69.24		
0+85.43 TO 1+14.58	LT	76.1
HIGH SCHOOL AVE		
0+25.00 TO 0+90.00	RT	638.8
UNION AVE		
1+08.24 TO 1+09.73	RT	4.3
WILSON AVE		
100+40.98 TO 100+87.94	LT	185.7
SUBTOTAL (2)		6226.3
SUBTOTAL (1)		64475.2
SUBTOTAL (2)		6226.3
TOTAL		70701.5

GUARDRAIL REMOVAL SCHEDULE		
LOCATION	SIDE	GUARDRAIL REMOVAL (FT)
IL RTE 159		
176+52.56 TO 176+78.49	LT	28.7
INDIANA AVE		
0+12.07 TO 0+28.37	RT	16.3
0+32.21 TO 0+60.82	RT	28.6
ALLEY 223+94		
0+24.55 TO 0+58.43	RT	34.4
TOTAL		108

MEDIAN REMOVAL SCHEDULE		
LOCATION	SIDE	MEDIAN REMOVAL (SQ FT)
WICKLIFFE AVE		
LT		110
TOTAL		110

PAVEMENT REMOVAL SCHEDULE		
LOCATION	PAVEMENT REMOVAL (SQ YD)	
IL RTE 159		
167+65 TO 169+50	830	
169+50 TO 174+50	2232	
174+50 TO 179+50	2424	
179+50 TO 184+00	2005	
184+00 TO 189+50	2460	
189+50 TO 195+00	2459	
195+00 TO 200+50	2452	
200+50 TO 206+00	2451	
206+00 TO 212+00	2661	
212+00 TO 218+00	2653	
218+00 TO 223+50	2456	
223+50 TO 229+50	1821	
229+50 TO 235+00	311	
235+100 TO 236+48	82	
E JOHNSON ST		
ALLEY 168+75	132	
E MADISON AVE	622	
ALLEY 172+00	131	
E WICKLIFFE AVE/KEEBLER AVE		
VALLEY AVE	244	
VALLEY LN	196	
E PARK AVE	911	
SPRING ST	542	
ALLEY 190+65	163	
AUTUMN AVE	522	
BROWN AVE	225	
ALLEY 193+03	112	
ALLEY 194+20	106	
WADSWORTH ST	179	
ALLEY 196+76	64	
DELEVAN	172	
REBECCA AVE	298	
ALLEY 199+96	62	
TILLOTSON AVE	330	
ALLEY 201+69	166	
MARY AVE	246	
ALLEY 205+61	120	
HIGH SCHOOL AVE	383	
HIGH SCHOOL ST	266	
UNION AVE	404	
WILSON AVE	204	
INDIANA AVE	530	
ALLEY 223+94	164	
ILLINOIS AVE	419	
MEADOW LN	199	
CALIFORNIA AVE	252	
CLAREMONT CT	126	
MOUNDS AVE	111	
CUMBERLAND AVE	141	
TEMPORARY PAVEMENT REMOVAL		
178+07 TO 186+00	711	
186+39 TO 187+69	42	
188+65 TO 192+14	92	
197+76 TO 199+24	38	
199+86 TO 201+52	40	
209+39 TO 214+39	129	
TOTAL		39333

DRIVEWAY PAVEMENT REMOVAL SCHEDULE			
LOCATION	SIDE	TYPE	DRIVEWAY PAVEMENT REMOVAL (SQ YD)
IL RTE 159			
164+25	LT	CONC	11
168+65	RT	CONC	19
169+35	RT	CONC	23
169+83	RT	CONC	15
170+59	RT	CONC	20
171+31	RT	CONC	20
171+90	RT	CONC	20
173+00	RT	CONC/BIT	30
174+41 TO 174+74	RT	CONC/BIT	61
175+45	RT	CONC	27
175+91	LT	CONC	13
176+16	LT	CONC	11
176+39	LT	CONC	11
177+41 TO 178+73	LT	BIT	189
177+45 TO 177+85	LT	CONC	23
178+10	RT	BIT	3
178+32	RT	BIT	3
178+35	LT	CONC	12
178+73 TO 179+44	LT	CONC	404
179+12	RT	CONC	201
179+76	RT	CONC	129
180+62	LT	CONC	36
180+95	LT	CONC/BIT	212
183+34 TO 184+08	LT	CONC	300
183+56	RT	CONC	28
184+24 TO 185+41	LT	CONC	563
184+68 TO 185+59	RT	CONC/BIT	429
185+59 TO 186+89	RT	CONC/BIT	346
187+61	LT	CONC	27
187+84	LT	CONC	63
188+71 TO 191+38	RT	CONC/BIT	564
189+06	LT	CONC	52
190+22	LT	CONC/BIT	69
190+80 TO 192+24	LT	CONC/BIT	324
192+56 TO 193+70	LT	CONC/BIT	229
194+93	LT	CONC	29
195+00	RT	CONC	98
195+00 TO 195+42	LT	CONC/BIT	115
195+70 TO 195+82	LT	BIT	7
196+05	RT	CONC	64
196+73	LT	CONC	18
196+93	LT	CONC	11
197+33	LT	CONC	26
197+51	RT	CONC/BIT	40
198+30	LT	CONC	79
198+53	RT	CONC	22
200+40	LT	CONC	73
200+50 TO 201+46	RT	CONC/BIT	229
200+72	LT	CONC	23
202+97	LT	CONC	45
203+43 TO 204+98	RT	CONC/BIT	310
203+61	LT	CONC	36
210+04	LT	CONC/BIT	141
210+24	RT	CONC/BIT	74
212+89	RT	CONC	482
214+02	LT	CONC/BIT	333
214+16	RT	CONC	31
214+89	LT	CONC	48
215+76	RT	CONC	7
216+33	LT	BIT	85
216+90	LT	BRICK	59
217+59	RT	CONC/BIT	223
218+14	LT	BIT	73
218+53	RT	CONC/BIT	61
218+64 TO 220+38	RT	CONC/BIT	630
219+18 TO 220+27	LT	CONC/BIT	144
220+29 TO 220+83	LT	CONC	89
220+93	LT	CONC	71
220+98 TO 222+11	RT	BIT	335
222+25	LT	CONC/BIT	24
222+55	RT	CONC	59
222+96	LT	CONC/BIT	52
223+66	RT	CONC	52
223+84	LT	BIT	79
224+14 TO 225+89	RT	CONC/BIT	559
224+91	LT	CONC	105
226+33 TO 227+11	RT	CONC	233
227+01	LT	CONC	154
SUBTOTAL (1)			9914

DRIVEWAY PAVEMENT REMOVAL SCHEDULE (CONT'D)			
LOCATION	SIDE	TYPE	DRIVEWAY PAVEMENT REMOVAL (SQ YD)
IL RTE 159 (CONT'D)			
227+48 TO 227+87	RT	CONC	22
228+59	LT	CONC/BIT	63
229+26	LT	CONC	75
229+76	LT	CONC/BIT	48
229+85	RT	BIT	65
230+87	LT	CONC	29
231+44	LT	BIT	17
231+96 TO 233+29	LT	BIT	184
233+87	RT	CONC	32
233+89 TO 234+11	LT	BIT	37
234+29 TO 235+75	RT	BIT	33
234+40	RT	BIT	10
234+97	RT	CONC	11
235+64	RT	CONC	11
236+26	LT	BIT	35
236+74 TO 237+58	RT	CONC	144
ALLEY 168+75			
0+46 TO 1+00	LT	BIT	113
E MADISON AVE			
1+37	LT	CONC	17
1+97	RT	CONC	12
E WICKLIFFE AVE			
57+78 TO 58+74	RT	CONC	114
58+84	RT	BIT	28
60+54	LT	CONC	27
61+03	LT	CONC	14
61+35	LT	CONC	18
61+48	RT	CONC	26
VALLEY AVE			
0+96 TO 1+20	RT	BIT	47
E PARK AVE			
67+53	LT	BIT	147
67+56	RT	CONC	18
68+17	RT	CONC	47
68+27 TO 69+67	RT	BIT	114
SPRING ST			
81+10	RT	CONC/BIT	39
AUTUMN AVE			
90+90 TO 91+10	LT	CONC	8
ALLEY 193+03			
0+59	RT	CONC	157
ALLEY 194+20			
0+33 TO 0+86	RT	BIT	69
WADSWORTH ST			
0+60 TO 0+70	RT	BIT	7
REBECCA AVE			
0+43 TO 1+10	LT	BIT	151
ALLEY 201+69			
0+68 TO 0+92	RT	CONC/BRK	21
UNION AVE			
1+20	RT	CONC	42
1+47	LT	CONC/BIT	11
INDIANA AVE			
1+18	LT	CONC	34
1+48	RT	BIT	52
ILLINOIS AVE			
1+08	RT	CONC	44
SUBTOTAL (2)			2196
SUBTOTAL (1)			9914
SUBTOTAL (2)			2196
TOTAL			12110

FILE NAME =	USER NAME = default	DESIGNED -	REVISED -
P:\Projects\513501\CADD\DN\0876885-sh\schedule.dgn		DRAWN -	REVISED -