

TEMPORARY PAVEMENT SCHEDULE					
LOCATION	SIDE	AGGREGATE BASE COURSE, TYPE A 8" (ISO YD)	HMA SURFACE COURSE, MIX "D", N90, 1 1/2" (TON)	HMA BINDER COURSE, IL-19.0, N90, 9 1/4" (TON)	
IL RTE 159					
178+07 TO 186+00	LT	711.3	59.8	368.5	
186+39 TO 187+69	LT	42.0	3.5	21.8	
188+65 TO 192+14	LT	91.9	7.7	47.6	
197+76 TO 199+24	LT	38.1	3.2	19.7	
199+86 TO 201+52	LT	40.4	3.4	21.0	
209+39 TO 214+39	LT	129.4	10.9	67.1	
TOTAL		1054	89	546	

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL			
LOCATION	RAISED REFLECTIVE PAVEMENT MARKERS		
	ONE WAY CRYSTAL MARKER (EA)	TWO WAY AMBER MARKER (EA)	ONE WAY AMBER MARKER (EA)
IL 159			
160+00 TO 163+00	3		
163+00 TO 167+47	6	17	6
167+47 TO 175+20		39	
175+20 TO 176+58	3	4	
177+46 TO 179+50	2	3	5
179+50 TO 230+97		257	
230+97 TO 237+50	16	33	
JOHNSON STREET			
11+00 TO 12+77		3	
WICKLIFFE			
57+20 TO 59+60	2	5	
TOTAL		404	

TEMPORARY STRIPING SCHEDULE						
LOCATION	TEMPORARY PAVEMENT MARKING (FT)					
	4" LINE		8" LINE	12" LINE	24" LINE	LETTERS & SYMBOLS (SQ FT)
	SOLID WHITE	SOLID YELLOW	SOLID WHITE	SOLID WHITE	SOLID YELLOW	
STAGE 1	6,556	15,707			72	
STAGE 2	2,475	15,870			157	
STAGE 3	6,083	16,046			135	
STAGE 4	4,661	21,326	284	4,316	126	774
SUBTOTAL	19,775	68,949	284	4,316	490	774
TOTAL	88,724		284	4,806	774	1,195

TEMPORARY AGGREGATE SCHEDULE				
	LOCATION	SIDE	TYPE	AGGREGATE FOR TEMPORARY ACCESS (TONS)
	IL RTE 159			
ALLEY	168+75.37	LT	ALLEY	95.9
E MADISON AVE	170+41.27	LT	SIDE STREET	401.6
E WICKLIFFE AVE	177+03.00	LT	SIDE STREET	541.6
E WICKLIFFE AVE	177+03.00	RT	SIDE STREET	578.4
COMMERCIAL ENTRANCE	179+05.0	LT	CE	73.3
COMMERCIAL ENTRANCE	179+10.6	RT	CE	20.7
COMMERCIAL ENTRANCE	179+76.1	RT	CE	42.6
COMMERCIAL ENTRANCE	180+94.1	LT	CE	53.1
COMMERCIAL ENTRANCE	181+30.0	RT	CE	8.4
VALLEY AVE	182+76.85	RT	SIDE STREET	193.6
COMMERCIAL ENTRANCE	183+37.3	LT	CE	11.0
PRIVATE ENTRANCE	183+62.6	RT	PE	17.6
COMMERCIAL ENTRANCE	183+69.1	LT	CE	20.0
VALLEY LANE	184+29.54	RT	SIDE STREET	141.9
COMMERCIAL ENTRANCE	184+55.6	LT	CE	49.0
COMMERCIAL ENTRANCE	184+88.7	RT	CE	26.0
E PARK AVE	186+19.85	LT	SIDE STREET	1024.6
SPRING ST	186+46.85	RT	SIDE STREET	556.7
COMMERCIAL ENTRANCE	189+07.1	LT	CE	18.0
ALLEY	189+00.00	RT	ALLEY	115.3
COMMERCIAL ENTRANCE	190+03.2	LT	CE	24.6
COMMERCIAL ENTRANCE	190+48.6	RT	CE	22.3
ALLEY	190+65.00	LT	ALLEY	110.7
AUTUMN AVE	191+33.00	RT	SIDE STREET	313.1
COMMERCIAL ENTRANCE	191+63.0	LT	CE	18.2
BROWN AVE	192+43.24	LT	SIDE STREET	176.9
ALLEY	193+03.40	RT	ALLEY	148.8
COMMERCIAL ENTRANCE	193+42.20	LT	CE	29.0
ALLEY	194+02.09	LT	ALLEY	73.1
COMMERCIAL ENTRANCE	194+91.7	LT	CE	7.4
COMMERCIAL ENTRANCE	194+96.3	RT	CE	14.6
COMMERCIAL ENTRANCE	195+28.1	LT	CE	22.5
WADSWORTH ST	195+99.06	LT	SIDE STREET	111.8
COMMERCIAL ENTRANCE	196+04.7	RT	CE	13.9
ALLEY	196+76.00	RT	ALLEY	37.6
COMMERCIAL ENTRANCE	196+91.6	LT	CE	26.0
COMMERCIAL ENTRANCE	197+33.1	LT	CE	8.9
COMMERCIAL ENTRANCE	197+48.1	RT	CE	9.8
DELEVAN ST	198+25.00	RT	SIDE STREET	107.8
PRIVATE ENTRANCE	198+31.6	LT	PE	28.0
PRIVATE ENTRANCE	199+35.6	RT	PE	28.1
REBECCA AVE	199+56.98	LT	SIDE STREET	165.0
ALLEY	199+96.02	RT	ALLEY	33.8
PRIVATE ENTRANCE	200+39.0	LT	PE	38.2
COMMERCIAL ENTRANCE	200+70.0	RT	CE	16.5
PRIVATE ENTRANCE	200+70.9	LT	PE	7.0
TILLOTSON AVE	201+67.90	RT	SIDE STREET	286.4
ALLEY	201+69.24	LT	ALLEY	99.9
PRIVATE ENTRANCE	202+96.4	LT	PE	23.4
COMMERCIAL ENTRANCE	203+70.1	RT	CE	14.6
MARY AVE	203+86.94	LT	SIDE STREET	190.5
COMMERCIAL ENTRANCE	204+83.5	RT	CE	12.8
ALLEY	205+61.17	LT	ALLEY	69.9
HIGH SCHOOL AVE	207+41.56	LT	SIDE STREET	275.4
HIGH SCHOOL AVE	207+41.56	RT	SIDE STREET	153.8
COMMERCIAL ENTRANCE	210+15.9	LT	CE	50.4
COMMERCIAL ENTRANCE	210+24.5	RT	CE	19.0
COMMERCIAL ENTRANCE	212+93.3	RT	CE	72.2
COMMERCIAL ENTRANCE	214+01.5	LT	CE	49.9
PRIVATE ENTRANCE	214+12.0	RT	PE	8.5
COMMERCIAL ENTRANCE	214+89.3	LT	CE	38.1
UNION AVE	214+93.56	RT	SIDE STREET	268.9
PRIVATE ENTRANCE	215+80.9	RT	PE	38.0
PRIVATE ENTRANCE	216+36.5	LT	PE	36.4
PRIVATE ENTRANCE	216+90.0	LT	PE	40.5
COMMERCIAL ENTRANCE	217+61.80	RT	CE	45.2
PRIVATE ENTRANCE	217+91.4	LT	PE	23.9
COMMERCIAL ENTRANCE	218+19.4	LT	CE	21.9
COMMERCIAL ENTRANCE	218+54.8	RT	CE	3.3
COMMERCIAL ENTRANCE	218+68 - 219+72	RT	CE	125.4
WILSON AVE	219+10.87	LT	SIDE STREET	165.5
COMMERCIAL ENTRANCE	219+98.8	LT	CE	15.5
COMMERCIAL ENTRANCE	220+46.3	LT	CE	19.4
COMMERCIAL ENTRANCE	220+75.4	LT	CE	10.9
COMMERCIAL ENTRANCE	221+04.7	LT	CE	39.9
INDIANA AVE	221+84.70	RT	SIDE STREET	345.0
SUBTOTAL (1)				8147.5

TEMPORARY AGGREGATE SCHEDULE				
	LOCATION	SIDE	TYPE	AGGREGATE FOR TEMPORARY ACCESS (TONS)
COMMERCIAL ENTRANCE	222+26.3	LT	CE	11.7
COMMERCIAL ENTRANCE	222+97.1	LT	CE	22.6
COMMERCIAL ENTRANCE	223+84.3	LT	CE	24.7
ALLEY	223+94.02	LT	ALLEY	94.7
COMMERCIAL ENTRANCE	224+73.6	RT	CE	35.9
COMMERCIAL ENTRANCE	224+92.1	LT	CE	28.6
ILLINOIS AVE	225+96.25	RT	SIDE STREET	314.0
COMMERCIAL ENTRANCE	226+96.6	LT	CE	37.2
MEADOW LANE	227+90.00	LT	SIDE STREET	223.6
CALIFORNIA AVE	228+12.89	RT	SIDE STREET	212.4
COMMERCIAL ENTRANCE	228+64.0	LT	CE	22.7
COMMERCIAL ENTRANCE	229+22.0	LT	CE	23.7
COMMERCIAL ENTRANCE	229+79.0	LT	CE	19.3
COMMERCIAL ENTRANCE	229+93.6	RT	CE	15.2
COMMERCIAL ENTRANCE	230+88.8	LT	CE	13.2
COMMERCIAL ENTRANCE	231+45.7	LT	CE	4.1
CLAREMONT CT	232+02.02	RT	SIDE STREET	136.3
COMMERCIAL ENTRANCE	232+44.9	LT	CE	11.8
COMMERCIAL ENTRANCE	233+02.5	LT	CE	6.5
COMMERCIAL ENTRANCE	233+86.7	RT	CE	13.7
MOUNDS AVE	234+18.00	LT	SIDE STREET	118.5
COMMERCIAL ENTRANCE	234+41.6	RT	CE	9.1
COMMERCIAL ENTRANCE	234+97.2	RT	CE	9.1
COMMERCIAL ENTRANCE	235+60.3	RT	CE	9.3
COMMERCIAL ENTRANCE	236+28.5	LT	CE	12.1
CUMBERLAND AVE	236+50.00	RT	SIDE STREET	136.1
E MADISON AVE				
PRIVATE ENTRANCE	1+37.0	RT	PE	9.2
PRIVATE ENTRANCE	1+96.2	LT	PE	7.2
E WICKLIFFE AVE				
COMMERCIAL ENTRANCE	58+30.9	RT	CE	14.5
E PARK AVE				
PRIVATE ENTRANCE	66+80.9	RT	PE	33.7
PRIVATE ENTRANCE	67+35.7	RT	PE	24.7
COMMERCIAL ENTRANCE	67+52.6	LT	CE	29.6
PRIVATE ENTRANCE	67+56.2	RT	PE	15.0
COMMERCIAL ENTRANCE	68+16.6	RT	CE	10.1
SPRING ST				
COMMERCIAL ENTRANCE	80+84.6	RT	CE	36.5
PRIVATE ENTRANCE	81+11.3	RT	PE	26.2
PRIVATE ENTRANCE	82+10.5	RT	PE	16.2
AUTUMN AVE				
COMMERCIAL ENTRANCE	90+68.8	RT	CE	55.0
PRIVATE ENTRANCE	90+99.3	RT	PE	24.4
ALLEY 193+03.40				
COMMERCIAL ENTRANCE	0+62.6	RT	CE	28.0
TILLOTSON AVE				
COMMERCIAL ENTRANCE	0+65.6	RT	CE	18.0
UNION AVE				
PRIVATE ENTRANCE	1+19.3	RT	PE	26.5
PRIVATE ENTRANCE	1+46.9	LT	PE	7.8
WILSON AVE				
COMMERCIAL ENTRANCE	100+66.2	LT	CE	17.8
INDIANA AVE				
COMMERCIAL ENTRANCE	0+75.8	RT	CE	15.3
COMMERCIAL ENTRANCE	1+19.4	LT	CE	17.8
COMMERCIAL ENTRANCE	1+48.2	RT	CE	17.8
ALLEY 223+94				
COMMERCIAL ENTRANCE	0+48.7	RT	CE	13.4
ILLINOIS AVE				
COMMERCIAL ENTRANCE	1+08.1	RT	CE	14.6
COMMERCIAL ENTRANCE	1+09.3	RT	CE	18.9
SUBTOTAL (2)				2064.2
SUBTOTAL (1)				8147.5
SUBTOTAL (2)				2064.2
TOTALS				10212

TEMPORARY CONCRETE BARRIER (STAGE 2 CONSTRUCTION)		
LOCATION	TEMPORARY CONCRETE BARRIER (FOOT)	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2 (EACH)
IL 159		
167+83, LT		1
167+83 TO 175+95	812.5	
175+95, RT		1
177+97, RT		1
177+97 TO 182+10	412.5	
182+10, RT		1
183+58, RT		1
183+58 TO 184+08	50	
184+08, RT		1
185+20.50, RT		1
185+20.50 TO 185+83	62.5	
185+83, RT		1
188+29, RT		1
188+29 TO 188+41.50	12.5	
188+41.50, RT		1
189+65.50, RT		1
189+65.50 TO 190+78	112.5	
190+78, RT		1
192+34, RT		1
192+34 TO 192+84	50	
192+84, RT		1
194+05, RT		1
194+05 TO 196+30	225	
196+30, RT		1
197+21, RT		1
197+21 TO 197+58.50	37.5	
197+58.50, RT		1
199+04, RT		1
199+04 TO 199+54	50	
199+54, RT		1
200+33, RT		1
200+33 TO 200+95.50	62.5	
200+95.50, RT		1
202+43.50, RT		1
202+43.50 TO 206+56	412.5	
260+56		1
208+17.50, RT		1
208+17.50 TO 214+30	612.5	
214+30		1
215+76.50 LT		1
215+76.50 TO 220+24	450	
220+24, LT		1
222+97.50 LT		1
222+97.50 TO 223+60	62.5	
223+60, LT		1
224+61.50, LT		1
224+61.50 TO 225+49	87.5	
225+49, LT		1
TOTAL	3512.5	32

TEMPORARY CONCRETE BARRIER (STAGE 3 CONSTRUCTION)				
LOCATION	RELOCATE TEMPORARY CONCRETE BARRIER (FOOT)	TEMPORARY CONCRETE BARRIER (FOOT)	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2 (EACH)	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2 (EACH)
IL 159				
167+87, RT			1	
167+87 TO 168+49.50	62.5			
168+49.50, RT			1	
169+25, RT			1	
169+25 TO 169+62.50	37.5			
169+62.50, RT			1	
171+26, LT			1	
171+26 TO 176+26	500			
176+26, RT			1	
177+97, RT			1	
177+97 TO 185+22	725			
185+22, RT			1	
187+30, RT			1	
187+30 TO 190+17.50	287.5			
190+17.50, RT			1	
191+14, RT			1	
191+14 TO 191+64	50			
191+64, RT			1	
193+11, RT			1	
193+11 TO 193+73.50	62.5			
193+73.50, RT			1	
194+68, RT			1	
194+68 TO 195+43	75			
195+43, RT			1	
196+65.50, RT			1	
196+65.50 TO 199+03	237.5			
199+03, RT			1	
200+23, RT			1	
200+23 TO 201+23	100			
201+23, RT			1	
202+11, RT			1	
202+11 TO 203+11	100			
203+11, RT			1	
204+56, RT			1	
204+56 TO 205+18.5	62.5			
205+18.5, RT			1	
206+02, RT			1	
206+02 TO 206+64.50	62.5			
206+64.50, RT			1	
208+18,				