

LOCATION	WATER MAIN TO BE ABANDONED 14" (FT)	WATER MAIN TO BE ABANDONED 12" (FT)	WATER MAIN TO BE ABANDONED 10" (FT)	WATER MAIN TO BE ABANDONED 6" (FT)	WATER MAIN TO BE ABANDONED 4" (FT)	WATER MAIN TO BE ABANDONED 2" (FT)	FIRE HYDRANTS TO BE REMOVED (EA)	WATER METER TO BE REMOVED (EA)	SANITARY SEWER REMOVAL 12" (FT)	SANITARY SEWER REMOVAL 10" (FT)	SANITARY SEWER REMOVAL 8" (FT)	SANITARY MANHOLES TO BE REMOVED (EA)
HIGH SCHOOL AVE -0+15 TO 1+05 0+12 TO 1+01 0+37.44, 22.25 L		135			90							
UNION AVE -0+16 TO 1+48				25			1					
WILSON AVE 100+24 TO 100+79 100+43.86, 21.29 R				67			1					
ILLINOIS AVE -0+21 TO 0+77					100							
MEADOW AVE 0+00 TO 0+92				95								
CALIFORNIA AVE 0+00 TO 1+09				112								
SUBTOTAL (2)	0	135	0	299	355	0	2	0	0	0	0	0
SUBTOTAL (1)	850	3240	175	2692	6384	260	10	12	886	82	906	6
SUBTOTAL (2)	0	135	0	299	355	0	2	0	0	0	0	0
TOTALS	850	3375	175	2991	6739	260	12	12	886	82	906	6

NOTE:

THE REMOVAL OF A WATER METER ASSEMBLY WILL ONLY BE PAID IF THE METER ASSEMBLY IS NOT REPLACED. IF THE EXISTING METER ASSEMBLY IS TO BE REPLACED, THEN THE REMOVAL OF THE EXISTING WATER METER ASSEMBLY WILL BE INCIDENTAL TO THE COST OF INSTALLING THE NEW METER ASSEMBLY AND THEREFORE NO QUANTITIES WILL BE FOUND IN THE SUMMARY OF QUANTITIES FOR REMOVAL OF WATER METERS.

NOTE:

"WATER MAIN TO BE ABANDONED" WORK WILL CONSIST OF CUTTING AND CAPPING THE EXISTING WATER MAIN WITH PLACEMENT OF GROUT IN THE EXISTING MAINS WHICH ARE TO BE ABANDONED IN PLACE. ABANDONMENT OF EXISTING WATER MAINS SHALL BE IN ACCORDANCE WITH THE "STANDARD SPECIFICATIONS FOR WATER & SEWER MAIN CONSTRUCTION IN ILLINOIS"

SANITARY STRUCTURE SCHEDULE

LOCATION	STRUCTURE	DEPTH (FT)	MANHOLES, TYPE A, SANITARY, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID (EA)	ADJUSTING SANITARY SEWER SERVICE LINE (EA)	SANITARY MANHOLES TO BE ADJUSTED (EA)	SANITARY MANHOLES TO BE RECONSTRUCTED (EA)
IL RTE 159						
177+02.86, 42.83 L	SMH 1-4				1	
177+28.62, 5.08 R	SMH 3-1	15.5				1
177+69.04, 16.50 L	SMH A-1	15.6	1			
178+71.05, 0.00	SMH A-2	14.3	1			
182+19.32, 5.50 R	SMH A-3	14.1	1			
186+19.32, 5.50 R	SMH A-4	19.2	1			
186+19.60, 24.42 R	SMH 3-3	19.6				1
186+62.38, 23.84 R	SMH 3-4				1	
188+63.12, 22.57 R	SMH 3-5				1	
194+75.59, 21.55 R	SMH 3-7				1	
198+46.60, 23.37 R	SMH 3-8				1	
205+05.73, 22.35 R	SMH 3-10				1	
208+45.30, 22.61 R	SMH 3-11				1	
209+76.29, 22.10 R	SMH 3-12				1	
210+05.25, 23.09 R	SMH 3-13				1	
210+38.95, 36.06 R	SMH 3-14				1	
187+04.70, 22.43 L	SMH 4-1				1	
189+45.05, 22.91 L	SMH 4-2				1	
192+41.68, 21.15L	SMH 4-3				1	
195+97.92, 24.48 L	SMH 4-4				1	
198+46.70, 22.47 L	SMH 4-5				1	
199+54.37, 22.58 L	SMH 4-6				1	
203+83.14, 23.18L	SMH 4-7				1	
209+65.02, 23.46 L	SMH 4-9				1	
210+24.30, 24.01 L	SMH 4-10				1	
213+78.70, 26.95 R	SMH 5-1				1	
215+03.02, 24.73 R	SMH 5-2				1	
217+91.05, 18.22 R	SMH 5-3				1	
221+08.26, 13.43 R	SMH 5-4				1	
221+81.88, 12.24 R	SMH 5-6				1	
215+24.47, 32.19L	SMH 6-1				1	
219+01.75, 38.46 L	SMH 6-2				1	
TOTALS			4	114	26	2

SANITARY PIPE SCHEDULE

UPSTREAM MANHOLE	DOWNSTREAM MANHOLE	SANITARY SEWER 15"	PIPE CLASS	TRENCH BACKFILL (CY)
SMH A-1	SMH 3-1	41	SDR 35	81
SMH A-2	SMH A-1	100	SDR 35	181
SMH A-3	SMH A-2	348	SDR 35	562
SMH A-4	SMH A-3	400	SDR 35	817
SMH 3-3	SMH A-4	19	SDR 35	47
TOTALS		908		1688

FILE NAME =	USER NAME = default	DESIGNED -	REVISED -
P:\Projects\513501\CADD\DN\0876885-sht	schedule.dgn	DRAWN -	REVISED -
	PLOT SCALE = 40.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 3/6/2013	DATE - 01/25/2013	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: N/A SHEET NO. 25 OF 31 SHEETS STA. N/A TO STA. N/A

F.A.P. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
600	60-(30,31,128)-3	MADISON	529	59
CONTRACT NO. 76B85				
ILLINOIS FED. AID PROJECT				