

GENERAL NOTES

Utilizing U.S. Route 67 North as Plan North and \odot of Roadway, all references to North, South, East or West are from this designated North. Any references to Left or Right are from \odot U.S. Route 67.

All new structural steel shall conform to AASHTO Classification M-270 Gr. 36, unless otherwise noted.

No Field Welding is permitted except as specified in the contract documents.

Plan dimensions and details relative to existing plans are subject to nominal construction variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.

Cost of removal and re-installation of all members necessary to complete the repair work as detailed on the plans shall be included in the cost of the repair work.

Areas of deck repairs shown are observed estimates from June 2012. The Engineer will determine final patch locations and quantities in the field before deck slab repair operations begin. The Engineer shall show actual locations of deck repairs on As-built Plans.

All steel railing elements to be repaired, shall be galvanized according to Article 509.05 of the Standard Specifications.

All steel railing elements to be repaired, shall have the replacement materials according to the appropriate materials listed in Article 509.02 of the Standard Specifications.

INDEX of SHEETS

1. General Plan and Elevation
2. General Data
3. Concrete Stopewall Illinois Abutment
4. Deck Slab and Parapets Spans 1 and 2
5. Deck Slab and Parapets Spans 5 and 6
6. Deck Slab and Parapets Spans 7 and 8
7. Deck Slab and Parapets Span 9
8. Deck Slab and Parapets Span 10 (So. Half)
9. Deck Slab and Parapets Span 11
10. Deck Slab and Parapets Spans 12, 13 and 14
11. Deck Slab and Parapets Spans 15, 16 and 17
12. Deck Slab and Parapets Spans 21 and 22
13. Cable Stay Layout - Numbering Sequence
14. Cable Wrapping
15. Cable Stabilizer Details
16. South Abutment
17. North Abutment
18. Pier Number 1 - Cap
19. Pier Number 1 - Columns
20. Pier Number 2 - Cap
21. Pier Number 3 - Cap
22. Pier Number 3 - Columns
23. Pier Number 4 - Cap
24. Pier Number 4 - Columns
25. Pier Number 5 - Cap
26. Pier Number 6 - Cap
27. Pier Number 7 - Cap
28. Pier Number 8 - Cap
29. Pier Number 8 - Columns
30. Pier Number 9 - Missouri Pylon
31. Missouri Pylon - (436.50 to 476.25)
32. Missouri Pylon - (476.25 to 492.92)
33. Missouri Pylon - Head and Access Spaces
34. Pier Number 10 - Illinois Pylon
35. Illinois Pylon - Head and Access Spaces
36. Lt. End Block - Concrete End Beam - over Pier Number 11
37. Pier Number 11 - Cap
38. Pier Number 14 - Cap
39. Pier Number 14 - Columns
40. Pier Number 16 - Columns
41. Pier Number 17 - Cap
42. Pier Number 19 - Cap
43. Pier Number 19 - Columns
44. Pier Number 20 - Columns
45. Pier Number 21 - Cap
46. Pier Number 21 - Columns
47. Missouri Approach Slab
48. Illinois Approach Slab

TOTAL BILL OF MATERIAL

ITEM	UNIT	QUANTITY
Slope Wall 6 Inch	SQ. YD.	2
Concrete Sealer	SQ. FT.	10424
Epoxy Crack Injection	FOOT	98
Graffiti Removal	SQ. YD.	1332
Cleaning Bridge Scuppers and Downspouts	Each	7
Structural Repair of Concrete (Depth equal to or less than 5 inches)	SQ. FT.	27
Deck Slab Repair (Partial)	SQ. YD.	33
Polyurethane Sealant	FOOT	104
Cable Wrapping	L. SUM	1
Cable Stabilizer Repairs	L. SUM	1



© Copyright Hanson Professional Services Inc. 2012

12/22/2012 12:42:02 PM 12/22/2012 12:42:02 PM 12/22/2012 12:42:02 PM

DESIGNED -	EXAMINED _____ DATE _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL DATA STRUCTURE NO. 060-0255		F.A.P. RTE. 304	SECTION 100B-105-1	COUNTY MADISON	TOTAL SHEETS 58	SHEET NO. 12
CHECKED -	PASSED _____ ENGINEER OF STRUCTURAL SERVICES				SHEET NO. 02 OF 48 SHEETS		CONTRACT NO. 76E73		ILLINOIS FED. AID PROJECT
DRAWN Rod	ENGINEER OF BRIDGES AND STRUCTURES								
CHECKED MNM									