

PAVEMENT MARKING SCHEDULE
(CONT.)

STATION TO STATION				WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING - LINE 4"			WR THPL PAVT. MARK. - LINE 6"	WR THPL PAVT. MARK. - LINE 24"	WR THPL PAVT. MARK. - LTRS. & SYMB.
				4 INCH WHITE (EDGE LINE)	4 INCH YELLOW (NO PASS ZONE)	4 INCH (SKIP-DASH)	CROSSWALK	STOP BARS	
				FOOT	FOOT	FOOT	FOOT	FOOT	
RT	157+08.0	TO	149+64.0		744				
LT	141+46.0	TO	139+35.0		211				
RT	141+46.0	TO	132+75.0		871				
LT	132+75.0	TO	123+35.0		940				
RT	126+94.0	TO	122+19.0		475				
LT	116+43.0	TO	110+83.0		560				
RT	99+85.0	TO	90+87.0		898				
LT	88+23.0	TO	79+78.0		845				
RT	30+65.0	TO	22+04.5		861				
	165+21.0	TO	141+46.0			594			
	139+35.0	TO	126+94.0			310			
	123+35.0	TO	104+80.0			464			
	103+63.0	TO	22+04.5			2040			
RURAL SUB-TOTALS				108,461	25,548	12,358	0	29	0
Eq. Sta. 22+04.5 (ah.) = Sta. 1343+13.9 (bk.) (Urban Limits Begin) (SEE NOTE 1)									
RT	1343+13.9	TO	1340+71.7	242.2					
LT	1343+13.9		1340+71.7	242.2					
RT	1343+13.9	TO	1340+71.7		242				
	1343+13.9	TO	1340+71.7			61			
Eq. Sta. 1340+71.7 (ah.) = Sta. 1340+76.5 (bk.) (SEE NOTE 1)									
LT	1340+76.5	TO	1317+74.2	2,302					
RT	1340+76.5	TO	1327+23.0	1,354					
RT	1326+26.0	TO	1317+74.2	852					
RT	1326+72.0	(STOP BAR @ WYE)					20		
RT	1340+76.0		1317+79.2		2297				
LT	1339+45.0		1317+79.2		2166				
RT	1340+76.5	TO	1339+45.0			33			
Eq. Sta. 1317+74.2 (ah.) = Sta. 1317+95.9 (bk.) (SEE NOTE 1)									
LT	1316+25.0	(STOP BAR @ S. R.)					13		
LT	1316+00.0	TO	1307+48.0	852					
RT	1315+50.0	TO	1307+48.0	802					
LT	1307+48.0	TO	1293+64.0	1,384					
RT	1307+48.0	TO	1293+64.0	1,384					
RT	1296+84.0	(RR XING STOP BAR)					13		
RT	1296+59.0	(RRXING 2-R'S)						7.2	
RT	1296+59.0	(RRXING 1-X)						54.0	

NOTE 1: STATIONING IS DECREASING FROM WEST TO EAST. ALL MEASUREMENTS REFLECT THIS. THEREFORE LT. IS ON NORTH SIDE OF CENTERLINE AND RT. IS ON SOUTH SIDE OF CENTERLINE.

FILE NAME =	USER NAME = \$USER*	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVEMENT MARKING SCHEDULE (CONTINUED)	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pwwork\pwwork\mccordkr\033289\178351-sht-plan.dgn		DRAWN -	REVISED -			329	(19,18,17,103)RS-4	PERRY	34	14	
\$MODELNAME*	PLOT SCALE = 200.0000' / in.	CHECKED -	REVISED -			CONTRACT NO. 78351					
	PLOT DATE = 3/22/2013	DATE -	REVISED -			SCALE:	SHEET	OF	SHEETS	STA.	TO