

EXISTING STORM SEWER REMOVAL SCHEDULE
(REQUIRE IN-PLACE TRENCH BACKFILL)

UPSTREAM STATION	OFFSET	DIA. (IN)	LENGTH (FT)	T.B. (CY)
1313+65.86	63.15 LT	12	71	8.6
1315+06.79	66.50 LT	10	75	12.7
1316+63.86	71.19 LT	10	82	15.4
1318+54.58	81.21 LT	10	32.00	5.28
1318+79.60	61.82 LT	15	74	15.3
1318+87.86	66.53 LT	10	10	1.4
1320+81.01	75.48 LT	12	88	20.3
1326+19.05	61.00 LT	12	13	2.4
1326+19.05	61.00 LT	12	71	16.8
1331+44.55	68.68 LT	12	35.00	9.00
1334+97.96	70.45 LT	12	83	23.1
1335+27.54	60.50 LT	12	31	5.4
1336+30.93	60.50 LT	12	72	14.5
1337+82.31	52.43 LT	10	65	8.8
1339+44.98	46.55 LT	12	59.00	11.45
1339+92.86	71.1 LT	10	54.00	15.34
1347+73.79	88.34 LT	10	16	2.8
1349+70.85	70.99 LT	10	14	2.1
1349+80.64	61.34 LT	15	73	14.8
1350+16.22	72.51 LT	12	38	5.0
1352+25.64	68.97 LT	10	94	18.8
1356+84.86	71.33 LT	12	83	17.0
1358+64.96	96.55 LT	12	83.00	10.96
1363+74.39	69.95 LT	10	46	6.3
1364+20.17	68.59 LT	12	44	5.8
1366+06.46	60.97 LT	10	73	11.8
1366+68.45	7.03 RT	12	33	5.4
1366+61.32	60.00 LT	12	88	14.3

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94 (DAN RYAN EXPRESSWAY)

EXISTING STORM SEWER
REMOVAL SCHEDULE

SCALE: NONE DRAWN BY: MB
DATE: MARCH 1, 2006 CHECKED BY: DA