

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN TOTAL	URBAN - 90% FEDERAL, 10% STATE					STRUCTURAL - IM			
				IM DAN RYAN J000-2A	IM DAN RYAN I000-2A	IM LIGHTING Y030-1E	IM SIGNING Y002-1C	IM SIGNING Y002-1C	Y007 WALL C	X771-2A	S881-2A	SNO16-2852
31102300	SUB-BASE GRANULAR MATERIAL, TYPE C 6"	SQ YD	828.0								828	
35300720	PORTLAND CEMENT CONCRETE BASE COURSE 13"	SQ YD	754		754							
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	9.1	0.2	8.9							
40600300	AGGREGATE (PRIMECOAT)	TON	46	1	45							
40600895	CONSTRUCTING TEST STRIP	EACH	2		2							
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	56		56							
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	2757	2757								
42001300	PROTECTIVE COAT	SQ YD	195,113	191,629	3484							
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	391							391		
42100380	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 14"	SQ YD	127554	100,145			27,409					
42101426	LUG SYSTEM COMPLETE 26'	EACH	3	3								
42101436	LUG SYSTEM COMPLETE 36'	EACH	1	1								
44000004	BITUMINOUS SURFACE REMOVAL 1"	SQ YD	17684	17684								
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	3107	147	2960							
44000011	BITUMINOUS SURFACE REMOVAL 4"	SQ YD	6733		6733							
44000100	PAVEMENT REMOVAL	SQ YD	120,254	120,254								
44000106	BITUMINOUS REMOVAL OVER PATCHES 1 1/2"	SQ YD	669		669							
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	17884	15337	2547							
44001980	CONCRETE BARRIER REMOVAL	FOOT	13112	12192	920							
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	4918	4918								
44004250	PAVED SHOULDER REMOVAL	SQ YD	42464	24,561	2478		15,425					
44004260	PAVED SHOULDER REMOVAL (SPECIAL)	SQ YD	2044	2044								
44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	4372	4372								
44201427	CLASS C PATCHES, TYPE II, 16 INCH	SQ YD	134		134							
44201431	CLASS C PATCHES, TYPE III, 16 INCH	SQ YD	148		148							
44201433	CLASS C PATCHES, TYPE IV, 16 INCH	SQ YD	422		422							
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	11,709	11,709								
48101200	AGGREGATE SHOULDERS, TYPE B	TON	379	379								
48300400	PORTLAND CEMENT CONCRETE SHOULDERS 9"	SQ YD	325		325							
48300800	PORTLAND CEMENT CONCRETE SHOULDERS 13"	SQ YD	912		912							
50100200	REMOVAL OF EXISTING STRUCTURES	L SUM	1							1		
50102400	CONCRETE REMOVAL	CU YD	29	2			12	5			10	
50200100	STRUCTURE EXCAVATION	CU YD	5950	616				861			4473	
50300150	NEOPRENE EXPANSION JOINT 2"	FOOT	242								242	

- * - SPECIALTY ITEM
- - IDOT PAY CODE SFTY-3N
- ⊙ - NON-PARTICIPATING

TYLIN INTERNATIONAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94 (DAN RYAN EXPRESSWAY)

SUMMARY OF QUANTITIES
SHEET 2 OF 9

SCALE: NONE
DATE: MARCH 7, 2006
DRAWN BY: RTM
CHECKED BY: MPG

Rev. 5-11-06

Rev.