

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94		COOK	916	16
STA. 190+65 (NB I-57) TO STA. 2316+00 (NB RYAN)				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
• (1516.1, 1717, & 1818) R-4				
				62304

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN TOTAL	URBAN - 90% FEDERAL, 10% STATE						
				FM DAN RYAN J000-2A	FM DAN RYAN I000-2A	FM LIGHTING Y030-1E	FM I.T.S. Y032-1F	STRUCTURAL-IM	Y007 WALL C	
X3540580	PORTLAND CEMENT IN GROUT	CU FT	800	800						
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	261	13	248					
X4066550	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N105	TON	1248	38	1210					
X4066660	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19, N105	TON	892		892.0					
X4409400	BITUMINOUS SURFACE REMOVAL 1 3/4"	SQ YD	5249	391	4858					
X4834090	PORTLAND CEMENT CONCRETE SHOULDERS 14"	SQ YD	35370	35370						
X6061001	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.48	FOOT	2896.0	2896.0						
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	12017.0	9791.0	2226.0					
X6370910	CONCRETE BARRIER, SINGLE FACE, 32 INCH HEIGHT	FOOT	13677	12898	779					
X6370912	CONCRETE BARRIER, SINGLE FACE, 32 INCH HEIGHT, SPECIAL	FOOT	238		238					
X6370925	CONCRETE BARRIER, SINGLE FACE, 42" (SPECIAL)	FOOT	7994	7994						
X6370935	CONCRETE BARRIER, SINGLE FACE, 32" (MODIFIED)	FOOT	882	882						
X6370940	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	20	20						
X6640210	TEMPORARY CHAIN LINK FENCE (PORTABLE)	FOOT	1885	1885						
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	24	24						
X0325416	TRAFFIC CONTROL AND PROTECTION FOR DETOUR ROUTE	L SUM	1	1						
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1						
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	457	457						
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	160	160						
XX001854	STABILIZED SUB-BASE, 6"	SQ YD	175338	147,929			27,409			
XX004200	PORTLAND CEMENT CONCRETE PAVEMENT 14" (JOINTED)	SQ YD	1239	1239						
XX004201	PAVEMENT REINFORCEMENT, 14"	SQ YD	127554	100,145			27,409			
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	872						872	
Z0002400	BALLAST	TON	1890	1890						
Z0002600	BAR SPLICERS	EACH	1028					1028		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.8	0.2					
Z0013825	CONTROLLED LOW STRENGTH MATERIAL	CU YD	503	327	176					
Z0018800	DRAINAGE SYSTEM	L SUM	1					1		
Z0022800	FENCE REMOVAL	FOOT	477						477	
Z0029300	GROUT REPAIR	FOOT	515						515	
Z0032700	KEYWAY REPAIR	FOOT	500						500	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	12	11	1					
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	34	28	6					
Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	43,100	43,100						
Z0041300	PROTECTIVE SHIELD	SQ YD	445					445		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	0.8	0.2					
Z0056220	SAND MODULE IMPACT ATTENUATOR TO BE REMOVED	EACH	11	11						
Z0068400	STEEL CASINGS, 42"	FOOT	45	45						
Z0076600	TRAINERS	HOUR	1500	1500						

* - SPECIALTY ITEM
 □ - IDOT PAY CODE SFTY-3N
 ○ - NON-PARTICIPATING

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 94 (DAN RYAN EXPRESSWAY)
 SUMMARY OF QUANTITIES
 SHEET 9 OF 9
 SCALE: NONE
 DATE: MARCH 7, 2006
 DRAWN BY: RTM
 CHECKED BY: MPG

TYLIN INTERNATIONAL

Rev. 5-11-06