

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN TOTAL	URBAN - 90% FEDERAL, 10% STATE						
				PCC PAVEMENT J000-2A	BITUMINOUS PAVEMENT I000-2A	LIGHTING Y030-1E	I.T.S. Y032-1F	SIGNING Y002-1C	STRUCTURAL-SFTY-2A SNO16-0143, 0144, 0145	SNO16-0073
X0320870	BRACED EXCAVATION	CU YD	954	751	203					
X0321866	REMOVE, STORE AND RE-ERECT SIGN PANEL	SQ FT	525					525		
X0322194	POLYMER MODIFIED PORTLAND CEMENT MORTAR	SQ FT	27						27	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	1509	128				1381		
X0322671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	3360	3360						
* X0322859	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	16	16						
* X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	42	42						
* X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	16599	11737	4862					
* X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	4150	2934	1216					
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	11932	11932						
X0324112	BARRIER BASE	FOOT	17253	15660	1593					
* X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	9028	9028						
* X0324469	CONDUIT ENCASED, REINFORCED CONCRETE, 2 - 4" DIA., CNC	FOOT	78			78				
* X0324471	CONDUIT ENCASED, REINFORCED CONCRETE, 4 - 4" DIA., CNC	FOOT	243			243				
* X0324646	CONDUIT ENCASED, REINFORCED CONCRETE, 6 - 4" DIA., CNC	FOOT	1605			1605				
X0324697	SOIL STABILIZERS	POUND	221000	221000						
X0324698	APPLYING DUST SUPPRESSION AGENT	UNIT	107	107						
* X0324980	CONDUIT ENCASED, REINFORCED CONCRETE, 3 - 4" DIA., CNC AND 1-2" DIA., CNC 2 WIDE X 2 HIGH	FOOT	97			97				
X0325082	CTA BARRIER REMOVAL	FOOT	9199	9199						
X0325083	CTA FENCE	FOOT	8280	8280						
X0325084	CTA GATES	EACH	9	9						
* X0325130	TUBULAR TRAFFIC SIGN POST	EACH	1					1		
X0712400	TEMPORARY PAVEMENT	SQ YD	11173	9719	1454					
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	652	25	627					
X4066550	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N105	TON	1690	43	1647					
X4066660	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19, N105	TON	1332		1332					
X4409400	BITUMINOUS SURFACE REMOVAL 1 3/4"	SQ YD	8621	436	8185					
X4834090	PORTLAND CEMENT CONCRETE SHOULDERS 14"	SQ YD	29133	29133						
X6022120	MANHOLES, DROP TYPE, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	2	1					
X6022130	MANHOLES, DROP TYPE, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	1	1					
X6061001	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.48	FOOT	1833.0	1833.0						
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	13251.5	9612.5	3639.0					

- * - SPECIALTY ITEM
- - IDOT PAY CODE SFTY-3N
- △ - IDOT PAY CODE Y080.
- ⊙ - NON-PARTICIPATING

TYLIN INTERNATIONAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94 (DAN RYAN EXPRESSWAY)

**SUMMARY OF QUANTITIES
SHEET 7 OF 8**

SCALE: NONE DRAWN BY: MPG
DATE: MARCH 1, 2006 CHECKED BY: TGB