

URBAN

PAYCODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITIES	90% FED. 10% STATE 0021 COOK	90% FED. 10% STATE 0021 DUPAGE
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	40	40	
20200100	EARTH EXCAVATION	CU YD	71	19	52
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	20	5	15
20400800	FURNISHED EXCAVATION	CU YD	23		23
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	104	104	
25000310	SEEDING, CLASS 4	ACRE	0.73	0.18	0.55
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	66	16	50
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	66	16	50
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	66	16	50
25100630	EROSION CONTROL BLANKET	SQ YD	3526	863	2663
25200110	SODDING, SALT TOLERANT	SQ YD	104	104	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	315	77	238
44003100	MEDIAN REMOVAL	SO FT	1209		1209
44004250	PAVED SHOULDER REMOVAL	SQ YD	89	36	53
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	400	66	334
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	261	53	208
60250200	CATCH BASINS TO BE ADJUSTED	EACH	1	1	
60608521	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.24	FOOT	322	84	238
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	501	88	413
63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	25		25
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	6	1	5
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	17	4	13
63200310	GUARDRAIL REMOVAL	FOOT	2783	485	2298
66400305	CHAIN LINK FENCE, 6'	FOOT	50	50	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	1.5	4.5
67100100	MOBILIZATION	LSUM	1	0.25	0.75
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	LSUM	1	0.20	0.80
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	LSUM	1	0.25	0.75


URBAN

PAYCODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITIES	90% FED. 10% STATE 0021 COOK	90% FED. 10% STATE 0021 DUPAGE
78200410	GUARDRAIL MARKERS, TYPE A	EACH	34	7	27
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	23	5	18
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	LSUM	1	0.67	0.33
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	24	9	15
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	286	52	234
Z0062002	SAW CUTTING, (FULL DEPTH)	FOOT	238		238
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	100	25	75
* 66900450	SPECIAL WASTE PLANS AND REPORTS	LSUM	1	0.25	0.75
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	11	3	8
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	LSUM	1		1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	LSUM	1		1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	LSUM	1		1

* SPECIALTY ITEM

Rev. 5-25-2016

FILE NAME: P:\2016\ME1027 - New York - PH11\6213 - Terminal Updates\CD03\SHS\MS\6213-Int-500.dgn
 PLOT SCALE: 24000 / in.
 USER NAME: Millennium Professional Services



2400 Warrville Road, Suite 203, Downers Grove, IL 60515
 630.785.8110 voice, 630.539.2566 fax
 www.mps-il.com
MILLENNIA PROFESSIONAL SERVICES

DESIGNED - AA	REVISED -
DRAWN - JP	REVISED -
CHECKED - TVN	REVISED -
DATE - 3/31/2016	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

VARIOUS LOCATIONS IN COOK AND DUPAGE COUNTIES
 SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2016-005GRR	COOK/DUPAGE	23	3
*VARIOUS			CONTRACT NO. 62C13	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				