



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 1, 2016

SUBJECT: FAU Route 9701 (OLD IL 13)
Section 12(1-2)
Jackson County
Contract No. 78463
Item No. 146, June 10, 2016 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 5 of the Special Provisions
2. Revised sheet 12 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Maureen M. Addis, P.E.
Acting Engineer of Design and Environment

A handwritten signature in black ink, appearing to read "Ted B. Walschleger" followed by a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Jeffrey L. Keirn, Region 5, District 9; Tim Kell; Estimates

CWR/ck

TWO WEEK NOTIFICATION PRIOR TO STARTING WORK

Effective December 2005

Revise the first sentence of Article 107.09 Public Convenience and Safety to the following "The Contractor shall notify the Engineer at least 14 days in advance of starting any construction work. For projects involving width or height restrictions or complete closures of the roadway or ramp, an additional 7 days of notice (21 days total) will be required."

This additional notification is required so that the public can be notified of the pending construction.

SIGN STRUCTURE

This work consists of furnishing and placing of the new Sign Structure. The sign will be made from the strongest-grade high-density polyethylene with 2 separate colors, one for surface of sign and one for the engraved lettering, which shall appear on both sides of sign. The surface of the sign shall be colored to match the granite façade on the north entrance of the Illinois Department of Transportation District 9 building. The engraved lettering shall be colored white. The lettering shall be state-of-the-art engraving revealing the second color. The sign will have UV inhibitors. The posts will be brushed stainless steel and will be surface mounted to the concrete foundation with brushed stainless steel surface mounts as shown on the plans, the manufactures instructions and as directed by the Engineer.

A color artist rendering of the sign (11X17) and a sample of the sign material with some lettering shall be submitted to the Engineer for approval prior to ordering the sign. The materials and lettering used in the construction of the sample shall be in accordance with all standards and instructions as listed in the project specifications and plans. The minimum size of the sample shall be 1 foot x 1 foot or of sufficient size to insure the color matches the building facade.

The furnishing and placing of the sign, the metal posts, surface mount bases, all hardware to install the sign on the concrete foundation and color sample shall be paid at the contract Lump Sum price for SIGN STRUCTURE.

The Illinois Department of Transportation Logo and font are standardized. The Resident Engineer will provide the Illinois Department of Transportation logo and lettering information.

Revised 6-1-16